



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22 *13562-72*
To

Dated *10-01-2022*

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:- Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in Email: ee-nir-hp@nic.in



Phone No.-01904-255140
Fax No. 01904-255740

NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **19.01.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **18.01.2022** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money (in Rupees)	Time	Cost of tender form Rs.
1	Construction of Rest House building (Additional Accommodation) at Anni in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authoprity etc complete).	98000.00	2000	Three months	350/-
2	Construction of Sub Treasury building at Anni in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same	98000.00	2000	Three months	350/-

	from competent authority etc complete).				
3	Construction of Primary Health Centre building at Kungash in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).	98000.00	2000	Three months	350/-
4	Construction of Primary Health Centre building at Jaon in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).	148000.00	3000	Three months	350/-
5	Construction of Kalyan Bhawan building at Nirmand in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).	98000.00	2000	Three months	350/-
6	A/R & M/O Showad Karana road km. 0/00 to 15/600. (SH:- Maintenance of earthen shoulder and clearing and grubbing road land in km. 0/00 to 15/600)	399566.00	8000.00	One month	350/-
7	A/R & M/O various roads under Nirmand Sub-Division. (Binding of office record files of Division office with cardboard cover on both sides of files)	487500.00	10000	Two months	350/-
8	A/R & M/O Behna Dalash road km. 0/00 to 17/345 (SH:- C/O PCC retaining wall at RD. 5/711 to 5/715).	77394.00	2000	One month	350/-
9	A/R & M/O Showad Karana road km. 0/00 to 15/600 (SH:- P/L Kharanja stone soling in km. 15/580 to 15/800 at Bus Stand)	267207.00	6000	Two months	350/-
10	A/R & M/O Ranabag Karshaigad road km. 0/00 to 14/510. (SH:- Construction of P.C.C. retaining walls at RD. 9/720 to 9/740)	418324.00	10000	One month	350/-
11	A/R & M/O Khanag Shush Takrasi road km. 0/00 to 8/690. (SH:- C/O wire crate R/Wall at RD 1/340 to 1/355)	355686.00	8000.00	One month	350/-
12	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O wire crated R/Wall at RD. 18/700.20 to 18/702.70) near khad	302886.00	8000.00	One month	350/-
13	A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00. (SH:- Providing and laying metalling and tarring work to improve riding quality at RD 6/985 to 7/120)	417296.00	10000	Three months	350/-
14	A/R & M/O road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.3/585 to 3/592.50)	279976.00	6000	Two months	350/-

15	A/R & M/O various roads under Neether Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchra drain) Post rain.	350000.00	7000.00	One month	350/-
16	A/R & M/O Ranabag Karshaigad road km. 0/00 to 14/510. (SH:- Maintenance of earthen shoulder and clearing and grubbing road land in km. 0/00 to 10/500)	74420.00	2000.00	One month	350/-
17	Providing and laying metalling and tarring works on Ranabag Lagoti road km. 0/00 to 14/510 under BASP. (Sub Head:- Providing and laying WBM G-III at various RDs between 10/00)	199340.00	4000.00	One month	350/-
18	Restoration of rain damages on road from Sarahar to Khathaya km. 0/00 to 1/00 (SH:- Hiring of Excavator cum loader for removal of formation deficiency in km. 0/00 to 1/00)	475000.00	10000	One month	350/-
19	A/R & M/O various roads under Dalash Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and snow various roads under Dalash Sub-Division)	375000.00	8000.00	One month	350/-
20	Construction of Toilet Block at Neether under BASP (SH:- Levelling of ground and construction of B/Wall at RD.14/315 to 14/322.50 of Road from Jn. of LDCK to Jn. of NAS road)	486055.00	10000	Two months	350/-

HIM SUCHANA AVAM JAN SAMPARK


 Executive Engineer
 Outer Seraj Division
 H.P.P.W.D., Nirmal,
 on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740



Certificate

Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 13562-72 dated
10.01.2022 is very urgent nature. So may be uploaded on Departmental
website in public interest please.


**Executive Engineer
Outer Seraj Division
H.P.PWD, Nirmand**
on behalf of Governor of Himachal Pradesh

Schedule of quantity

Name of Work: Construction of Kalyan Bhawan at Nirmand in District Kullu (H.P.) (Sub Head:- Consultancy services for preparation of DPR including survey and investigation of site and preparation of working estimate including bidding documents and approval of the same from competent authority etc complete).						
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Consultancy services for preparation of working estimate as per HSPR 2020 dully supported with analysis of rates for all scheduled items and non scheduled item on market rates in all respect in manuscript form and submission the same to higher office for proper scrutiny/approval. If any correction/ amendments has desired by the higher office, the same may be corrected complete in all respect as desired competent authority or directed by the Engineer-in-Charge. After that the DPR should be submitted in five copies dully computerized along with soft copy complete in all respect including obtaining approval of the same from competent authority and preparation/approval of bidding documents complete.	1.000	One Job			98000.00
Total in Figures						2000
						Three months

22
Executive Engineer
Quarry Serai Division
HPWD, Nirmand

Condition for payment will be as under:-

- 1 On submission of manuscript copy to the Division office = 20%
- 2 On approval of the manuscript copy from the competent authority and submission of fair DPR in five copies alongwith soft copy of the same to Division office =30%
- 3 After approval of working estimate and bidding documents of the project from the competent authority. =50%
- 4 The rates are inclusive of all taxes including GST

Schedule of quantity						
Name of work:- A/R & M/O Showad Karana road km. 0/00 to 15/600. (SH:- Maintenance of earthen shoulder and clearing and grubbing road land in km. 0/00 to 15/600)				Estimated cost:- Rs. 399566.00 Earnest Money:- Rs. 8000.00 Time:- One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201 including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	34200	Per Square Metre			
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	18804.00	Square Metre			
Total in Figures						


 Executive Engineer
 Civil & Survey Division
 H.F. & W.D., Nilgiri

8

Schedule of quantity.						
Name of Work:- A/R & M/O Behna Dalash road km. 0/00 to 17/345 (SH:- C/O PCC retaining wall at RD. 5/711 to 5/785).				Estimated cost:- Earnest Money		
				Time		
				One month		
				AMOUNT		
SL No.	Description of work	Qty.	Unit	Figures	RATE	Words
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	4.40	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	11.68	Cubic Metre			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.16	Cubic Metre			
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	15.32	Cubic Metre			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.92	Cubic Metre			
Total in Figures						

Executive Engineer
 Outer Seral Division
 HPWD, Noida

Signature of Tenderer with seal

Schedule of quantity						
Name of Work: A/R & M/O Showad Karana road km. 0/00 to 15/600 (SH:- P/L Kharanja stone soling in km. 15/580 to 15/800 at Bus Stand)				Estimated cost:- Rs.267207.00 Earnest Mony:- Rs. 6000.00 Time :- Two months.		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	980.00	Square metre			
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub grade including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	980.00	Square metre			
3	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 150mm spread thickness(finished work including materials and labour) and as per directions of the Engineer-In-Charge including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	147.00	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Saraj Division
 HP/PWD, Demand

Signature of Tenderer with seal

Schedule of quantity

Schedule of quantity						
Name of Work:- A/R & M/O Ranabag Karshaigad road km. 0/00 to 14/510 . (SH:- Construction of P.C.C. retaining walls at RD. 9/720 to 9/740)				Estimated cost:- Earnest Money Time		418324.00 10000 One month
SL. No.	Description of work	Qty.	Unit	Figures	RATE	AMOUNT
				Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	14.00	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	25.20	Cubic Metre			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	8.60	Cubic Metre			
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	92.00	Cubic Metre			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.80	Cubic Metre			
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each			
Total in Figures						


 Executive Engineer
 Outer Saraj Division
 HPPWD, MIDLAND

Schedule of quantity									
Name of Work: A/R & M/O Khanag Shush Takrasi road km. 0/00 to 8/690. (SH:- C/O wire crate R/Wall at RD 1/340 to 1/355)				Estimated cost:- Earnest Money Time			355686.00		
							8000		
							One month		
							AMOUNT		
Sl. No.	Description of work	Qty.	Unit	RATE		Words	Figures	Cubic Metre	Cubic Metre
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	20.25	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	32.40	Cubic Metre						
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete.	135.00	Cubic Metre						
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	26.10	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Setai Division
 HPWD, Himmatnagar

Schedule of quantity

Schedule of quantity						
Name of Work: A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00 (SH:- C/O wire crated R/Wall at RD. 18/700.20 to 18/702.70) near khad				Estimated cost:-		
				Earnest Money		302886.00
				Time		8000
				One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	9.00	Cubic Metre			
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix 1:2:4 (one cement : two sand : four graded stone aggregate 20 mm (twenty millimetre) nominal size) in open foundations including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	25.38	Cubic Metre			
3	Providing mild / tor steel reinforcement for RCC work including bending, binding and placing in position complete up to all heights including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	0.27	Tonne			
4	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS:280 and I.S.4826 in 100mmx100mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stones boulders of approved quality weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 complete including carriage of materials in all leads and lifts as per direction of Engineer-in-Charge complete	44.93	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Seral Division
 HPPWD, Mandla

SCHEDULE OF QUANTITY						
Name of work:-A/R & M/O Wazir Bowali to Mohali road km. 0/00 to 26/00. (SH:- Providing and laying metalling and tarring work to improve riding quality at RD 6/985 to 7/120)						
				Estimated Cost:-417296.00		
				Earnest money:- 10000.00		
				Time:- Three months		
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading I as per Technical Specification Clause 404 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	54.68	Per Cubic Metre			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per Technical Specification Clause 405 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	39.49	Per Cubic Metre			
3	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per Technical Specification Clause 405, including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	37.97	Per Cubic Metre			
4	Providing and applying priming coat with bitumen emulsion (SS-1) using bitumen distributor at the rate of 0.85 kg. (Zero point eight five Kilogramme) per square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications clause of 502 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	506.25	Per Square Metre			
5	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion pressure distributor @ 0.275 kg (Zero point two seven five Kilogramme) per square metre of the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specifications of clause 503 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	506.25	Per Square Metre			
6	Providing and laying 30 mm (thirty millimetre) thick bituminous concrete with 100-120 PH batch type hotmix plant producing and average output of 75 tonne (Seventy five tonne) using crushed aggregates of specified grading premixed with bituminous binder @ 5.5 (Five point five) percent or mix and filler including addition Zycotherm @ 0.10 % (zero point ten percent) of weight of bitumen, transporting the hot mix to work site lying with a hydro static paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem roller to achieve the desired compaction as per MORTH specification No. 50 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Birumen will be supplied by the department free of cost)	15.19	Per Cubic Metre			


 Executive Engineer
 Outer Seral Division
 HPWD, Ahmednagar

14

Schedule of quantity									
Name of Work: A/R & M/O road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (Sub Head:- Construction of R/Wall at RD.3/585 to 3/592.50)									
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		Estimated cost:-		Two months AMOUNT
					Words	Time	Earnest Money		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	19.88	Cubic Metre						279976.00
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	20.63	Cubic Metre						6000.00
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.00	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	32.75	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	30.55	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.85	Cubic Metre						
Total in Figures									


 Executive Engineer
 Outer Sanction Division
 HPRWD, Noida

Signature of Tenderer with seal

SCHEDULE OF QUANTITY

Name of work :- A/R & M/O various roads under Neelher Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and construction of road side kutchha drain) Post rain.

Estimated Cost Rs. 350000/-
Earnest Money Rs. 7000/-
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	280.00			Per Hour	
					Total	


 Executive Engineer
 Outer Seral Division
 HPPWD, Pimpri

Schedule of quantity						
Name of work:- A/R & M/O Ranabag Karshaigad road km. 0/00 to 14/510. (SH:- Maintenance of earthen shoulder and clearing and grubbing road land in km. 0/00 to 10/500)				Estimated cost:- Rs. 74220.00 Earnest Money:- Rs. 2000.00 Time:- One month		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Clearing and grubbing road land including uprooting wild vegetation, grass, bushes, shrubs, saplings and trees of girth upto 300 mm, removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, upto a lead of 1000 m including removal and disposal of top organic soil not exceeding 150 mm in thickness as per Technical Specification Clause 201 including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	7400	Per Square Metre			
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	2877.00	Square Metre			
		Total in Figures				


 Executive Engineer
 Civil & Survey Division
 HPPWD, Mumbai

17

Schedule of Quantity						
Name of work:- Providing and laying metalling and tarring works on Ranabag Lagoti road km. 0/00 to 14/510 under BASP. (Sub Head:- Providing and laying WBM G-III at various RDs between 10/00)				Estimated cost:- Rs. 199340.00		
				Earnest Money:- Rs. 4000.00		
				Time:- One month		
Sr. No.	Description of work	Qty.	Unit	Figures	Rate	AMOUNT
					Words	
1	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 405, Grade-III A. By manual Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	78.36	Per Cubic Metre			
Total in Figures						


 Executive Engineer,
 Outer Serai Division,
 HPWD, Jalandhar.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on road from Sarahar to Khathaya km. 0/00 to 1/00 .
(SH:- Hiring of Excavator cum loader for removal of formation deficiency in km. 0/0 to 1/00)

Estimated Cost Rs. 475000/-
Earnest Money Rs. 10000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of formation deficiency at various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	380.00			Per Hour	
					Total	


Executive Engineer
Outer Sarai Division
HPPWD, Noida

Name of work :- A/R & M/O various roads under Dalash Sub-Division. (SH:- Hiring of Excavator cum loader for removal of slips and snow of various roads under Dalash Sub-Division)

SCHEDULE OF QUANTITY

Estimated Cost Rs. 375000/-
Earnest Money Rs. 8000/-

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for removal of slips and snow from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	300.00			Per Hour	
					Total	

Executive Engineer
Outer S&S Division
H&S&W Division

Schedule of quantity

Name of Work:- Construction of Toilet Block at Neether. (SH:- Levelling of ground and construction of B/Wall at RD.14/322.50 of Road from Jn. of LDCK to Jn. of NAS road) <i>under B&D.</i>		Estimated cost:- Earnest Money Time		486055.00 10000.00 Two months	
Sl. No.	Description of work	Qty.	Unit	Figures	Words
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 34.58 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	345.75	Cubic Metre		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	21.75	Cubic Metre		
3	Providing and Laying cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) and curing complete including the cost of farmwork for plain/reinforced concrete in retaining walls, breast walls, as per drawing and HP.PWD technical specifications including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	84.62	Cubic Metre		
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	30.00	Each		
Total in Figures					

RW
Executive Engineer
Outer Saraj Division
HPPWD, Noida