

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22
To

13802-12

Dated 21-01-2022

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.


Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740



NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **28.01.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **27.01.2022** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF** failing which no tender form will be issued to him.

Work No.:-1 Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MMGSY. (SH: Formation cutting 5/7 mtr wide road in Km. 0/175 to 0/330) Estimated cost: Rs. 4,89,020 /- Earnest money Rs.:- 10,000/- time three Months Cost of form:-350/-

Work No.:-2 Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MMGSY. (SH: Formation cutting 5/7 mtr wide road in Km. 1/360 to 1/480) Estimated cost: Rs. 4,89,440 /- Earnest money Rs.:- 10,000/- time three Months Cost of form:-350/-

Work No.:-3 A/R & M/O Wazir Bowali Mohali road km 0/00 to 26/00 (SH:- C/O R/Wall at RD. 25/270 to 25/285).Estimated cost: Rs. 4,95,637 /- Earnest money Rs.:- 10,000/- time two Months Cost of form:-350/-

Work No.:-4 Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MMGSY. (SH: Formation cutting 5/7 mtr wide road in Km. 0/330 to 0/705). Estimated cost: Rs. 4,94,984 /- Earnest money Rs.:- 10,000/- time three Months Cost of form:-350/-


Work No.:-5 A/R & M/O various roads under Brow Sub-Division. (SH: Supplying and stacking of dual directional delineators at Brow). Estimated cost: Rs. 4,75,000 /- Earnest money Rs.:- 10,000/- time one Month Cost of form:-350/-

Work No.:-6 Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MMGSY. (SH: Formation cutting 5/7 mtr wide road in Km. 1/480 to 1/645) Estimated cost: Rs. 4,78,516 /- Earnest money Rs.:- 10,000/- time three Months Cost of form:-350/-

Work No.:-7 Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MMGSY. (SH: Formation cutting 5/7 mtr wide road in Km. 1/645 to 1/975) Estimated cost: Rs. 4,74,032 /- Earnest money Rs.:- 10,000/- time three Months Cost of form:-350/-

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand
on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140
Fax No. 01904-255740

“A”Certificate

Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 13802-12 dated
21.01.2022 is very urgent nature. So may be uploaded on Departmental
website in public interest please.

**Executive Engineer
Outer Seraj Division
H.P PWD, Nirmand**

on behalf of Governor of Himachal Pradesh

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MMGSY. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/330 to 0/705)

Estimated cost:-
494984.00
Earnest Money
10000

Time
Three months
AMOUNT

Sl. No.	Description of work	Qty.	Unit	RATE	
				Figures	Words
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 278 84 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2545.95	Cubic Metre		
Total in Figures					

22
Executive Engineer,
Outer Seal Division
HPPWD, Himachal

Schedule of quantity						
Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MMGSY. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/360 to 1/480)				Estimated cost:-		489440.00
				Earnest Money		10000
				Time		Three months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 278.78 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2007.30	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Semi Division
 HPPWD, Mumbai

Schedule of quantity

Schedule of quantity							
Name of Work: A/R & M/O Wazir Bowali Mohali road km 0/00 to 26/00 (SH:- C/O R/Wall at RD. 25/270 to 25/285)							
				Estimated cost:-		495637.00	
				Earnest Money		10000.00	
				Time		Two months	
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	AMOUNT	
					Words		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	36.00	Cubic Metre				
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	34.95	Cubic Metre				
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	10.80	Cubic Metre				
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	95.05	Cubic Metre				
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.82	Cubic Metre				
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each				
Total in Figures							


 Executive Engineer
 Outer Survey Division

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MMGSY. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/330 to 0/705)				Estimated cost:- Earnest Money		494984.00
				Time		10000
				Three months		
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract of achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 278.84 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2545.95	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Seraj Division
 HPPWD, Jammu

Schedule of Quantity

Name of work: - A/R & M/O various roads under Brow Sub-Division. (SH:-Supplying and stacking of dual directional delineators at Brow.)

Estimated cost:- 475000.00

Earnest money:- 10000.00

Time:- One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Supplying and stacking of dual directional delinator made of dia 18 gauge M.S. rectangular pipe of size 25x68 mm and of length 600 mm pipe stove enamelled and baket to 120 c/powder coated.Head made of ABS plastic rectangular moulded with flat face provided with high tensity presmastic reflectors of colour (white/yellow/red) of size 100x125 mm with additional to reflective strips of 25mm wide make greens/ lite including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	500 Nos.	Each			



Executive Engineer,
Outer Seeraj Division,
HP.P.W.D. Nirmand.

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MMGSY. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/480 to 1/645)					Estimated cost:-		478516.00	
					Earnest Money		10000	
					Time		Three months	
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT	
					Words			
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 271.74 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on porta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2099.40	Cubic Metre					
Total in Figures								


 Executive Engineer
 Outer Survey Division
 HPPWD, Thiruvananthapuram

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MMGSY. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/645 to 1/975)					Estimated cost:-	
					Earnest Money	10000
					Time	Three months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 270.27 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1897.80	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Survey Division
 U.P.P.W.D. Varanasi