

Himachal Pradesh
Public Works Department

No. PW-SKT-CB -Tender/2021-22

22138-40

Dated:- 04-1-2022

To,


The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 27.01.2022 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above (in triplicate)


Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat

1. Copy along with N.I.T. to the Chief Engineer Mandi Zone HP.PWD. Mandi for information please.
2. Copy along with N.I.T. to the Superintending Engineer 1st Circle, HP.PWD. Mandi for information please.


Executive Engineer,
Sarkaghat Division
HP.PWD. Sarkaghat.

**Himachal Pradesh
Public Works Department**

“Notice Inviting Tender”

Sealed item rate tender are hereby invited in form No. 6&8 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act.1968. The important dates of tender are as under:-

The last date and time of receipt of application for tender form 27.01.2022 up to 4.00 P.M.

The last date for sale of tender is up to 28.01.2022 at 4.00PM.

The tender shall be received up to 11:00 AM on 29.01.2022 to be opened on the same day at 11:30 AM in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 29.01.2022. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.


Sr. No.	Name of work	Estimated cost.	Earnest Money.	Cost of form.	Time allowed.
1.	R/R Damages on Bhaderwar Dangar Pingla Road Km. 0/0 to 4/500 (SH:- C/O R/wall with stone facia at RD 2/115 to 2/130)	242507	5000	350	One Month
2.	A/R & M/O on Fatehpur Chandesh Durgapur Road Km. 0/0 to 22/0 (SH:- Construction of B/wall in PCC 1:5:10 at RD 14/450 to 14/455)	153379	3000	350	One Month
3.	Restoration of Rain Damages on Karnal Chari Megal Road Km. 0/0 to 3/500 (SH:- Repair of Pot holes between Km. 0/0 to 2/0)	146347	2900	350	One Month
4.	A/R & M/O Link Road Salyani to Jaman Gallu Km. 0/0 to 2/375 (SH:- R/wall in PCC with stone facia at RD 0/150 to 0/165)	186605	4000	350	One Month
5.	Construction of link Road to Bihu Manotla GP Jahmat (SH:- C/O Soling and cement concrete 1:2:4 at RD 0/0 to 0/015 and 0/090 to 0/135)	175750	3500	350	One Month
6.	Construction of Missing CD on Tikkari Khudla via Gehra Bhadrol road Km. 0/0 to 2/500 (SH:- Construction of 900mm dia RCC hume pipe culvert with wing wall at RD 0/080) SCSP	262776	5500	350	One Month
7.	R/R Damages on Batail Banoha Road Km. 0/0 to 8/0 (SH:- Construction of U-Shape Drain at RD 3/540 to 3/595)	169381	3400	350	One Month

8.	A/R & M/O Jamni Gounta Rakhota Road Km. 0/0 to 7/500 (SH:- Providing and laying interlocking paver block pavement at Km. 2/980 to 3/075, 4/210 to 4/270 and 3/810 to 3/840)	491051	1000	350	One Month
9.	Baldwara Construction of Ornamental Rain Shelter on Jogindernagar Sarkaghat Ghumarwin Road at Near Baldwara Collage (SH:- Construction of Rain Shelter near Baldwara Collage	358536	7200	350	One Month

TERMS AND CONDITONS:-

Following documents should accompany with the application for tenders.

1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST.
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.
4. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
5. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
6. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
7. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)
8. The earnest money for the above works should be attached with application forms.
9. Cost of tender for the above works may be deposited in cash with application.
10. All the required documents should be submitted with the application others wise single application may be rejected.
11. The Executive Engineer reserves the right to accept / reject any tender / application or all tenders without assigning any reason.


Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- R/R damages on Bhaderwar Dangar Pingla road Km 0/0 to 4/500. (SH:- C/O R/wall with stone facia at RD 2/115 to 2/130)

Estimated cost :- Rs. 2,42,507/-

Earnest Money:- Rs. 5000/-

Time Limit One month

Sr.No	Description of item/Sub Head	Quantity	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m in all kind of soil . with in all lead and lift and as per the direction of Engineer -in -charge.	23.40			Per cubic metre	
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with :Cement mortar 1:6 (1 cement : 6 coarse sand) with in all lead and lift and as per the direction of Engineer -in -charge.	14.85			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) with in all lead and lift and as per the direction of Engineer -in -charge.	34.50			Per cubic metre	
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge.	28			Each	
5	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	11.70			Per cubic metre	
					Total:-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O on Fatehpur Chandesh Durgapur road Km 0/0 to 22/0 (SH:- Construction of B/wall in PCC 1:5:10 at RD 14/450 to 14/455).

Estimated cost :- Rs. 1,53,379/-
Earnest Money:- Rs. 30000/-
Time Limit One month

Sr.No	Description of item/Sub Head	Quantity	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil.	17.10			Per cubic metre	0
2	Centering and shuttering including strutting, propping etc. and removal of form work for :Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets,kerbs and steps etc.with in all lead and lift and as per the direction of Engineer -in -charge.	49.80			Per square metres	0
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) with in all lead and lift and as per the direction of Engineer -in -charge.	29.24			Per cubic metre	0
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge.	9			Each	0
					Total:-	


Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Karnal Chahri Megal road Km 0/0 to 3/500 (SH:- Repair of pot holes between km 0/0 to 2/0).


Estimated cost :- Rs.146347/-
 Earnest Money:- Rs. 2900/-
 Time Limit one month

Sr.N o	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B and as per specification clause 1904.2, 503 and 508.1 and entire carriage of material within all leads, lifts and other incidentals.	857.33			Per square metre	146347
					Total:-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O Link Road Salyani to Jamman Gallu km 0/0 to 2/375 (SH: C/O R/Wall in PCC with stone fascia at RD 0/150 to 0/165).						
				Estimated cost :-		Rs. 186605.00
				Earnest Money:-		Rs. 4000.00
				Time Limit:-		One month
	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavatory) manual means in foundation trenches or drains (not exceeding 1.5 m, in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, with in a lead of 50 m all kinds of soil.	20.55			Per cubic metre	
2	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20mm nominal size) upto plinth level with Cement mortar 1:6 (1 cement :6 coarse sand)	12.60			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level 1:5:10 (1 cement :5 fine sand :10 graded stone aggregate 40 mm nominal size)	24.00			Per cubic metre	
4	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	28.00			Each	
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8	7.50			Per cubic metre	
					Total:-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.


Draft Schedule of Quantity

Name of Work:- Construction of Link Road to Bihu -Manofla G.P Jahmat (SH: C/O soling and Cement concrete 1:2:4 at RD 0/0 to 0/015 and 0/090 to 0/135)				Estimated cost :-	Rs. 175750
				Earnest Money:-	Rs. 3500.00
				Time Limit:-	Two month
	Description of item/Sub Head	Quantity	Rates		Amount
			In Figure	In words	
1	Stone soling properly hand packed filling interstices with khranja stone and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etcetra. complete as per HP.PWD specification. 100mm (one hundred milimetre) spread thickness (finished work including materials and labour) including carriage of materials within all leads and lifts and other incidentals.	27			Per cubic metre
2	Providing, laying in position cement concrete of specified grade excludng the cost of centering and shuttering all work up to plinth level 1:2:4 (1 cement :2 coarse sand: 4 graded stone aggregate 40 mm (forty millimetre) nominal size as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	27.00			Per cubic metre
				Total :-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.


SCHEDULE QUANTITY

Name of Work:- Construction of missing CD on Tikri Khudla via Gehra Bhadrol Road km 0/0 to 2/500 (SH:- Construction of 900 mm dia RCC Hume pipe culvert with wing wall at RD.0/080). (Under SCSP)					Estimated cost :-	Rs:- 262776.00
					Earnest Money:-	Rs:- 5500.00
					Time Limit:-	One month
Sr.No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) as directed by Engineer- in-charge. All kinds of soil.	46.76			Per cubic metre	
2	Providing and Laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level 1:4:8: (one Cement :four coarse sand: eight graded stone aggregate) 40 mm (forty millimetre) nominal size as per drawing and HP, PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	3.19			Per cubic metre	
3	Providing, laying, in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level 1:3:6 (one cement :three coarse sand:six graded stone aggregate) 20 mm (twenty millimetre) nominal size as per drawing and HP, PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	10.89			Per cubic metre	
4	Providing and laying Non-Pressure NP2 class (light duty) R.C.C.pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement :two fine sand) including testing of joints etcetra. 900 mm dia (nine hundred millimetre) as per drawing and HP, PWD technical specification including carriage of materials with in all leads, and lifts and direction of Engineer- in- Charge.	7.00			Per running metre	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level 1:5:10 (one cement :five fine sand :ten graded stone aggregate) 40 mm (forty millimetre) nominal size as per drawing and HP, PWDD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	25.85			Per cubic metre	
6	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	7.74			Per cubic metre	
					Total:-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE QUANTITY

Name of Work:- R/R Damages on Batail Banoha Road km 0/0 to 8/0 (SH:- Construction of U- Shape drain at RD 3/540 to 3/595).									
Estimated cost :-				Rs:- 169381.00					
Earnest Money:-				Rs:- 3400.00					
Time Limit:-				One month					
Sr. No	Description of item/Sub Head	Quantity	Rates		Unit	Amount			
			In Figure	In words					
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) as directed by with in all leads and lifts and direction of Engineer- in- Charge.	39.87			Per cubic metre				
2	Providing, laying, in position cement concrete of specified grade excuding the cost of centering and shuttering all work up to plinth level 1:3:6 (one cement :three coarse sand:six graded stone aggregate) 20 mm (twenty millimetre) nominal size as per drawing and HP PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	30.26			Per cubic metre				
						Total:-			


 Executive Engineer,
 B&R Divison,
 HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O on Jamni Gounta Rakhota road Km 0/0 to 7/500 (SH:- Providing and laying interlocking paver block pavement at km 2/980 to 3/075, 4/210 to 4/270 and 3/810 to 3/840).

Estimated cost :- Rs. 4,91,051/-
 Earnest Money:- Rs. 10,000/-
 Time Limit One month

Sr. No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2.4 (1 Cement : 2 coarse sand) 4stone aggregate 40 mm nominal size) if/in all leads, lifts and other incidental charges.	23.41			Per cubic metre	0
3	Providing and laying of interlocking concrete block pavement of NTC Tiles or equivalent and of required shade having thickness of 80mm (eighty millimetre) as per drawing and technical specifications clause 1504 including entire carriage of material within all leads, lifts and other incidental charges.	601.25			Per square metre	0
					Total:-	0

Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHUDULE OF QUANTITY

NAME OF WORK :- Construction of Ornamental Rain Shelter on Joginder nagar Sarkaghat Ghumna Road at near Baldwara College) (SH:- Construction of Rain Shelter Baldwara near Baldwara College) (Right side)

NAME OF WORK :- Construction of Ornamental Rain Shelter on Joginder nagar Sarkaghat Ghumwar Road at near Baldwara College) (SH:- Construction of Rain Shelter Baldwara near Baldwara College) (Right side)			Estimated Cost :- Rs. 358536 /-		
			Earnest Money:- Rs. 7200 /-		
			Time allowed:- one month		
Sr.No	Description of Item	Quantity	Rates In Figure In words	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre)in width or 10 sqm (ten square) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.(fifty metre)	4.24		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (One Cement : three coarse sand) : six graded stone aggregate 20 mm (twenty millimetre)nominal size including carriage of materials within all leads and lifts and other incidental charges.	1.06		Per cubic metre	
3	Random rubble masonry with hard stone in superstructure above plinth level and upto floor live level, including leveling up with cement concrete 1:6:12 (One cement :six coarse sand : twelve graded stone aggregate 20 mm (twenty millimetre)nominal size at window sills, ceiling level and the like.Cement mortar 1:6 (one cement :six coarse sand) including carriage of materials within all leads and lifts and other incidental charges.	7.43		Per cubic metre	
4	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete including carriage of materials within all leads and lifts and other incidental charges.	5.82		Per cubic metre	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (One Cement : four coarse sand) : eight graded stone aggregate 40 mm (forty millimetre)nominal size including carriage of materials within all leads and lifts and other incidental charges.including carriage of materials within all leads and lifts and other incidental charges.	2.18		Per cubic metre	
6	Kota stone slab flooring over 20 mm (twenty millimetre) (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (One cement : four coarse sand) : including carriage of materials within all leads and lifts and other incidental charges.	29.85		Per Square metre	

7	Providing and fixing Ornamental pillar including cost of binding wire and entire carriage of materials within all leads and lifts and other incidentals charges as per direction of Engineer-In-Charge.	3.00	Each
8	Providing and fixing 0.60 mm (zero point six zero millimetre) thick pre-painted steel sheet made of TATA Durashine in roofing with hot dipped metallic zinc coated sheet with the top coat of regular modified polyester (RNP) organic coating of 20 (twenty) micron over five microns primer coating to back coat of polyester over 5 (five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimetre) dia metre with pre-painted limpet and rubber washer complete with all accessories as required as per the direction of Engineer-In-Charge upto all floor levels in all heights/depth including carriage of materials within all leads and lifts and other incidentals charges. The rates are inclusive of royalty, malkana toll tax, sale tax GST or other taxes imposed by the Government.	22.20	Per Square metre
9	Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.50 mm (zero point five zero millimetre) (+0.05%) total coated thickness, Zinc coating 120 grams (one hundred twenty gram) per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self-drilling/self-tapping screws complete Ridges plain (500 - 600mm) (five hundred - six hundred millimetre) including carriage of materials within all leads and lifts and other incidentals charges.	12.60	Per running metre
10	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. x sand) Upto all floor level, including carriage of materials within all leads and lifts and other incidentals charges as per direction of Engineer-In-Charge.	737.00	Per Kilogramme
11	Providing and fixing sitting Bench including carriage of materials within all leads and lifts and other incidentals charges.	4.00	Each
			Total:-

Executive Engineer,
B&R Division,
HP PWD, Sarkaghat.