

**Himachal Pradesh
Public Works Department**

No. PW-SKT-CB -Tender/2021-22

23174-76

Dated:- 20.01.2022

To,

The Executive Engineer I.T. Cell,
Nigam Bihar Shimla -2

Subject:-

Publishing of Notice inviting tenders.

Enclosed please find herewith copies of notice inviting tender for the up loading on department website before 01.02.2022 as per notification issued by Pr. Secy. (PW) to the Govt. of HP vide letter No. PBW (B) A (3)1/2020 dated 16th July 2021. As the works mentioned in the Tender Notice are urgent nature.

DA:-As above (in triplicate)


**Executive Engineer,
Sarkaghat Division
HP.PWD.Sarkaghat**

1. Copy along with N.I.T. to the Chief Engineer Mandi Zone HP.PWD. Mandi for information please.
2. Copy along with N.I.T. to the Superintending Engineer 1st Circle, HP.PWD. Mandi for information please.


**Executive Engineer,
Sarkaghat Division
HP.PWD. Sarkaghat.**

Himachal Pradesh
Public Works Department
"Notice Inviting Tender"

Sealed item rate tender are hereby invited in form No. 6&8 by the Executive Engineer B&R Division, HP.PWD. Sarkaghat HP. on behalf of the Governor of Himachal Pradesh for the following works from the instruction and are also registered contractor of appropriate class enlisted in HP.PWD whose registration stood renewed as per revised instruction and are also registered dealers under the Himachal Pradesh General sales Tax Act. 1968. The important dates of tender are as under:-

The last date and time of receipt of application for tender form 01.02.2022 up to 4.00 P.M.

The last date for sale of tender is up to 02.02.2022 at 4.00PM.


The tender shall be received up to 11:00 AM on 03.02.2022 to be opened on the same day at 11:30 AM. in presence of the intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non refundable) during the working hours on 03.02.2022. The earnest money in the shape of National saving certificate, time deposit account in any post office/bank in HP. duly pledged in favor of the Executive Engineer B&R Division HP.PWD. Sarkaghat must accompany with each tender Conditional & in complete tenders and the tender received without earnest money will be summarily rejected. The offer of tender shall be kept open for 90 days. The Executive Engineer, reserved the right to accept or reject, the tender without assigning any reason.

Sr. No.	Name of work	Estimated cost.	Earnest Money.	Cost of form.	Time allowed.
1.	Construction of Govt. Sen. Sec. School Pounta Tehsil Sarkaghat Distt. Mandi (H.P) (SH:- Land site Development & Construction of R/wall at RD 0/0 to 0/015) Deposit work	476766	10000	350	One Month
2.	Construction of Degree College Baldwara in Tehsil Baldwara Distt. Manti (HP) Construction of Stage in College Campus)	334069	7000	350	Two Months

TERMS AND CONDITIONS:-

Following documents should accompany with the application for tenders.


1. The contractor/firms should be registered as or/dealer under HP Sales Tax Act. 1968/GST
2. The intending contractors/firms shall have to produce the copy of latest enlistment in HPPWD.
3. The contractor is required to submit an affidavit for not having more than two works in hand in the shape of affidavit duly attested by the competent authority.
4. If any of the date mentioned above happened to be Gazette Holiday the same shall be processed on next working day.
5. The contractor should quoted the rate of all the items in the tender both in figures and in words failing which tender is likely to be rejected.
6. The copy of Employees Provident Funds (EPF Number) GST, Pan Number, should be attached with application.
7. Minimum one similar work done of amount not less than 40% (Forty percent) of the estimated cost (without liquidated Damage or compensation) in last five years)
8. The earnest money for the above works should be attached with application forms.
9. Cost of tender for the above works may be deposited in cash with application.
10. All the required documents should be submitted with the application others wise single application may be rejected.
11. The Executive Engineer reserves the right to accept / reject any tender / application or all tenders without assigning any reason.


Executive Engineer,
Sarkaghat Division
HP.PWD, Sarkaghat

SCHEDULE OF QUANTITY

Name of Work:- Construction of Science lab Govt. Senior Sec. School Pounta Tehsil Sarkaghat Distt Mandi (H.P) (SH:- Land Site Development & Construction of R/wall at RD. 0/0 to 0/015). (Deposit work)					Estimated cost :-	Rs. 476766.00
					Earnest Money:-	Rs. 10000.00
					Time Limit:-	One month
	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5 m, (one point five metre) in width or 10 sqm (ten square metre) on plan including dressing of sides and ramming of bottoms, lift upto 1.5 m, (one point five metre) including getting out the excavated soil and disposal of surplus excavated soil as directed, with in a lead of 50 m (fifty metre) all kinds of soil with in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	160.74			Per cubic metre	
2	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) Ordinary rock with in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	107.16			Per cubic metre	
3	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square metre) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m, (one point five metre) with in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	19.65			Per cubic metre	
4	Centering and shuttering including strutting, propping etcetra and removal of form work for foundations, footings, bases for columns as per drawing and HP, PWD technical specification including carriage of materials with in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	101.25			Per square metre	
5	Providing and Laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work up to plinth level 1:4:8:1 (one Cement :four coarse sand: eight graded stone aggregate) 40 mm (forty millimetre) nominal size as per drawing and HP, PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	79.35			Per cubic metre	


6	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC (Polyvinyl Chloride) pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 with in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	25.00	Each	
			Total:-	


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.

SCHEDULE OF QUANTITY

Name of Work:- Construction of Degree College Baldwara in Tehsil Baldwara Distt. Mandi (H.P) (SH):- Construction of Stage in College Campus).						
Estimated cost :-				Rs. 334069 /-		
Earnest Money:-				Rs. 7000 /-		
Time Limit:-				Two month		
Sr.N o	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 (thirty centimetre) cm in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten square) on plan including getting out and disposal of excavated earth lead upto 50 m (fifty metre) and lift upto 1.5 m.(one point five metre) with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	36.66			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five coarse sand): ten graded stone aggregate) 40 mm (forty millimetre) nominal size with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	10.59			Per cubic metre	
3	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etcetra. In layers not exceeding 20cm (twenty centimetre) in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m (fifty metre)and lift upto 1.5 m. (one point five metre)with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	35.86			Per cubic metre	
4	Boulder filling dry hand packed tightly as in wire crate apron bund in floor in all leads and lifts and carriage of materials by all modes of transportation and with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	10.76			Per cubic metre	
5	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate)20 mm(twenty millimetre)nominal size upto plinth level with :Cement mortar 1:6 (one cement : six coarse sand) in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	4.89			Per cubic metre	

6	Coursed rubble masonry (first sort) with hard stone in foundation and plinth with :Cement mortar 1:6 (one cement : six coarse sand) with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	18.52		Per cubic metre
7	Kota stone slab flooring over 20 mm (twenty millimetre)(average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (one cement : four coarse sand) : 25 mm (twenty five millimetre)thick with in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	113.20		Per square metre
				Total:-


 Executive Engineer,
 B&R Division,
 HP PWD, Sarkaghat.