HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed item rate tenders are hereby invited by Executive Engineer, NH Division, HP.PWD. Solan on behalf of Governor of Himachal Pradesh for the following works from the approved registered Contractors of appropriate class (D) enlisted with Himachal Pradesh Public Works Department, whose registration stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:-

| ī | Tender Schedule | Date | Time |
|------|---|------------|----------|
| l.e. | The last date for receipt of application for tender Form. | 20/01/2022 | 4.00 PM |
| 2. | The last date for issue of tender Form | 21/01/2022 | 4.00 PM |
| 3. | The last date for receipt of tender. | 24/01/2022 | 10:30 AM |
| 4. | The date of opening of tender. | 24/01/2022 | 11:00 AM |

The tender forms can be obtained against payment of Rs.350/- (Non refundable) and contractor will be required to produce documents of registration in appropriate class, list of completed works and sales tax registration certificate. The tenders shall be opened in presence of contractor or their authorized representative.

The earnest money in shape of National Saving Certificate/Time deposit account of nationalized saving or Saving Bank account in any of the post offices and F.D.R. of Nationalized Bank duly pledged in favour of the Executive Engineer, NH Division, HP.PWD, Solan must accompany with the tender offer. The exemption from depositing the earnest money with each tender earlier granted has been withdrawn under Govt. Notification No. PWE (B&R)(B)14(18) / 98-11 dated 4.11.2003 and accordingly the tender received without assigning any reasons thereto shall not be entertained.

The tenders will be issued only to them who qualify the criteria after the scrutiny of application Form. The tenders not accompanying the Earnest money shall be rejected at the time of opening. The contractor shall also indicate the detail of Earnest money in the tender document. The request on prescribed application should accompany the registration of appropriate class, sales tax registration No. work done certificate. The tenders shall be opened on schedule date and time in presence of contractor or in the presence of the authorized representative.

The validity of tenders has been given in the tender document. If any contractor/firm withdrawn the offer within validity period then their earnest money shall be forfeited and shall finally be at the disposal of State Govt. The contractors are advised to write the rates both in figures and in words, failing which the tender shall be rejected.

Conditional and incomplete tenders shall out rightly be rejected.

Application for obtaining the tender form must accompany the latest renewal of enlistment and proof of CST No/NOC from Excise and Taxation Department regarding Sale Tax clearance. The offer shall be kept open for 120 days.

If due to any unforeseen reasons the office of the Executive Engineer, NH Division, HP.PWD, Solan remain closed on the notified date of sale and receipt of tender, the tender will be sold and received/opened on next working day of same specified time.

Description of JOB:-

| Sr. No. | Name of work | Estimated Cost | Earnest Money | Time |
|---------|---|-------------------|------------------|--------------|
| 1 | C/O Steel frame structure shed for now clearance and deicing development construction of Calcium Chloride Brine making simple machine at Chabara store at km 159/820 on NH 22 (New NH 05) | 490313/- | 10000/- | Three months |
| 2 | Balance work estimate for safety & Beautification of mural (SH-; Providing steel welded wire mesh fencing and painting at Rd 67/145 to 67/165 on NH 05, Parwanoo in the state of H.P. | 223277/- | 4500/- | One month |

Term and Conditions:-

The contractor will have to produce following documents and attached attested copies of the same at the time of submitting application for issue of tender Form.

- Enlistment/renewal in appropriate class in HP.PWD. i)
- PAN Card issued by the Income Tax Department. ii)
- Statement showing the ongoing works in HP.PWD. iii)
- E.P.F registration. iv)

Certified that the above work is of emergent nature in exigency of Public Interest.

Executive Engineer, Solan NH Division, HP.PWD. Solan.

Dated: 14-01-2022

No. NHD/CB/TA/NIT/2022-

5113-32

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief, HP.PWD, Shimla.

2. The Chief Engineer, NH, HP.PWD, Shimla.

3. The Chief Engineer, (South), HP.PWD, Shimla.

- 4. The Chief Engineer, (North), HP.PWD, Dharamshala.
- 5. The Chief Engineer, (CZ), HP.PWD, Mandi.
- 6.All the Superintending Engineer, in HP.PWD,
- 7. All the Assistant Engineers under this Division.
- 8. Notice Board.
- 9. The Executive Engineer, IT Cell in the o/o Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer, Solan NH Division, HP.PWD., Sølan.

SCHEDULE OF QUANTITY

Estimated Cost Rs. 223277/-only Earnest Money Rs. 4500/-only Time:- One Month

NAME OF WORK:- Balance work estimate for Safety & Beuatification of Mural (SH:-Providing Steel welded Wire mesh fencing and painting at RD

67/145 to 67/165 on NH-05, Parwanoo in the state of Himachal Pradesh

| | | | | | - | |
|-----|---|-------------|------|---------------|--------|--------|
| Sr. | Sr.N Description of Items. | Quantity | Rate | Rate In Words | Unit | Amount |
| · o | | | | | | |
| 1 | Providing and fixing Steel work welded in built up sections/ framed work, including | 1208.82 Kg | | | Per | |
| | cutting, hoisting, fixing in position and applying a priming coat of approved steel primer | | | | × 8 | |
| | using structural steel etc. as required. | | | | | |
| | In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works | | | | | |
| | including all leads, lifts and carriage of materials and as per the direction of Engineer-in- | | | | | |
| | Charge. | | | | | |
| 7 | Providing and fixing 10 Gauge weld mesh of size 100mm x100 mm for floor/roof slab | 46.54 Sqmt. | | | Per | |
| | concrete screed over the micro beams as reinforcement. The weld mesh shall be fixed | | | | Sqmt. | |
| | as per drawing including all leads, lifts and carriage of materials and as per the direction | | | | | |
| | of Engineer-in-Charge. | | | | | |
| 8 | Providing and Finishing with Epoxy paint (two or more coats) at all locations prepared | 69.81 Sqmt. | | | Per | |
| | and applied as per manufacturer's specifications including appropriate priming coat, | | | | Sqmt | - |
| | preparation of surface, etc. complete. | | | | | |
| | On steel work including all leads, lifts and carriage of materials and as per the direction | | | | | |
| | of Engineer-in-Charge. | | | | | |
| 4 | 4 Providing and Finishing walls with textured exterior paint of required shade: | 55.22 Sqmt. | | | Per | |
| | New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming | | | | sqmt. | |
| | coat of exterior primer applied @ 2.20kg/10 sqm including all leads, lifts and carriage of | | | | | |
| | materials and as per the direction of Engineer-in-Charge. | | 0 | | | |
| | | | | Total | | |
| | | | 1 | | | |

Executive Engineer, NH Division HPRWD. Solan

SCHEDULE OF QUANTITY

Estimated Cost Rs. 490313/-only Earnest Money Rs. 10000/-only

Time:-Three months

No 4 Description of Items Providing and fixing Steel work welded in built up sections/ framed work, Providing and laying in position cement concrete of specified grade excluding the cost of Excavation work by mechanical means (Hydraulic excavator)/ manual means in lifts and carriage of materials as per the direction of Engineer-in-Charge. guard bar, ladder, railings, brackets, gates and similar works including all leads, approved steel primer using structural steel etc. as required In gratings, frames, including cutting, hoisting, fixing in position and applying a priming coat of graded stone aggregate 20 mm nominal size)including all leads, lifts and carriage of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size)including all leads, lifts and carriage of centering and shuttering - All work up to plinth level :1:5:10 (1 cement : 5 fine sand : 10 Providing and laying in position cement concrete of specified grade excluding the cost of materials as per the direction of Engineer-in-Charge. within a lead of 50 m: in Ordinary rock including all leads, lifts and carriage of getting out the excavated soil and disposal of surplus excavated soils as directed including dressing of sides and ramming of bottoms, lift upto 1.5 m, including foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan) materials as per the direction of Engineer-in-Charge. materials as per the direction of Engineer-in-Charge. NAME OF WORK :- C/O Steel frame structure Shed for Snow Clearance and Deicing Development construction of Calcium Chloride Brine Making Simple machine at Chabara store at Km 159/820 on NH-22 (New NH 05) 3667.72 Kg Quantity 2.31 cum 2.59 cum 0.29 cum Rate in Rate in Words figures Total Unit Per Kg cum cum cum Per Per Per Amount

Executive Engineer,
NH Division, HPPWD.,
Solan