

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWF/CB/2nd C/Tender/2022:- 20038-40
To,

Dated: 14-02-2022

The Executive Engineer (IT Cell),
Nigam Vihar, Shimla.

Subject:- **Publication of tender Notice.**

In this connection, it is submitted that the tender notice of the works given in the Notice Inviting Tender for uploading on Departmental website as per Notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated 16.07.2021 as the works mentioned in the Tender Notice are urgent nature and public interest. The Tender Notice and Schedule of quantity is enclosed herewith please.

DA/As above


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur for information please.
 2. Copy of Computer Cell Office of the Executive Engineer (IT Cell), Nigam Vihar, Shimla for uploading the NIT on the Departmental website please.
- DA/As above.


Executive Engineer,
Fatehpur Divn. HPPWD,
Fatehpur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Short term tender notice

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Fatehpur Divn. HPPWD, Fatehpur for the following works on behalf of Governor of HP from the approved and eligible contractor enlisted in HPPWD Class (C&D), so as to reach in the office of the Executive Engineer, Fatehpur Divn. HPPWD, Fatehpur on or before **23.02.2022** up to 10:30 AM and will be opened on the same day at 11.00 AM in the presence of the contractors or their authorized representatives if any. The application for purchase of tender will be received up to 1.30PM on dated **22.02.2022**. The tender form can be had from his office against cash payment (Non refundable) up to 2.00 PM on **22.02.2022**.

The Earnest Money in the shape of the NSC, s Time Deposit Accounts/ Saving Accounts in any of the post office in H.P. duly pledged in favour of the Executive Engineer, must be accompanied with the tender. Conditional tender, tender received without earnest money will be summarily rejected and if holiday declared by the Govt. on the above date due to any reason the tender shall be received and opened on the next working day. The Executive Engineer reserves the right to reject the tender without assigning any reasons.

Sr. No	Name of work	Estimated cost in (Rs.)	E/Money (in Rs.)	Time limit	Cost of Form	Class
1.	Construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Construction of Basketball Court Playground Part-III) Deposit work.	Rs.167913/-	Rs.3400/-	One month.	350/-	D&C
2.	Balance work for the construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Distempering, painting, construction of pedestal for water storage tank, WS & SI etc.) Deposit work.	Rs.445642/-	Rs.9000/-	One month.	350/-	D&C

It is certified that the above works are urgently required in the interest of the people of this area, hence being the emergent nature of work, the tender of these works be called in short notice without publishing in Newspaper however same should be shown on departmental web sites.

- Note:-
- (1) The contractor may produce the copy of the latest enlistment/ renewal and PAN.
 - (2) The contractor must be registered as a dealer under HPST Act, 1968 and should produce sale tax clearance certificate from the Excise & Taxation department.
 - (3) The contractor shall produce registration of labour from the competent authority under contract Act, 1970 failing which no tender shall be issued to him.
 - (4) Special care should be taken to write the rates both in figures and in words, failing which the case likely to be rejected.
 5. registered under GST No. & EPF

Executive Engineer
Fatehpur Divn. HPPWD
Fatehpur.

SCHEDULE OF QUANTITY

Job No. 8

Name of work:- Construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH):- Estimated cost:- Rs.167913/- only
Construction of Basketball Court Playground Part-III) Deposit work.

Earnest Money : Rs.3400/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying in position cement concrete (cast in situ) of specified grade excluding the cost of centering and shuttering all work upto plinth level 1:2:4 (one cement isto two coarse sand isto four graded stone aggregate 20mm (twenty millimetre) nominal size as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	28.20 cubic meter			Per cubic meter.	

Executive Engineer,
Fatehpur Divn. HPPWD,
Fatehpur

SCHEDULE OF QUANTITY

Job No. 2

Name of work:- Balance work for the construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- ~~Construction of Distempering, painting, pedestal for water storage tank, WS & SI etc.~~)
Deposit work.

Estimated cost:- Rs.445642/- only
Earnest Money : Rs.9000/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Excavation in foundation, trenches etcetera in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work and doing work in saturated soil conditions upto any depth and lift including chiseling or wedging out rocks where blasting work is prohibited or any other mixed variety of soil including shoring, strutting dewatering and pumping or bailing out water (surface and sub soil water) upto any depth or any quantum of water including slush which may arise during dewatering, removal of slush and stacking the serviceable and unserviceable material clear from the edges of excavation as directed by the Engineer-in-charge and then returning the stacked soil in 15 cm (fifteen centimeters) layers when required into plinths and sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable excavated earth as per specification, . approved drawing .design as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of material with in all leads lifts and other incidental and all type of taxes imposed by the Government.	20.74 Cubic meter.			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) and curing complete, in or under water, including pumping or bailing out water/dewatering, removal of slush which may arise at the time of laying under water complete excluding the cost of form work in foundation and plinth in all depths/heights as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads and lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax, GST, Sales tax or any taxes imposed by the Government.	1.73 Cubic meter.			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete 1:2:4 (one cement: two sand : four graded crushed stone aggregate 20mm (Twenty millimetre) nominal size) of Grade M-20 (Twenty) mix designed to obtain the minimum compressive strength of 20 N (twenty Newton) per square millimeter with minimum cement contents, of 320 kg (three hundred twenty kilogramme) per cubic meter and curing complete excluding the cost of form work and reinforcement for reinforced concrete work in Foundations, footings bases of columns and the like and mass concrete as per HPPWD specification or as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of Malkhana, Royalty, Octroi, toll tax, GST, Sale tax or any taxes imposed by the Government.	6.53 Cubic meter.			Per cubic meter	

4	Stone filling behind retaining walls as per HPPWD specification or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidental. The rate including Royalty, Malkhana, Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	3.60 Cubic meter			Per cubic meter	
5	Filling in plinth with sand under floors including watering, ramming, consolidating and dressing complete as per HPPWD specification or as directed by Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidental. The rate including Royalty, Malkhana, Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	7.20 Cubic meter			Per cubic meter	
6	Cement concrete flooring 1:2:4 (one cement isto two sand into four graded stone aggregate) 20mm (twenty millimeter) nominal size laid in one layer finished with a floating coat of neat cement including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	36.00 Square meter.			Per square meter	
7	Providing and fixing ISI marked 15mm (fifteen millimeter) nominal bore/diameter to wall, ceiling and floor galvanised mild steel tubes (medium grade) tube fitting and clamps including making good the wall, ceiling and floors including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	150.00 Running meter.			Per running meter	
8	Providing and fixing ISI marked 20mm (twenty millimeter) nominal bore/diameter to wall, ceiling and floor galvanised mild steel tubes (medium grade) tube fitting and clamps including making good the wall, ceiling and floors including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	158.00 Running meter.			Per running meter	
9	Fixing water meter stop-cock in galvanised mild steel tube including necessary fittings such as mild steel galvanised jam nut, sockets, etc. cutting and making long screws complete (water metre and stop cock to be measured and paid for separately) 20mm (twenty millimeter) nominal bore including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	1.00 Number			Each	
10	Taking out water metre (any pattern) with spigot and socket connecting pipes for pipes (80mm to 150mm) eighty millimetre to one hundred fifty millimeter) nominal bore of the following nominal bore including burning out tow lead joints 50mm fifty millimeter) including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	1.00 Number			Each	

11	Providing and fixing 15mm (fifteen millimeter) diameter C.P. stop cocks of Prayag/Hindware/cera of its equivalent as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate including of all type of taxes imposed by the Government.	10.00 Numbers			Each	
12	Providing and fixing 20mm (twenty millimeter) diameter C.P. stop cocks of Prayag/Hindware/cera of its equivalent as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate including of all type of taxes imposed by the Government.	10.00 Numbers			Each	
13	Providing and fixing PVC water storage tank of ISI : 12701 marked, G.I. inlet and outlet connection, 15mm (fifteen millimeter) nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting upto all heights above ground level 2000 (two thousand) litres net capacity tank including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	7.00 Number			Each	
14	Providing and fixing IS marked big size No. 2071 (two thousand seventy one) of Cera / Hindware or equivalent in white colour vitreous china water closet squatting pan (Orissa type W.C. pan) size 580 x 440mm (five hundred eighty into four hundred forty millimeter) Orissa pattern (earth work, bed concrete, foot rest and trap to be measured and paid for separately) . as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate including of all type of taxes imposed by the Government.	4.00 Numbers			Each	
15	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately) Angle Indian Universal closet including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	3.00 Numbers			Each	
16	Providing and fixing 10.0/12.50/15.00 litres vitreous China low level flushing cistern with a pair of C.I. or mild steel brackets, complete with fitting such as lead valve less syphon, 15mm nominal size brass ball valve with polythene float, C.P. Brass handle, unions and couplings for connections with inlet, outlet and overflow pipes, 40mm dia C.P. flush bend including cutting holes in walls and making good the same and connecting the flush beng with cistern and closet (overflow pipe to be measured and paid for separately). including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	7.00 Numbers			Each	

17	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers solid type white plastic seat and cover including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	3.00 Numbers			Each	
18	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings flat back 550mmx400mm (five hundred fifty millimetre into four hundred millimeter) including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	7.00 Numbers			Each	
19	Providing and fixing 15mm (fifteen millimetre) dia C.P. brass bib tap with capstan head including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	7.00 Numbers			Each	
20	Providing and fixing 15mm (fifteen millimetre) dia C.P. brass pillar tap with capstan head including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	7.00 Numbers			Each	
21	Providing and fixing 600x450mm (Six hundred into four hundred fifty millimeters) bevelled edge mirror of superior glass (atultuff or equivalent make) mounted on 6mm (Six millimeters) thick A.C. sheet or plywood sheet and fixed to wooden plugs with C.P. brass screws and washers complete as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate including of all type of taxes imposed by the Government.	7.00 Numbers			Each	
22	Providing and fixing 100mm (One hundred millimetre) sand cast iron grating for gully, floor or Nahni trap including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	7.00 Numbers			Each	

23	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430 x 260mm x 350 and 340x430x265mm sizes, respectively with automatic flushing cistern with fittings R.S or C.I. Brackets standard size galvanised steel flush pipe and spreaders galvanised steel flush pipe and spreaders with brass unions and G.I. clamps complete, including painting of cistern and fittings, cutting and making good the walls floors where required one urinal basin with 5 (five) litres C.I. automatic flushing cistern. including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	4.00 Numbers			Each	
24	Providing and fixing division plate for urinals 600mmx300 (six hundred millimetre into three hundred) Vitreous china including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	3.00 Numbers			Each	
25	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface. including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government	1885.53 Square meter.			Per square meter	
26	Distemper (two or more coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and sand papered smooth priming coat with distemper primer as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rate inclusive Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	1345.18 Square meter.			Per square meter	
27	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) of Asian paints/Nerolac paints or its equalised brand and manufacture of approved shade on undecorated wall surfaces (two or more coats) to give an even shade and final finish after thoroughly cleaning / brushing the surfaces to remove all dirt, dust mortar dropping and other foreign matter and sand papered smooth including applying of putty as required for making the surfaces complete upto all floor level as per specifications approved drawings, design, as per entire satisfaction and direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	1107.00 square meter.			Per square meter	


 Executive Engineer,
 Fatehpur Divn. HPPWD,
 Fatehpur
