

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PWF/CB/2nd C/Tender/2022:- 19083-85
To,

Dated:

11/2/2022


The Executive Engineer (IT Cell),
Nigam Vihar, Shimla.

Subject:-

Publication of tender Notice.

In this connection, it is submitted that the tender notice of the works given in the Notice Inviting Tender for uploading on Departmental website as per Notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated 16.07.2021 as the works mentioned in the Tender Notice are urgent nature and public interest. The Tender Notice and Schedule of quantity is enclosed herewith please.

DA/As above



Executive Engineer,
Fatehpur Divn. HPPWD,
Fatehpur

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur for information please.

2. Copy of Computer Cell Office of the Executive Engineer (IT Cell), Nigam Vihar, Shimla
for uploading the NIT on the Departmental website please.

DA/As above.


Executive Engineer,
Fatehpur Divn. HPPWD,
Fatehpur

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Short term tender notice

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Fatehpur Divn. HPPWD, Fatehpur for the following works on behalf of Governor of HP from the approved and eligible contractor enlisted in HPPWD Class (C&D), so as to reach in the office of the Executive Engineer, Fatehpur Divn. HPPWD, Fatehpur on or before **19.02.2022** up to 10:30 AM and will be opened on the same day at 11.00 AM in the presence of the contractors or their authorized representatives if any. The application for purchase of tender will be received up to 1.30PM on dated **17.02.2022**. The tender form can be had from his office against cash payment (Non refundable) up to 2.00 PM on **18.02.2022**.

The Earnest Money in the shape of the NSC, s Time Deposit Accounts/ Saving Accounts in any of the post office in H.P. duly pledged in favour of the Executive Engineer, must be accompanied with the tender. Conditional tender, tender received without earnest money will be summarily rejected and if holiday declared by the Govt. on the above date due to any reason the tender shall be received and opened on the next working day. The Executive Engineer reserves the right to reject the tender without assigning any reasons.

Sr. No	Name of work	Estimated cost in (Rs.)	E/Money (in Rs.)	Time limit	Cost of Form	Class
1.	A/R & M/O Jagnoli Bhatta Bhawara Baruna Hadwal road km. 0/0 to 4/0 (SH:- Providing and laying interlocking paver block at R.D.2/600 to 2/630, 2/705 to 2/770).	Rs.390840/-	Rs.7900/-	One month	350/-	D&C
2.	A/R & M/O Jagnoli Bhatta Bhawara Baruna Hadwal road km. 0/0 to 4/0 (SH:- Providing and laying interlocking paver block at R.D.2/770 to 2/865).	Rs.390840/-	Rs.7900/-	One month	350/-	D&C
3.	Balance work of construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Construction of Edge wall & prepainted Chhajjas etc.) Deposit work.	Rs.280701/-	Rs.5700/-	One month	350/-	D&C
4.	Construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Construction of Basketball Court play ground Part-I) Deposit work.	Rs.435616/-	Rs.8800/-	One month	350/-	D&C
5.	Balance work for the construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Providing and fixing M.S. pedestal for PVC water tank) Deposit work.	Rs.469806/-	Rs. 9400/-	One month	350/-	D&C
6.	Construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Construction of Basketball Court Playground Part-II) Deposit work.	Rs.495968/-	Rs.10000/-	One month	350/-	D&C

It is certified that the above works are urgently required in the interest of the people of this area, hence being the emergent nature of work, the tender of these works be called in short notice without publishing in newspaper, however, same should be shown on departmental web sites.

Note:- (1) The contractor may produce the copy of the latest enlistment/ renewal and PAN.

(2) The contractor must be registered as a dealer under HPST Act, 1968 and should produce sale tax clearance certificate from the Excise & Taxation department.

(3) The contractor shall produce registration of labour from the competent authority under contract Act, 1970 failing which no tender shall be issued to him.

(4) Special care should be taken to write the rates both in figures and in words, failing which the case likely to be rejected.

5. registered under GST No. & EPF

Executive Engineer
Fatehpur Divn. HPPWD
Fatehpur.

SCHEDULE OF QUANTITY

Job No.1

Name of work:- A/R & M/O Jagnoli Bhatta Bhawara Barrua Hadwal road km. 0/0 to 4/0 (SH:- Providing and laying interlocking paver block at R.D.2/600 to 2/630, 2/705 to 2/770).

Estimated cost:- Rs.390840/- only

Earnest Money : Rs.7900/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	47.50 Cubic meter.			Per cubic meter	
2	Providing and laying of interlocking concrete block pavement having thickness 80mm (Eighty millimeters) in grey and coloured shade make over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	475.00 Square meter			Per Square meter.	

Executive Engineer,
Fatehpur Divn. HPP WD,
Fatehpur
gm

SCHEDULE OF QUANTITY

Job No.2

Name of work:- A/R & M/O Jagnoli Bhatta Bhawara Baruna Hadwal road km. 0/0 to 4/0 (SH:- Providing and laying interlocking paver block at R.D.2/770 to 2/865).

Estimated cost:- Rs.390840/- only

Earnest Money : Rs.7900/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	47.50 Cubic meter.			Per cubic meter	
2	Providing and laying of interlocking concrete block pavement having thickness 80mm (Eighty millimeters) in grey and coloured shade make over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer-in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	475.00 Square meter			Per Square meter.	

Executive Engineer,
Fatehpur Divn. HPPWD,
Fatehpur
gmr

SCHEDULE OF QUANTITY


Job No.3

Name of work:- Balance work of construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Construction of Edge wall & prepaainted Chhajjas etc.) Deposit work.

Estimated cost:- Rs.280701/- only
Earnest Money : Rs.5700/- only
Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	26.04 Cubic meter.			Per cubic meter	
2	Providing and fixing 0.60mm (zero point six zero millimeter) thick prepaainted steel sheet in roofing hot dipped metallic zink coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with prepaainted iron J or L hooks, bolts and nuts 6mm (six millimeter) dia meter with prepaainted limpet and rubber washers complete with all accesories as required as per direction of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental Charges. The rate includes, royalty charges, octroi, sale tax, malkana, G.S.T. and all other taxes as imposed by the Government.	54.90 Square meter.			Per square meter	
3	Steel work welded in built up sections trusses and framed work, including cutting, hoisting fixing in position and applying a priming coat of red lead paint complete in beams, joists channels angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Royalty, Malkhana, Octroi, Toll Tax Sales tax or any other taxes imposed by the Government.	13.73 Quintal			Per Quintal	

4	Providing and fixing M.S. (Mild steel) BP (Black plain) sheet 1.66mm to 2mm (one point six six millimetres to two millimetres) thick in eaves board/facia/soffits/ ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-Charge (Base members of steel work shall be measured and paid separately), including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S. T. and all other taxes as imposed by the Government.	51.24	Square meter.				Per square meter	
5	Providing and fixing 2 (two) horse power centrifugal mono block pump 80x80mm (eighty into eighty millimeter) crompton/kirloskar including carriage of materials within all leads, lifts and other incidental Charges. The rate including royalty charges, octroi, malkhana, sale tax, G.S. T. and all other taxes as imposed by the Government.	1.00	Number				Each	


 Executive Engineer,
 Fatehpur Divn. HPPWD,
 Fatehpur

SCHEDULE OF QUANTITY

Job No.4

Name of work:- Construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.) (SH:- Construction of Basketball Court play ground Part-I) Deposit work.


Estimated cost:- Rs.435616/- only

Earnest Money : Rs.8800/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Excavation in foundation, trenches etcetera in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work and doing work in saturated soil conditions upto any depth and lift including chiseling or wedging out rocks where blasting work is prohibited or any other mixed variety of soil including shoring, strutting dewatering and pumping or bailing out water (surface and sub soil water) upto any depth or any quantum of water including slush which may arise during dewatering, removal of slush and stacking the serviceable and unserviceable material clear from the edges of excavation as directed by the Engineer-in-charge and then returning the stacked soil in 15 cm (fifteen centimeters) layers when required into plinths and sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable excavated earth as per specification, . approved drawing . design as per the entire satisfaction and direction of the Engineer -in -Charge including carriage of material with in all leads lifts and other incidental and all type of taxes imposed by the Government.	12.30 Cubic meter.			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (forty millimeter) nominal size) and curing complete, in or under water, including pumping or bailing out water/dewatering, removal of slush which may arise at the time of laying under water complete excluding the cost of form work in foundation and plinth in all depths/heights as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads and lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax, GST, Sales tax or any taxes imposed by the Government.	39.86 Cubic meter.			Per cubic meter	
3	Precast concrete block masonry (including quion blocks, jamb blocks, closer etc.) with solid concrete blocks of approved size made of cement concrete 1:3:6 (one cement isto three sand six graded stone aggregate 40mm (forty millimeter) and down gauge) foundation and plinth upto all floor level in cement mortar 1:6 (one cement isto six sand) as per HPPWD specifications or as directed by the Engineer-in-Charge including carriage of materials within all leads and lifts. The rate inclusive of Malkhana, royalty, octroi, toll tax, GST, Sales tax or any taxes imposed by the Government.	5.10 Cubic meter.			Per cubic meter	

4	Construction of granular sub base by providing well graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site upto any leads spreading in uniform layers with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per MORD technical specification clause 401 (i) for Grading-I material as per the entire satisfaction and direction of Engineer-in-charge. The rate is including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.	28.20 Cubic meter.			Per cubic meter	
5	Providing and laying Tor steel reinforcement for Reinforced Cement Concrete work including bending, binding and placing in position complete including cost of binding wire and other incidentals due for its completion up to all floor level complete as per HPPWD specifications or as directed by the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Octroi, Toll Tax, GST, Sales tax or any other taxes imposed by the Government.	4247.25 Kilogramme			Per Kilogra mme.	
6	Applying priming coat on new concrete/masonry/asbestos cement/ plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required with Readymixed primer as per specifications approved drawings, design, as per entire satisfaction and direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	608.00 square meter.			Per square meter	
7	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) of Asian paints/Nerolac paints or its equaried brand and manufacture of approved shade on undecorated wall surfaces (two or more coats) to give an even shade and final finish after thoroughly cleaning / brushing the surfaces to remove all dirt, dust mortar dropping and other foreign matter and sand papered smooth including applying of putty as required for making the surfaces complete upto all floor level as per specifications approved drawings, design, as per entire satisfaction and direction of the Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidental. The rate including royalty charges, octroi, malkhana, sale tax, G.S.T. and all other taxes as imposed by the Government.	730.00 square meter.			Per square meter	


 Executive Engineer,
 Fatehpur Diya. HPPWD,
 Fatehpur

SCHEDULE OF QUANTITY

Job No. 5

Name of work:- Balance work for the construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Delhi in Tehsil Fatehpur, Dist Kangra (H.P.) (SH:- Providing and fixing M.S. pedestal for PVC water tank) Deposit work.

Estimated cost:- Rs.469806/- only

Earnest Money : Rs.9400/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Steel work welded in built up sections trusses and framed work, including cutting, hoisting fixing in position and applying a priming coat of red lead paint complete in beams joists channels angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as directed by the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate inclusive of Malkhana, royalty, octroi, toll tax, Sale tax, GST or any taxes imposed by the Government.	66.31 Quintal			Per Quintal	

Executive Engineer,
Fatehpur Divn. HPPWD,
Fatehpur
2/10

SCHEDULE OF QUANTITY

Job No. 6

Name of work:- Construction of 10 Nos. Class Rooms in WRS Govt. Degree College at Dehri in Tehsil Fatehpur, Distt Kangra (H.P.)
(SH:- Construction of Basketball Court Playground Part-II) Deposit work.

Estimated cost:- Rs.495968/- only

Earnest Money : Rs.10000/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium tensile steel bars as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	773.51 kilogram me			Per kilogra mme	
2	Providing and laying in position cement concrete (cast in situ) of specified grade excluding the cost of centering and shuttering all work upto plinth level 1:2:4 (one cement isto two coarse sand isto four graded stone aggregate 20mm (twenty millimetre) nominal size as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, GST, sale tax or other taxes imposed by the Government.	73.50 cubic meter			Per cubic meter.	

Executive Engineer,
Fatehpur Divn. HPPWD,
Fatehpur