

CERTIFICATE

Certified that tenders called vide this office Notice No PWD/KB/CB/Tender/2020-21 – 7445-54 dated 3.2.2022 for 2 Jobs is hereby invited without press notice due to exigencies/emergency of works in the public interest

Executive Engineer
Kotla behar Division HPPWD
Kotla behar (H.P.)

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated **02.03.2022 up to 10.30 AM** and the same will be opened on the same day at **11.30 AM** in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to **2.00 PM** on dated **28.2.2022** and tender forms can be obtained from this office against cash payment (nonrefundable) on **28.2.2022 at 5.00 PM** and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	A/R & M/O Kotla Behar Ghatti Bilwan Road Km 0/0 to 9/9165 (SH:- Repair of Pot Holes in km 0/0 to 9/165)	489335	9600	One Month	350	6&8
2	A/R & M/O Bagli to karoa Road Km 0/0 to 2/060 (SH:- P/I Bituminous Macadam in between km 1/0 to 2/060 for repair of pot holes)	442117	8900	Two sMonth	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,

~~Executive Engineer,~~
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER 2020-21 7445-54

DATED

3/2/2022

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.

Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.

~~Executive Engineer,~~
Kotla Behar Division HPPWD.,
Kotla Behar

BILL OF QUANTITY

JOB NO. 1 Pa

Estimate Cost :- Rs. 4,89,335/-
Earnest Money :-Rs. 9,800/-
Time Limit :-One Month.

Name of work:- A/R & M/O Kotla Behar Chatti Bilwan road Km. 0/0 to 9/165 (SH: Repair of pot holes in Km. 0/0 to 9/165)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing laying, spreading by manual/mechanically means and compacting to 75mm (seventy five millimeter) compacted thickness, stone aggregates of Grading-III, 53mm to 22.4mm (fifty three to twenty two point four millimetre) size to water bound macadam specification including spreading in uniform thickness, using template, hand packing motor grader, rolling with three wheeled roller 80-100 (eighty to hundred) kN static weight in stages to proper grade and camber including applying and brooming stone screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.18cum (zero point one eight cubic metre) per ten square metre of road surface to fill up the interstices of coarse aggregate, watering and compacting to the required density for grading-III as per MORD Technical specification clause 405 and as per entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	20.00			Per cubic metre	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	2750.00			Per Square metre	
TOTAL						

Executive Engineer,
Kotla Behar Division,
MPPWD Kotla Behar

BILL OF QUANTITY

Estimate Cost :- Rs. 442117/-
 Earnest Money :-Rs. 8900/-
 Time Limit :-Two Month.

Name of work:- A/R & M/O Bagli to Karaa road Km. 0/0 to 2/060 (SH: P/L Bituminous Macadam in between Km. 1/0 to 2/060 for repair of pot hole

Sr. No.	Description of Item	Quantity	Rate in		Unit	Am
			Figures	Words		
1	Providing and applying tack coat with bitumen emulsion RS-I, including cleaning the road surface with hydraulic brooms and spraying with emulsion pressure distributor at the rate 0.275 kg (zero point two seven five kilogramme) per square meter on the prepared granular surface treated with primer complete as per MORD Technical specification clause 503, and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	1443.00 Square metre			Per square meter	
2	Providing and laying 50mm (Fifty millimetre) thick bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder, transported to site upto all laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	72.15 Cubic metre			Per Cubic metre	
TOTAL						

Executive Engineer,
 Kotla Behar Division,
 MPWD Kotla Behar.