

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-MDI-E-Tender-NIT/2021-22-

20639-41

Dated:- 14/2/2022

To

The Executive Engineer (IT Cell),
Nigam Bhhar, Shimla-2.


Subject: -

Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. Mandi.

Copy forwarded the Superintending Engineer, 1st Circle, HPPWD, Mandi for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell) Nigam Bihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. Mandi.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., Mandi on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **26.02.2022 up to 12:00 Noon** and the same shall be opened on the same day **at 12:30 P.M.** in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on **25.02.2022 upto 12:00 Noon.**

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., Mandi reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Annual repair & maintenance of Non residential building under HPPWD Sub-Division Padhar. (SH:- Providing Cup boards, PVC flooring, painting and distempering of J.E. office cum store building for Kunnu Section at Hardgaloo).	2,84,807/-	5,100/-	350/-	One month
2	Annual repair & maintenance of Non residential building under HPPWD Sub-Division Padhar. (SH:- Providing brick work in partition walls, vitrified tile flooring & cement plastering of J.E. office cum store building for Kunnu Section at Hardgaloo).	2,56,859/-	5,100/-	350/-	One month
3	Restoration of rain damages on Bhiuli Chhipnu road Km 0/000 to 4/000. (SH:- Construction of retaining wall at RD 3/735 to 3/745)	4,97,601/-	10000/-	350/-	One month
4	Restoration of rain damages on Bhiuli Chhipnu road Km 0/000 to 4/000. (SH:- Construction of retaining wall at RD 3/745 to 3/755)	2,24,507/-	4,500/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

HIM SUCHANA AVAM JAN SAMPARK

Executive Engineer,
Mandi Division No. I,
HPPWD., Mandi Distt. Mandi (H.P.)

Schedule of Quantity

Name of work:- Annual repair & maintenance of Non residential building under H.P.P.W.D. Sub Division Padhar. (Sub Head:- Providing Cup boards, PVC flooring, painting and distempering of J.E. Office cum store building for Kunnu Section at Hardgaloo.)

Estimated Cost:- Rs. 284807.00
Earnest Money:- Rs. 5100.00

Time:- One month

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing and fixing 2mm (two millimetre) thick PVC antistatic vinyl flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) complete as per specification including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction and satisfaction of Engineer-in-Charge.	30.02 Sqm.			Per square metre	
2	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade on new work (two or more coats) over and including water thinnable priming coat with cement primer complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	466.85 Sqm.			Per square metre	
3	Painting two coats (excluding priming coat) on old wood and wood based surfaces, with ready mixed paint to give an even shade including cleaning the surface of all dirt, dust and other foreign matter, sand papering and stopping including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	62.88 Sqm.			Per square metre	
4	Painting (two or more coats) on previous work with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including cleaning the surface of all dirt, dust and other foreign matter, sand papering and stopping including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	15.50 Sqm.			Per square metre	
5	Finishing walls with Acrylic Smooth exterior paint of required shade on previous work (two or more coat applied @ 1.67 ltr./ 10 sqm (one point six seven litre per ten square metre) over and including priming coat of exterior primer applied @ 2.20 ltr./ 10 sqm (two point two zero litre per ten square metre) including carriage of material in all leads and lifts and other incidentals complete as per the entire satisfaction and direction of Engineer-in-Charge.	80.64 Sqm.			Per square metre	
6	Providing and fixing cup board shutters with 25 mm (twenty five millimetre) thick veneered particle board IS : 3097 marked, exterior grade (Grade I), of approved make with decorative veneering on one side and commercial veneering on other side, including second class teak wood lipping of 25 mm (twenty five millimetre) wide x 12 mm (twelve millimetre) thick with necessary screws and bright finished stainless steel piano hinges including carriage of material in all leads and lifts and other incidentals complete as per the entire satisfaction and direction of Engineer-in-Charge.	82.08 Sqm.			Per square metre	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
7	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etcetera as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of material in all leads and lifts and other incidentals complete as per the entire satisfaction and direction of Engineer-in-Charge.	27.00 Kg.	.		Per kilogram	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 J.P. PWD, Mandi.

Schedule of Quantity

Estimated Cost:- Rs. 256859.00
 Earnest Money:- Rs. 5100.00
 Time:- One month

Name of work:- Annual repair & maintenance of Non residential building under H.P.P.W.D. Sub Division Padhar. (Sub Head:- Providing brick work in partition walls, vitrified tile flooring & cement plastering of J.E. Office cum store building for Kunnu Section at Hardgaloo.)

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	8.77 Cum.			Per cubic metre	
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	14.94 Sqm.			Per square metre	
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6 (one cement : six coarse sand) including curing and carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.41 Cum.			Per cubic metre	
4	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor all level including curing and carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	16.74 Sqm.			Per square metre	
5	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % (zero point zero eight) percent and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (at the rate of three point three kilogram per squaremetre) including grouting the joint with white cement & matching pigments etcetera including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	40.25 Sqm.			Per square metre	
6	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% (zero point zero eight) percent and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm (six millimetre) thickness, including grouting of joints (Payment for grouting of joints to be made separately) including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.41 Sqm.			Per square metre	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work up to plinth level 1:2:4 (one cement : two sand : four graded, crushed stone aggregate 20mm (twenty millimetre) nominal size.) including curing and carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.92 Cum.			Per cubic metre	
8	15 mm (fifteen millimetre) cement plaster on fair/rough side of brick/ concrete/ stone walls of mix 1:5 (one cement: five coarse sand) complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	88.05 Sqm.			Per square metre	
9	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	466.85 Sqm.			Per square metre	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 H.P.P.W.D. Mandi.

Schedule of Quantity

Estimated Cost:- Rs. 497601.00
Earnest Money:- Rs. 10000.00
Time:- One month

Name of work:- Restoration of rain damages on Bhiuli Chhipnu road Km. 0/000 to 4/000.
Sub Head:- Construction of retaining wall at RD 3/735 to 3/745.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	12.85 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	94.10 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	6.90 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	20.00 Nos.			Each	
					Total	


Executive Engineer,
Mandi Division No.1,
H.P.W.D. Mandi.

Schedule of Quantity

Estimated Cost:- Rs. 224507.00
 Earnest Money:- Rs. 4500.00
 Time:- One month

Name of work:- Restoration of rain damages on Bhili Chhipnu road Km. 0/000 to 4/000.

Sub Head:- Construction of retaining wall at RD 3/745 to 3/755.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	11.80 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203 . Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	41.58 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	4.50 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other other incidentals as per direction of Engineer-in-Charge.	8.00 Nos.			Each	
					Total	


 Executive Engineer,
 Mandi Division No.1,
 H.P. PWD, Mandi.