

Telephone No: 01782-233214
E-mail: eenh-ram-hp@nic.in

No. PW/EE/NH/RMP-CB-Tender /2021-22- 75 98-30
To


Dated:- 01/02/2022

✓ The Executive Engineer, (IT)
Nigam Vihar Shimla-2.

Subject: - Publication of Tender notice


Enclosed please find herewith NIT for uploading on department website as per Notification Pr. Secy. (PW) to the Govt. of HP letter No. PBW(B)A(3)1/2020 dated 19 June 2021 as the work mentioned in the NIT are urgent nature and in public interest.

DA:- Copy of NIT and schedule of quantity


Executive Engineer,
NH Division HPPWD,
Rampur Bushahr.

Copy forwarded to the Superintending Engineer NH Circle HPPWD Shimla for information, please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action, please.


Executive Engineer,
NH Division HPPWD,
Rampur Bushahr.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**


Sealed item rate tender(s) on PWD form No.6 & 8 are hereby invited/re-invited by the Executive Engineer, NH- Division, HP.PWD, Rampur Distt. Shimla (H.P) on behalf of the Governor of H.P for the following works from the registered contractors in HP.PWD in appropriate class to reach in this office on **08-02-2022** up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **07-02-2022** i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without **earnest money and cost of tender form** or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer NH-Division HP.PWD Rampur Bushahr Distt. Shimla H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Form No.	Cost of form
1	A/R and M/O on NH-05 Km 236/00 to 368/00 (SH:- Construction of wire crate R/wall at RD 285/095 to 285/115).	4,90,487/-	9,800/-	Two months	6&8	350/-
2	A/R & M/o on NH-05 Km 236/00 to 368/00 (SH:- Construction of R/wall in PCC at RD 282/880 to 282/887 & V-shape drain at Km 287/425 to 287/570)	4,78,750/-	9,600/-	Two months	6&8	350/-
3	A/R & M/o on NH-305 Sainj Luhri Aut road Km 0/00 to 53/00 Supplying and installation of delineators between Km 0/00 to 5/00)	4,99,472/-	10,000/-	Two months	6&8	350/-
4	A/R & M/o on NH-305 Sainj Luhri Aut road Km 0/00 to 53/00 Supplying and installation of delineators between Km 5/00 to 10/00)	4,94,760/-	9,900/-	Two months	6&8	350/-

SPECIAL CONDITIONS

- The material shall be arranged by the contractor himself.
- The detail of documents to be attached with the application is given below.
 - Latest copy of renewal enlistment.
 - Copy of Pan Card.
 - Copy of GST No.
- The offer of the tender shall be kept open for 90 days
- Tender received after the specified time/date shall not be opened.
- Executive Engineer NH-division HP.PWD Rampur Distt. Shimla H.P. reserves the right to reject any or all tender/s without assigning any reasons.
- If due to any unforeseen reasons the office of the Executive Engineer NH-Division HP.PWD Rampur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
- Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
- The contractor/ firms are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
- The labourcess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
- The labour cess @ 1% will be deducted from the gross amount of the bill
- A contractor enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification No.PBW (B) 22-1/2002 dated 26-05-2015.
- The Contractor will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act.1952 before award of work.
- Cement should be purchased from H.P. State Civil Supply Corporation
- GST will be deducted from each bill as per latest instruction of the Government.



Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr.

No.PW/EE/NH/RMP/CB-Tender Notice/2021-22- 7518-27

Dated:-01-02-2022


Copy forwarded for information to:-

- Engineer-in-Chief, HP.PWD, Shimla
- Chief Engineer (NH) HP.PWD, Shimla-1
- Superintending Engineer, NH-Circle, HP.PWD, Shimla. It is requested to kindly issue the certificate the tender of above emergent nature in public interest.
- All the Assistant Engineer working under this division
- A/B & D/B in this office.
- Notice board of this office.


Executive Engineer,
NH Division, H.P.PWD,
Rampur Bushahr.

Certificate

Certified that the tenders for the work invited vide this office NIT No. PW/EE/NH/RMP-CB-Tender/2021- 7518-27 dated 01-02-2022 is of urgent nature and in public interest.


Executive Engineer
NH Division HPPWD
Rampur Bushahr


SCHEDULE OF QUANTITY

NAME OF WORK:- A/R and M/O NH-305 Sainj Luhri Aut road Km 0/00 to 53/00 Supplying and installation of delineators between Km 5/0 to 10/00				(SH:-	Estimated cost:- 494760.00 Earnest money:- 9900.00 Time:- One Month	
Sr, No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Supplying and installation of delineators(road way indicators,hazard markers,object markers) 900mmheight, painted black and white in 15 cm wide strips,48 mm dia circular reflectorised panels at the top and conforming to IRC-79 and the drawings including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer -in- charge.	525.00			Each	
					Total:-	


Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R and M/O NH-305 Sainj Luhri Aut road Km 0/00 to 53/00 Supplying and installation of delineators between Km 0/0 to 5/00)				(SH:-	Estimated cost:- 499472.00 Earnest money:- 10000.00 Time:- One Month	
Sr, No.	Sub head/item of work	Quantity	Rate In Figure	Rate In words.	Unit	Amount
1	2	3	4	5	6	7
1	Supplying and installation of delineators(road way indicators,hazard markers,object markers) 900mmheight, painted black and white in 15 cm wide strips,48 mm dia circular reflectorised panels at the top and conforming to IRC-79 and the drawings including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer -in- charge.	530.00			Each	
					Total:-	



Executive Engineer,
NH Division HPPWD,
Rampur Bsr.

Schedule of Quantity						
Name of work:- A/R & M/O on NH-05 Km 236/00 to 368/00 (SH:- Construction of wire crate R/wall at RD 285/095 to 285/115)				Estimated Cost:- 490487.00		
				Earnest Money 9800.00		
				Time :- Two Month		
S.No	Descriptions.	Quantity	Rate		Unit	Amount
			In figure	In words.		
1	Cutting in earth work in all kinds of soils such as pick work, jumper work, soft and hard rock i.e. chiselling and wedging out of rock if required and saturated soils and their intermediate classifications in all heights and depths. Stacking the useful stone/materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges including loading of truck for carrying the unserviceable materials. Any loss of public/private property during the course of execution shall be the sole responsibility of the contractor which shall have to be duly compensated by him at his own cost in all cases, the work shall be carried out as per clause 301 of section 300 of MORTH specifications to the entire satisfaction and direction of Engineer-in-Charge.	66.00 Cum			Per cubic meter.	
2	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications in all kinds of soils i.e. pick work, jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	165.60 Cum			Per cubic meter.	
3	Providing and laying of boulders apron laid in wire crate made with 4 mm (Four milimetre) thick G.I wire confirming to IS 280 and IS 4826 in 100x100 mm(hundred into hundred milimetre) mesh (Weaved diagonal) in all heights and depths including 10% extra for laps and joints laid with stone boulders weighing not less than 40Kg(Forty kilograms) each including carriage of materials by mechanical transport in all leads and lifts confirming with the MORTH Specification (Latest revision) and as per direction of the Engineer-in-Charge.	56.70 Cum			Per cubic meter.	
Total Rs:-						

Note:-Contractor will himself arrange the following materials:-

1.G.I.wire:-wire will be arranged by the contractor himself.

2.Accounting system will be same as is being followed as per present practice.


Executive Engineer,
N.H.Division,HP.PWD,
Rampur Bsr.


Schedule of Quantity

Name of work:- A/R & M/O on NH-05 Km 236/00 to 368/00. (SH:-Construction of R/wall in P.C.C. at RD 282/880 to 282/887 & V- shape Drain at Km m287/425 to 287/570)				Estimated Cost:- 478750.00		
				Earnest Money 9600.00		
				Time :- Two Month		
S.No.	Descriptions	Quantity	Rate		Unit	Amount
			In figure	In words.		
1	Cutting in earth work in all kinds of soils such as pick work, jumper work, soft and hard rock i.e. chiselling and wedging out of rock if required and saturated soils and their intermediate classifications in all heights and depths. Stacking the useful stone/materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges including loading of truck for carrying the unserviceable materials. Any loss of public/private property during the course of execution shall be the sole responsibility of the contractor which shall have to be duly compensated by him at his own cost in all cases, the work shall be carried out as per clause 301 of section 300 of MORTH specifications to the entire satisfaction and direction of Engineer-in-Charge.	11.20 Cum			Per cubic meter.	
2	Earthwork in excavation for structures in all depths as per drawing and technical specifications as per Clause 304 of section 300 of MORTH specifications in all kinds of soils i.e. pick work, jumper work, blasting work in soft and hard rock and intermediate classifications of soil including chiselling and wedging out of rock with in all depths and heights, stacking the useful materials and disposal of unserviceable materials upto the identified dumping site as per the direction of the Engineer-in-Charges with in all leads and lifts. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	39.50 Cum			Per cubic meter.	

3	Providing and laying mechanically mixed and vibrated cement concrete M-15 containing minimum contents of cement is 5.50 bags per cum in all heights and depth as per drawing and technical specifications in foundation of retaining walls complete as per MORTH specification No.1500,1700 & 2100 including carriage of all materials within all leads and lifts with all modes of transportation and equipment and cost of formwork required to complete the work to the satisfaction of the Engineer-in-Charge.	73.08 Cum.			Per cubic meter.	
4	Providing and laying 100mm diameter (Hundred milimeter) P. V.C. pipe in weep holes in R/wall in requisite slopes for drainages as per the direction of the Engineer-in-charges including carriage of materials in all leads and lifts with mechanical means.	17.50 Rmt.			Per Running meter	
5	Providing and laying back filling behind Retaining walls satisfying the requirement as per drawing and technical specifications in all heights and depths compacted to a firm condition complete including carriage of materials by mechanical transport in all leads and lifts and as per direction of the Engineer-in-Charge.	10.08 Cum.			Per cubic meter.	
						Total Rs:-

Note:-Contractor will himself arrange the following materials:-

- 1.Cement:-To be purchased from H.P. State Civil Supplies Corporation.
- 2.Accounting system will be same as is being followed as per present practice.


Executive Engineer,
N.H.Division,HP.PWD,
Rampur Bsr.