



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22 *14829-29*

Dated *11-02-2022*

To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity
And "A" Certificate**

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

[Signature]
Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140
Fax No. 01904-255740




NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD, for the following works, so as to reach this office on **19.02.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 a.m. in presence of the interested contractors or their authorized representative. The tender form can be had from the office of Executive Engineer Outer Seraj Division HP.PWD, Nirmand on cash payment (Non- refundable) on or before **18.02.2022** during office hours till 1.00 p.m. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued . The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected .The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money (in Rupees)	Time	Cost of tender form Rs.
1	Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MNP. (SH: Formation cutting 5/7 mtr wide road in Km. 0/705 to 0/810).	422755.00	10000.00	Three months	350/-
2	Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MNP. (SH: Formation cutting 5/7 mtr wide road in Km. 0/810 to 0/930).	473098.00	10000.00	Three months	350/-
3	Improvement of identified black spots by providing corrective measures on various roads under Nirmand Sub-Division. (SH:- Providing and supplying intesty Engineering grade prismatic sheeting at various roads).	498600.00	10000.00	One month	350/-

4	Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MNP. (SH: Formation cutting 5/7 mtr wide road in Km. 0/930 to 1/105).	456660.00	10000.00	Three months	350/-
5	Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MNP. (SH: Formation cutting 5/7 mtr wide road in Km. 1/105 to 1/240).	453906.00	10000.00	Three months	350/-
6	Construction of link road from Deori to Burjikhad Km. 0/00 to 2/500 under MNP. (SH: Formation cutting 5/7 mtr wide road in Km. 1/240 to 1/360).	484923.00	10000.00	Three months	350/-

HIM SUCHANA AVAM JAN SAMPARK


Executive Engineer
Outer Seraj Division
H.P RWD, Nirmand
on behalf of Governor of Himachal Pradesh



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140
Fax No. 01904-255740

Certificate

**Certified that the tenders called vide this
Office letter No.-PW/OSDN/TA/Tender-NIT/2021-22- 14819-29 dated
11.02.2022 is very urgent nature. So may be uploaded on Departmental
website in public interest please.**


**Executive Engineer
Outer Seraj Division
H.P.PWD, Nirmand
on behalf of Governor of Himachal Pradesh**

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/705 to 0/810)					Estimated cost:-	422755.00
					Earnest Money	10000
					Time	Three months
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 240.99 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1702.05	Cubic Metre			
Total in Figures						


 Executive Engineer.
 Outer Serai Division.
 HPPWD, Narmad.

2

Schedule of quantity						
Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/810 to 0/930)				Estimated cost:-		473098.00
				Earnest Money		10000
				Time		Three months
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 270.53 cum. In all cases. @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1763.25	Cubic Metre			
Total in Figures						


 Executive Engineer,
 Outer Section Division,
 HPPW Dehradun

Schedule of Quantity

NAME OF WORK:- Improvement of identified black spots by providing corrective measures on various roads under Nirmand Sub-Division.
(SH:- Providing and supplying intensity Engineering grade prismatic sheeting at various roads.)

Estimated Cost: - Rs. 498600.00
Earnest Money: - Rs. 10000.00
Time: -One Month

Sr. No	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing and supplying high intensity engineering grade prismatic sheeting on the front side of existing W-metal beam crash barrier of size 300x450mm (Three hundred into four hundred fifty millimetre) in yellow and white colour at site within all leads and lifts as per direction of Engineer-In Charge complete in all respect.	450.00	Per Running Metre			


Executive Engineer,
Outer Serai Division,
HP.PWD, Nirmand.

4

Schedule of quantity						
Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/930 to 1/105)				Estimated cost:- Earnest Money		456660.00
				Time		10000
				Three months		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	
					Words	AMOUNT
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 260.60cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1798.30	Cubic Metre			
Total in Figures						

Executive Engineer,
Outer Sersa Division,
HPPW, Noida

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/105 to 1/240)					Estimated cost:- Earnest Money 10000 Three months		453906.00
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT
					Words	Time	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 258.62 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on pro rata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1847.25	Cubic Metre				
Total in Figures							


 Executive Engineer,
 Outer Seral Division,
 HPPWD, Demand.

Schedule of quantity

Name of Work: Construction of link road from Deorikhad to Burjikhad km. 0/00 to 2/500 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 1/240 to 1/360)					Estimated cost:-	484923.00
					Earnest Money	10000
					Time	Three months
Sl. No.	Description of work	Qty.	Unit	Figures	RATE	AMOUNT
					Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 275.88 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor. which shall have to be duly compensated by him in all cases.	2041.35	Cubic Metre			
Total in Figures						


 Executive Engineer,
 Outer Service Division,
 HPPW/17 Armand.