

Himachal Pradesh
Public Works Department
No. PW-SD-1-CTR- Tender-NIT/2021-22- 24283-84 Dated:- 31/7/22

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice
Inviting tender for uploading on department website as per notification Pt. Secy. (PW) to the Govt. of
Himachal Pradesh letter No. PBW/ (B/A(3)1/2020 dated Shimla-2 the 16th July 2021 as the works
mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
Shimla Division No-1,
HPPWD, Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
Shimla Division No-1,
HPPWD, Shimla-3.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

1. Date of receipt of application for tender forms:- 11-2-2022 upto 4:00 PM
2. Dated of issue /sale of tender forms:- 14-02-2022 upto 4:00 PM
3. Date of receipt of tender:- 15-02-2022 up to 10:30 AM
4. Date of opening of tender:- 15-02-2022 up to 11:00 AM

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O various roads under sub Division No. VIII Kasumpti Shimla-9 (SH- Removal of solidified snow by manual labour).	58343/-	1200/-	350/-	60 days	Class-D
2	Improvement of Black spot in various roads under Sub Division Mashobra (SH)- Providing and fixing of typical Sign board, 200 mtr stone in road from cheeg to Dharech km. 0/00 to 6/00 Dharech Juggar khagna km. 0/00 to 8/720).	99076/-	2000/-	350/-	30 days	Class-D
3	(i) Restoration of rain Damages on Shelonbag Darthog road km. 0/00 to 6/00 (SH)- Hitting of ICB for removal of slips in km. 0/00 to 6/00 (ii) Restoration of rain damages on Janedghat Dublu road km. 0/00 to 15/00 (SH)- Hiring of ICB for removal of slips in km. 0/00 to 8/00).	270000/-	5400/-	350/-	As and when required	Class-D
4	Construction of water storage tank stand in Govt. residential (GAD) colony Mehil Kasumpti Shimla (SH- C/O water storage tank stand set No.1 to 8 type-II M1 Kasumpti Shimla).	327473/-	6600/-	350/-	60 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/firm who fulfil the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnst Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic/ conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/Firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.

No. PW-SD-I/CB-Tender/21-22-
Copy forwarded to :-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-II HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM / DAO.
9. Notice Board.

24288-301

Executive Engineer,
Shimla Division No-I,
HPPWD, Shimla-3.
Dated :- 8/2/22

Executive Engineer,
Shimla Division No-I,
HPPWD, Shimla.

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.									
Name of Work :- A/R & M/O various roads under Sub-Division No.VIII Kasumpti Shimla-9 (SH: Removal of solidified snow by manual labour)									
Time:- 60 Days.									
Estimated Cost:- 58,343.00		Earliest Money :- 1,200.00							
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate	In figures	In words	Unit	Amount	
1	Removal of snow: Removal of Snow from road surface height upto 1.5 metres including carriage of materials in all leads and lifts as per directions of the Engineer in-Charge.	225.00		Cum			Per Cubic Metre	Total	

Executive Engineer,
Shimla Division No.1,
H.P.P.W.D Shimla-3.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,076.00	
Name of Work :- Improvement of Black spot in various roads under Sub-Division Mashobra (SH :- Providing and Fixing of typical PMGSY board, KM stone, 200 mtr. Stone in road from Cheeg to Dharech Km. 0/00 to 6/000, Dharech Juggar Khagna Km. 0/00 to 8/720).						Earnest Money :- 2,000.00	
						Time:- 30 days.	
Sr.N o.	Description	Qty.	Rates in			Unit	Amount
			Figs	Words			
1	2	3	4	5	6	7	
1	Reinforced cement concrete M15 brand grade kilometre stone/ ordinary Kilometer stone(Precast) local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge.	10.00	Nos			Each	
2	Reinforced cement concrete M15 brand grade KM stone 5th km stone fixed in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 including carriage of material with in all leads and lifts as per the direction of Engineer-in-Charge.	4.00	Nos			Each	
3	Providing and fixing of typical informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm (One point six millimetre) thick, top and middle plate duly welded with MS flat iron 25mm x 5m (Twenty five millimetre into five millimetre) size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm (Twenty five millimetre into Twenty five millimetre into five millimetre). The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 (Two) nos. 75mm x 75 mm (Seventy five millimetre into Seventy five millimetre) of 12 (Twelve) SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, 600mm (Four hundred fifty millimetre into Four hundred fifty millimetre into six hundred millimetre into six hundred millimetre) below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm (forty seven millimetre into forty seven millimetre) of 12 (twelve) SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause 1701 and Annexure 1700.1 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Nos			Per Each	
4	Reinforced cement concrete M15 grade kilometre stone/local stone of standard design as per IRC:8 fixing in position including painting and printing, etc as per drawing and Technical Specification Clause 1703 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (ii) 200 m (Two hundred millimetre) stone (precast)	11.00	Nos			Per Each	
						Total	

Executive Engineer,
Shimla Division No.1,
H.P.P.W.D. SHIMLA-3.

SCHEDULE OF QUANTITY						
Name of work: - (i) Restoration of Rain damages on Shelonbag Darbhog road Km. 0/00 to 6/00 (SH:-Hiring of JCB for removal of Slips in Km. 0/00 to 6/00) (ii) Restoration of Rain damages on Janedhat Dublu road Km. 0/00 to 15/00 (SH:-Hiring of JCB for removal of Slips in Km. 0/00 to 8/00)		Estimated Cost: -Rs 2,70,000/-only Earnest Money : Rs 5,400/-only Time - As and When required				
		Qty.	Rate	In words	Unit	Amount
1	2	3	In figure		6	7
Hiring of exxcavater -cum-loader for removal of snow debris and dressing of berms including cost of fuel oil, lubricants , wages of operational staffs any repair package during operation will be carried out at his risk ands cost including carriage of machinery from one place to another at required locatiopn. Actual working will be accounted for payment and proper disposal slips debries by contractor will be insured and including all leads and lifts work shallcarriage of materials upto all leads and lifts and as per direction of Engineer-in-Charge.		270.00	Hour		Per hour	
					Total:-	

Executive Engineer
Shimla Division No-1
H.P.P.W.D, Shimla-3

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.				Estimated Cost:- 3,27,473.00	
Name of Work :- Construction of Water storage Tank stand in Govt. residential(GAD) colony Mehli Kasumpti Shimla (SH: C/O Water storage tank stand set No.1 to 8 Type-II M1 Block Mehli Kasumpti Shimla)				Earnest Money :- 6,600.00	
				Time:- 60 Days.	
Sr. No	Description of Work / Item (S)	No. of Qty.	Estimated Rate	Unit	Amount
1	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2151.57	Kg.	Per Kilo-gram	
2	Providing and fixing M.S. welded mesh 25mmx25mmx3mm thick as per approved design welding with electric plant complete including applying priming coat of red lead paint as per HP PWD Specification 1990 Volume-1 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	62.38	Sqm	Per Square Metre	
3	Providing and fixing ISI marked oxidised M.S. pressed butt hinges with necessary screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)125x65x2.12 mm	30.00	Nos	Each	
4	Providing and fixing 0.60mm thick preprinted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns rimer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with preprinted iron J or L hooks, bolts and nuts 6mm dia metre with preprinted limpet and rubber washers omplete with all accesories as required as per the direction of Engineer-in-charge.	14.35	Sqm	Per Square Metre	
5	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)15 mm dia nominal bore	204.71	Rmt	Per Running Metre	
6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	117.29	Sqm	Per Square Metre	
				Total	

Executive Engineer,
Shimla Division No.1,
HP PWD Shimla-3.