

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tenders are hereby invited by Executive Engineer, NH Division, HP.PWD, Solan on behalf of Governor of Himachal Pradesh for the following works from the approved registered Contractors of appropriate class (D) enlisted with Himachal Pradesh Public Works Department, whose registration stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:-

	Tender Schedule	Date	Time
1.	The last date for receipt of application for tender Form.	10/2/2022	4.00 PM
2.	The last date for issue of tender Form	11/2/2022	4.00 PM
3.	The last date for receipt of tender.	14/2/2022	10:30 AM
4.	The date of opening of tender.	14/2/2022	11:00 AM

The tender forms can be obtained against payment of Rs.350/- (Non refundable) and contractor will be required to produce documents of registration in appropriate class, list of completed works and sales tax registration certificate. The tenders shall be opened in presence of contractor or their authorized representative.

The earnest money in shape of National Saving Certificate/Time deposit account of nationalized saving or Saving Bank account in any of the post offices and F.D.R. of Nationalized Bank duly pledged in favour of the Executive Engineer, NH Division, HP.PWD, Solan must accompany with the tender offer. The exemption from depositing the earnest money with each tender earlier granted has been withdrawn under Govt. Notification No. PWE (B&R)(B)14(18) / 98-11 dated 4.11.2003 and accordingly the tender received without assigning any reasons thereto shall not be entertained.

The tenders will be issued only to them who qualify the criteria after the scrutiny of application Form. The tenders not accompanying the Earnest money shall be rejected at the time of opening. The contractor shall also indicate the detail of Earnest money in the tender document. The request on prescribed application should accompany the registration of appropriate class, sales tax registration No. work done certificate. The tenders shall be opened on schedule date and time in presence of contractor or in the presence of the authorized representative.

The validity of tenders has been given in the tender document. If any contractor/firm withdrawn the offer within validity period then their earnest money shall be forfeited and shall finally be at the disposal of State Govt. The contractors are advised to write the rates both in figures and in words, failing which the tender shall be rejected.

Conditional and incomplete tenders shall out rightly be rejected.

Application for obtaining the tender form must accompany the latest renewal of enlistment and proof of CST No/NOC from Excise and Taxation Department regarding Sale Tax clearance. The offer shall be kept open for 120 days.

If due to any unforeseen reasons the office of the Executive Engineer, NH Division, HP.PWD, Solan remain closed on the notified date of sale and receipt of tender, the tender will be sold and received/opened on next working day of same specified time.

The Executive Engineer reserves the right to accept or reject the tender without assigning any reason

Description of JOB:-

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time
1	C/O Steel frame structure shed for now clearance and deicing development construction of Calcium Chloride Brine making simple machine at Chabara store at km 159/820 on NH 22 (New NH 05) (SH- Providing and fixing pre coated galvanized sheet, flooring, providing and fixing sintex tank and water supply)	394981/-	8000/-	Three months

Term and Conditions:-

The contractor will have to produce following documents and attached attested copies of the same at the time of submitting application for issue of tender Form.

- Enlistment/renewal in appropriate class in HP.PWD.
- PAN Card issued by the Income Tax Department.
- Statement showing the ongoing works in HP.PWD.
- E.P.F registration.

Certified that the above work is of emergent nature in exigency of Public Interest.

Executive Engineer,
Solan NH Division,
HP.PWD., Solan.

No. NHD/CB/TA/NIT/2022-

5447-88

Dated:- 04/02/2022

Copy forwarded to the following for information and necessary action:-

- 1.The Engineer-in-Chief, HP.PWD, Shimla.
2. The Chief Engineer, NH, HP.PWD, Shimla.
- 3.The Chief Engineer,(South), HP.PWD, Shimla.
- 4.The Chief Engineer,(North), HP.PWD, Dharamshala.
- 5.The Chief Engineer,(CZ), HP.PWD, Mandi.
- 6.All the Superintending Engineer, in HP.PWD,
7. All the Assistant Engineers under this Division.
8. Notice Board.
9. The Executive Engineer, IT Cell in the o/o Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Solan NH Division,
HP.PWD., Solan.

Estimated Cost Rs.394981/-only

SCHEDULE OF QUANTITY Earnest Money Rs. 8000/-only

Time:- Three Months

NAME OF WORK :- C/O Steel frame structure Shed for Snow Clearance and Deicing Development construction of Calcium Chloride Brine Making Simple machine at Charbara store at Km 159/820 on NH-22 (New NH 05) (SH:- Providing and fixing Pre-coated galvanised sheet, flooring , providing and fixing sintex tank and water supply etc.

Sr.No.	Description of Items.	Quantity	Rate in Figures	Rate in Words	Unit	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : In 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	4.57 cum			Per cum	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : In 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	3.04 cum			Per cum	
3	Providing and laying Brick flooring with bricks of class designation 7.5 on a bed of 12 mm cement mortar, including filling the joints with same mortar, with common burnt clay non modular bricks: In 1:6 (1cement : 6 coarse sand) including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	30.48 Sqmt.			Per Sqmt.	

4	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.60 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	136.84 Sqmt.			Per Sqmt.	
5	Providing and finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete : On steel work including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	158.12 Sqmt.			Per Sqmt.	
6(a)	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, Sintax IS : 12701 marked, double layer water tank 1000 ltr capacity (6*1000) = 6000 ltr with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including cutting to size and shape wherever required including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	6.00 Nos			Each	
b)	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, Sintax Chemically storage tank IS : 12701 marked, double layer water tank 1000 ltr capacity with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	1.00 No.			Each	

c)	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, Sintax Chemically storage tank IS : 12701 marked, double layer water tank 500 ltr capacity with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	1.00 No.			Each	
7	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work : Exposed on wall 15mm dia nominal bore including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	38.00 Rmt			Per rmt	
8	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 15mm nominal bore including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	1.00 No.			Each	
9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge: External Work					
a)	25mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	18.40 rmt			Per rmt	
b)	20mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	30.40 rmt			Per rmt	
c)	32mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	9.70 rmt			per rmt	
10	Providing and fixing unplasticized polyvinyl chloride (UPVC) pipes, accessories Union) having thermal stability for hot & cold water supply including all UPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step UPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. (Jindal UPVC Pipe)					

a)	25mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	4.00 Nos			Each	
b)	20mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	6.00 Nos			Each	
c)	32mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	2.00 Nos			Each	
11	Providing and fixing unplasticized polyvinyl chloride (UPVC) pipes, accessories (Stop Cock/Ball Valve) having thermal stability for hot & cold water supply including all UPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step UPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. (Jindal UPVC Pipe)					
a)	25 mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	3.00 Nos			each	
b)	20mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	6.00 Nos			each	
c)	32mm dia including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	2.00 Nos			each	
12	Providing and fixing 10 Gauge weld mesh of size 50mm x50 mm for floor/roof slab concrete screed over the micro beams as reinforcement. The weld mesh shall be fixed as per drawing including all leads, lifts and carriage of materials as per the direction of Engineer-in-Charge.	16.80 Sqmt.			per sqmt.	
					Total	

Executive Engineer,
NH Division, RRPWD
Solapur