

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed items rate tender on form 6&8 are invited by the Executive Engineer HPPWD Kotla Behar Division Kotla Behar for the following works from the approved and eligible contractors enlisted with HPPWD Department so as to reach in this office on dated 05.04.2022 up to 10.30AM and the same will be opened on the same day at 11.30 AM in the presence of contractors /firms or their authorized representative. The application for purchase of tender forms will be received up to 2.00 PM on dated 04.04.2022 and tender forms can be obtained from this office against cash payment (nonrefundable) on 04.04.2022 (5.00) and no tender form shall be issued by the post. The amount of earnest money in shape of FDR of any nationalized bank in HP duly pledged in the Name of Executive Engineer HPPWD Kotla Behar Division Kotla Behar

The conditional tender and tender received without earnest money (FDR) will be rejected and if holiday declared by the Govt. on the above date due to any reasons the tender shall be received and opened on the next working day. The undersigned reserved the right to rejected tender without assigned any reasons, .

Sr No	Name of work	Estimated cost	Earnest money	Time Limit	Cost of tender form	Form No
1	Repair of Type -II Quarter at CHC Dada Siba Tehsil Dada Siba Distt Kangra (H.P)(SH :- Repair of Door window plastering etc)	384848	7700	Two Month	350	6&8
2	A/R & M/O Various Roads Under HPPWD Sub Division Dada Siba (SH:- Repair of pot holes in kotla Section)	499298	7520	Two Month	350	6&8
3	A/R & M/O Various Roads Under HPPWD Sub Division Dada Siba (SH:- Repair of pot holes in Section Dada Siba -II)	499298	7520	Two Month	350	6&8

1) Certified that tender of above works are being called in Exigency of public interest ,

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

NO.PWD/KB/CB/TENDER 2020-21

9363-9370

DATED 21.3.2022

Copy to the F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla -2 for favour of information please.

Copy to the Engineer-in-Chief HPPWD Shimla for information please.


Copy to the Chief Engineer (KZ) HPPWD Dharamshala for favour of information please.

Copy to the Superintending Engineer 9th Circle HPPWD Nurpur for favour of information please.

Executive Engineer,
Kotla Behar Division HPPWD.,
Kotla Behar

CERTIFICATE

Certified that tenders called vide this office Notice No PWD/KB/CB/Tender
-2021-22 - 9363-9370 dated 21.4.2022 for 3 No.s Job is hereby invited without press notice
due to exigencies / emergency of work in the public interest


Executive Engineer
Kotla Behar Division
HPPWD Kotla Behar

BILL OF QUANTITY

Estimate Cost :- Rs. 3,84,848/-

Earnest Money :-Rs. 7700/-

Time Limit :- Two Months.

Name of work: Repair of Type-II quarter at CHC Dada Siba, Tehsil Dada Siba, District Kangra HP (SH: Repair of door windows, Plastering etc.)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking upto any lead, lift and other incidentals as per direction of the Engineer-in-Charge. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	15.00 Number			Each	
2	Providing Sal wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length completed as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all lead, lift and other incidentals. (hold fast lugs or dash fastener shall be paid for separately) The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	0.80 Cubic metre			Per cubic metre	
3	Providing and fixing 35mm (Thirty five millimetre) second class teak wood panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all lead, lift and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	11.72 Square metre			Per Square metre	
4	Providing and fixing 35mm(Thirty five millimetre) thick Second class teak wood wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4mm (One decimal four) in both directions with wire of dia 0.63mm (Zero decimal six three millimetre), for doors, windows and clerestory windows with hinges and necessary screws complete as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all lead, lift and other incidentals. The rate is including Royalty, Malkhana, Octroi, GST, toll tax, sales tax or any other taxes imposed by the Government.	11.37 Square metre			Per Square metre	

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
5	Repairs to plaster of any thickness with cement mortar 1:4 (one cement isto four course sand) in patches of area 2.50 (Two decimal five zero) square meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	264.67 Square metre			Per Square metre	
6	Distemping (two or more coats) with oil bound washable distemper of approved brand and manufacture (Nerolac/Asian or equivalent make) and of required shade on un-decorated wall surfaces to give an even shade over and including a priming coat with distemper, primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth and carriage of materials within all leads, lifts and other incidental. The rate inclusive of Malkhana, Royalty, Octroi, toll tax, Sale Tax, GST or any taxes imposed by the Government.	1191.47 Square metre			Per Square meter	
7	Painting wood work Two or more coat with Dulux Multi Surface Paint of required shade, applied at the rate 0.90 ltr/10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied at the rate 0.75 ltr/10 sqm (Zero point seven five litre per ten square metre) of approved brand and manufacture as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	447.69 Square metre			Per Square meter	
	TOTAL					

Executive Engineer,
HPPWD Division,
Kotla Behar.

BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,298/-
 Earnest Money :- Rs. 7520/-
 Time Limit :- Two Months.

Name of work:- A/R & M/O various roads under HPPWD Sub Division Dada Siba (Sh: Repair of Pot Holes in Kotla Section)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1, and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Maikhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government. The rate is including Royalty, Maikhana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	2200.00 Square metre			Per Square metre	
	TOTAL					

Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar.

BILL OF QUANTITY

Estimate Cost :- Rs. 4,99,298/-
 Earnest Money :-Rs. 7520/-
 Time Limit :-Two Months.

Name of work:- A/R & M/O various roads under HPPWD Sub Division Dada Siba (Sh: Repair of Pot Holes in Section Dada-II)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (Twenty millimetre) thick pre-mix carpet and seal coat type B specification. Clause 1904.2, 503 and 508.1 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government. The rate is including Royalty, Malkana, Octroi, GST, toll tax, sale tax or any other taxes imposed by the Government.	2200.00 Square metre			Per Square metre	
	TOTAL					

Executive Engineer,
 Kotla Behar Division,
 HPPWD Kotla Behar