

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

No.-PW/OSDN/ Tender-NIT/2021-22 *19370-80*
To

Dated *31-03-22*

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind

Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity


**Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.**

Copy forwarded with its enclosure for information to :-


1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.


**Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand.**



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140

Fax No. 01904-255740

NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on **08.04.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on **07.04.2022** between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **07.04.2022** between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment / renewal/ exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money	Time	Cost of tender form Rs.
1	A/R & M/O various roads under Anni Sub-Division (SH:- Providing patch work on various roads under Anni section)	4,88,000/-	10,000/-	Two Months	350/-
2	A/R & M/O various roads under Anni Sub-Division (SH:- Providing patch work on various roads under Showad section)	4,88,000/-	10,000/-	Two Months	350/-
3	A/R & M/O road from Jn. of NAS to Jn. of LDCK road KM. 0/000 to 26/765 (SH:- Providing patch work between km. 0/0 to 14/0)	3,66,000/-	8,000/-	Two Months	350/-
4	A/R & M/O LDCK road KM. 0/0 to 48/420 and road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (SH:- Providing patch work on LDCK road between KM. 0/0 to 10/00 and road from Jn. of LDCK to Jn. of NAS road between km. 0/00 to 4/00)	2,28,750/-	6,000/-	Two Months	350/-

5	A/R & M/O Nore to Wazir Bowali road KM. 0/000 to 37/000 (SH:- Providing patch work between km. 0/00 to 11/00 and 20/00 to 25/00)	4,57,500/-	8,000/-	Two Months	350/-
6	A/R & M/O Wazir Bowali Mohali road KM. 0/0 to 26/00. (SH:- Providing patch work between km. 0/00 to 26/00)	4,57,500/-	10,000/-	Two Months	350/-
7	A/R & M/O various roads under Dalash Sub-Division (SH:- Providing patch work on various roads under Dalash Sub-Division)	2,28,750/-	6,000/-	Two Months	350/-
8	Construction of link road from Thandapani to village Sarahan km. 0/00 to 1/410) Under SCSP Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/705 to 0/810)	4,70,517/-	10,000/-	One Month	350/-
9	Construction of link road from Thandapani to village Sarahan km. 0/00 to 1/410) Under SCSP Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/810 to 0/885)	4,21,681/-	10,000/-	One Month	350/-
10	Construction of link road from Kailidhar to Bharguridhar km. 0/00 to 1/00 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/0 to 0/075)	4,99,716/-	10,000/-	One Month	350/-
11	Construction of link road from Kailidhar to Bharguridhar km. 0/00 to 1/00 under MNP. (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/075 to 0/210)	4,85,625/-	10,000/-	One Month	350/-

It is certified that the above tenders i.e Sr. No 1 to 11 are very urgent nature, So may be uploaded on department website in public interest


 Executive Engineer
 Outer Seraj Division
 H.P PWD, Nirmand
 on behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O various roads under Anni Sub-Division (SH:- Providing patch work on various roads under Anni section)				Estimated Cost:-488000.00	
				Earnest money:- 10000.00	
				Time:- Two months	
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	2440.00	Per Square Metre		


 Executive Engineer,
 Outer Sraik Division,
 HP.PWD. Kirmand.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O various roads under Anni Sub-Division (SH:- Providing patch work on various roads under Showad Section)				Estimated Cost:-488000.0	
				Earnest money:- 10000.00	
				Time:- Two months	
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	2440.00	Per Square Metre		Amount


 Executive Engineer,
 Outer Seraj Division,
 HP.PWD. Miranand.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O road from Jn. of NAS to Jn. of LDCK road K.M. 0/0 to 26/765. (SH:- Providing patch work between km. 0/00 to 14/00)					Estimated Cost:-366000.00	
					Earnest money:- 8000.00	
					Time:- Two months	
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	1830.00	Per Square Metre			


 Executive Engineer,
 Outer Survey Division,
 HP.PWD. Mandi.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O LDCK road KM. 0/0 to 48/420 and road from Jn. of LDCK to Jn. of NAS road km. 0/00 to 32/00. (SH:- Providing patch work on LDCK road between KM. 0/0 to 10/00 and road from Jn. of LDCK to Jn. of NAS road between km. 0/00 to 4/00)					Estimated Cost:-228750.00	
					Earnest money:- 6000.00	
					Time:- Two months	
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	1143.75	Per Square Metre			


 Executive Engineer,
 Outer Section Division,
 HP.PWD, Nirmand.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Nore to Wazir Bowali road KM. 0/0 to 37/00. (SH:- Providing patch work between km. 20/00 to 25/00 and 0% to 11/00)					Estimated Cost:-457500.00	
					Earnest money:- 10000.00	
					Time:- Two months	
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete. (Bitumen will be supplied by the department free of cost)	2287.50	Per Square Metre			


 Executive Engineer,
 Outer Seraj Division,
 HP.PWD-Namand.

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/O Wazir Bowali Mohali road K.M. 0/0 to 26/00. (SH:- Providing patch work between km. 0/00 to 26/00)

Estimated Cost:-457500.00
Earnest money:- 10000.00

Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Time:- Two months	
					Rate in words	Amount
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	2287.50	Per Square Metre			

20
Executive Engineer,
Outer Serai Division,
HP.PWD, Nirmand.

7

SCHEDULE OF QUANTITY						
NAME OF WORK:- A/R & M/O various roads under Dalash Sub-Division (SH:- Providing patch work on various roads under Dalash Sub-Division)						
Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Estimated Cost:-228750.00	
					Earnest money:- 6000.00	
					Time:- Two months	
				Rate in words	Amount	
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Bitumen will be supplied by the department free of cost)	1143.75	Per Square Metre			

20

Executive Engineer,
Outer Serai Division,
HP.PWD, Nirmand.

Schedule of quantity						
Name of Work: Construction of link road from Thandapani to village Sarahan km. 0/00 to 1/410) Under SCSP				Estimated cost:-		470517.00
Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/705 to 0/810)				Earnest Money		10000
Sl. No.	Description of work	Qty.	Unit	RATE		One month AMOUNT
				Figures	Words	
1.	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 399.87 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1729.97	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Sarai Division
 HPPWD, Noida

Schedule of quantity						
Name of Work: Construction of link road from Thandapani to village Sarahan		km. 0/00 to 1/410) Under SCSP				
Sub Head:- Formation cutting		5/7 mtr wide road in km. 0/810 to 0/885)				
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 368.74 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1550.41	Cubic Metre			421681.00
Total in Figures						10000
						One month


 Executive Engineer
 Outer Seral Division
 HPPWD, HPPWD

Signature of Tenderer with seal

10

Schedule of quantity						
NAME OF WORK:- Construction of link road from Kailidhar to Bharguridhar km. 0/00 to 1/00 under B-887 . (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/0 to 0/075)						
Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Figures	RATE	Amount
					Words	One month
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 286.60 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on porta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1719.60	Cubic Metre			499716.00
Total in Figures						10000
						One month
						AMOUNT

Executive Engineer
Outer Seraj Division
HPPWD, Nirmal

Signature of Tenderer with seal

Schedule of quantity

NAME OF WORK:- Construction of link road from Kailidhar to Bharguridhar km. 0/00 to 1/00 under PWD (Sub Head:- Formation cutting 5/7 mtr wide road in km. 0/075 to 0/210)					Estimated cost:- Earnest Money		485625.00
					Time		10000
					One month		
Sl. No.	Description of work	Qty.	Unit	Figures	RATE		AMOUNT
					Words		
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 304.68 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor. which shall have to be duly compensated by him in all cases.	1538.54	Cubic Metre				
Total in Figures							


 Creative Engineer
 Outer Survey Division
 HPPWD, Jalandhar

Signature of Tenderer with seal