

Himachal Pradesh  
Public Works Department

No:-PW/SRDD-CB-CTR-NIT/2021-22-  
To

23965

Dated:- 23 <sup>3</sup>/<sub>2022</sub>

✓ The Executive Engineer (IT Cell),  
H.P.P.W.D. Nigam Vihar Shimla-2.

**Subject:-**

**Notice Inviting Tender for uploading the same on  
departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT)  
of various works in respect of this office for uploading the same on departmental  
website.

**Encl:-Copy of NIT**

Executive Engineer  
Shimla Rural Division  
HPPWD Dhamsi

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Sealed item rate tenders on PWD Form 6 & 8 are hereby invited by the Executive Engineer, Shimla Rural Division, H.P.P.W.D. Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on before **06-04-2022 up to 11:00 AM** and the same shall be opened on the same day at **11:30 AM** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **05-04-2022 up to 4:00 PM** and the application for issue of tender form shall be received on **04-04-2022 up to 4:00 PM**.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer, Shimla Rural Division, HPPWD Dhami must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	C/o proposed 24 m span single lane RCC T-beam bridge on Thachi Rehana road over Sainj Khad (SH:- Proof checking of detailed design and structure drawings on minor bridge).	Rs. 1,50,000/-	Rs. 2,000/-	One Month	Rs. 350/-
2	Geotechnical investigation for construction of parking at Totu Shimla.	Rs. 4,87,500/-	Rs. 10,000/-	One Month	Rs. 350/-
3	Geotechnical investigation for construction of ROB on the land adjoining Shimla-Kalka railway line at ward No. Majiath, Municipal corporation Shimla.	Rs. 4,50,000/-	Rs. 9,000/-	One Month	Rs. 350/-
4	Geotechnical investigation for Construction of science learning and creativity Centre (SH:- C/o planetarium at Bhog, Anandpur).	Rs. 2,75,500/-	Rs. 5,600/-	One Month	Rs. 350/-
5	C/o Topographical Survey of Cafe at science technology at Shoghi (SH:- Preparation of Contour Plan).	Rs. 25,000/-	Rs. 500/-	One Month	Rs. 350/-
6	C/o Topographical Survey of Parking at Bailau gang (SH:- Preparation of Contour Plan).	Rs. 25,000/-	Rs. 500/-	One Month	Rs. 350/-
7	Geotechnical investigation for construction of ROB on the land adjoining Shimla-Kalka railway line at ward No. 7 Majiath, Municipal corporation Shimla (SH:- Topographical Survey of ROB and Road).	Rs. 99,000/-	Rs. 2,000/-	One Month	Rs. 350/-
8	C/o link road Devidhar to Sheedal via Ambri km. 3/00 to 5/500 & link road Bag to village Farinda km. 0/00 to 3/00 (SH:- Preparation of digital map/CA, FCA case and monitoring of MOEF portal).	Rs. 96,800/-	Rs. 2,000/-	One Month	Rs. 350/-
9	C/o link road Deolla Shayalti Heaven up to Village Sharoh km. 0/00 to 8/00 &	Rs. 96,800/-	Rs. 2,000/-	One Month	Rs. 350/-

	link road from Jajher to Barity km. 0/00 to 4/00 (SH:- Preparation of digital map/CA, FCA case and monitoring of MOEF portal).				
10	Improvement of Curves on Shimla Nalagrah road km. 7/00 to 22/00 (SH:- Improvement of Curves at Rd. 7/510 to 7/550).	Rs. 99,900/-	Rs. 2,000/-	One Month	Rs. 350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their **PAN** No., **GST** No., copy of **enlistment** renewed letter alongwith **FDR** against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer  
Shimla Rural Division  
H.P.P.W.D. Dharni

On behalf of Governor of Himachal Pradesh  
HIM SUCHNA AWAM JANSAMPARK

No: PW-SRDD-CB-CTR / 2020-21- 23966-75

Dated: 23/3/2022

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4<sup>th</sup> Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer  
Shimla Rural Division  
H.P.P.W.D. Dharni

### Certificate

Certified that the tenders called vide this office notice No.PW-SRDD-CB-CTR/2022- 23966-75 dated 23/03/22 for 10 number jobs is hereby invited without press notice due to exigencies/emergency of works in the public interest.

Executive Engineer,  
Shimla Rural Division,  
H.P.P.W.D. Dharni.



### Schedule Of Quantity

Name Of Work :- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION OF PARKING AT TOTU SHIMLA.

Estimated Cost:- 4,87,500  
Earnest Money:- 9800.00  
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate	In figures	In words	Unit	Amount
		3	4	5	6	7	8	
1	Sub soil investigation in all type of soil/ Strata by drilling bore holes of NX size ( 75 millimetre diameter) ranging from 10 metres or above in depth for investigation of soil/ rock conditions at site of work including mobilization and de- mobilization for drilling shifting of machinery to bore site making plateform and water arrangement for drilling. The scope of work includes preservation of core including relevant fields and laboratory tests and submission of geological report of complex site of work including cartage of materials within all leads and lifts as per the direction of Engineer - in - Charge.	65	Amt job				Per job Running rate	
	<b>Total Rs.</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, P.O., Dharmi.

### Schedule Of Quantity

Estimated Cost:- 2,75,500

Earnest Money:- 5600.00

Time:- One Months.

Name Of Work :- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION OF SCINCE LEARNING AND CREATIVITY CENTER (C/O PLANETARIUM AT BHOG, ANANDPUR)

S.No	Description of Work	No. of Qty.		Rate	In words		Unit	Amount
		3	4	In figures	6	7	8	
1	2							
1	Sub soil investigation in all type of soil/ Strata by drilling bore holes of NX size ( 75 millimetre diameter) ranging from 10 metres or above in depth for investigation of soil/ rock conditions at site of work including mobilization and de- mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant fields and laboratory tests and submission of geological report of complex site of work including carriage of materials within all leads and lifts as per the direction of Engineer - in - Charge.	33	Amt+ job			Per job running meter.		
2	preparation of digital Survey Contour plan with drawing complete in all respect in manuscript from and submission of the same to higher office for approval, If any correspondence/ ammendment has desired by this office as well as by head office, the same may be rectified as desired and directed by the Engineer in charge in all respect. After approval the same should be submitted in two set of fair drawing against asain if any coeception/ ammendment as desired by head office as per the direction of Engineer in charge complete. for the work.	1	job			Per job		
Total Rs.								

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dharmi. *Singh*

### Schedule Of Quantity

Name Of Work :- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION ROB on the land adjoining Shimla- Kalka Railway line at Ward No- Majiath, Municipal Corporation Shimla.

Estimated Cost:- 4,50,000  
Earnest Money:- 9000.00  
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate	In words		Unit	Amount
		3	4	In figures	6	7	8	
1	Sub soil investigation in all type of soil/ Strata by drilling bore holes of NX size ( 75 millimetre diameter) ranging from 10 metres or above in depth for investigation of soil/ rock conditions at site of work including mobilization and de- mobilization for drilling shifting of machinery to bore site making plateform and water arrangement for drilling. The scope of work includes preservation of core including relevent fields and laboratory tests and submission of geological report of complex site of work including carnage of materials within all leads and lifts as per the direction of Engineer - in - Charge.	60	Rmt. feet				Per feet Running Meter	
Total Rs.								

Executive Engineer,  
Shimla Rural Division,  
HP, RWD, Dhani. *[Signature]*

### DNIT/Schedule of Quantity

Name of work :- C/O link road Devdhar to Sheetal via Ambri Km 3/000 to 5/500 & Link road Bag to village Fairinda Km 0 000 to 3/000 (SH:- Preparation of digital map /CA, ICA case and monitoring of MOEF portal )

Estimated Cost: 96800/- only.  
Time :- One Month

S.No	Sub- Head and Item of Work	Qty	Rate		Unit	Amount
			In Figure	In word		
1	2		4	5	6	7
1	Preparation of FCA case of above proposed road in Suni Sub Division under Shimla Rural Division HP PWD Dhami with on line the case and monitoring of MOEF with preparation of five sets hard copy of folder and attending the all observation complete as per the direction of Engineer in Charge.	2.000				
2	Preparation of digital map of KML/SHF files with collection of data from site as per FCA guideline of MOEF proposed CA site with GPS coordinaters as per latest guidelines with collection the data from site of above proposed road with on line and monitoring of MOEF and attending the all observation complete as per the direction of Engineer in Charge.	2.000				
Total						96800.00

Draft Schedule of Quantity approved for Rs 96800/- Only (Rupees Ninety six thousand & eight hundred only at Sr No-1065----- Year 2021-22

  
Assistant Engineer  
HPPWD Sub Division  
Suni

  
HPPWD Dhami



## DNIT/Schedule of Quantity

**Name of work :-** Construction of Link road from Deolla Shyalti Heaven up to village Sharoh km 0/000 to 8/000 & C/O Link road from Jajher to Barity Km 0/000 to 4/000 (SH). Preparation of digital map /C.A. FCA case and monitoring of MOEF portal )

**Estimated Cost: 96800/- only.**  
**Time :- one Month**

S.No	Sub-Head and Item of Work	Qty	Rate		Unit	Amount
			In Figure	In word		
1	2	3	4	5	6	7
1	Preparation of FCA case of above proposed road in Suni Sub Division under Shimla Rural Division HPP PWD Dharni with on line the case and monitoring of MOEF with preparation of five sets hard copy of folder and attending the all observation complete as per the direction of Engineer in Charge.	2.000				
2	Preparation of digital map of KML/SHP files with collection of data from site as per FCA guideline of MOEF proposed C.A site with GPS coordinators as per latest guidelines with collection the data from site of above proposed road with on line and monitoring of MOEF and attending the all observation complete as per the direction of Engineer in Charge.	2.000				
<b>Total</b>						<b>96800.00</b>

Draft Schedule of Quantity approved for Rs 96800/- Only (Rupees Ninety six thousand & eight hundred only at Sr No 1004/----- Year 2021-22


**Executive Engineer**  
**Shimla Rural Division**  
**HPP PWD, Dharni**

**Assistant Engineer**  
**HPP PWD Sub Division**  
**Suni**



### Schedule of Quantity

Name of work : C/O proposed 24 m span single lane RCC T-beam bridge on Thachi Rehana road over Sainj Khad.(Sub head: Proof checking of detailed design and structure drawings of minor bridge)						Estimated Cost Rs 150000/-	
						Earnest money Rs. 2000/-only	
						Time :- One Month	
S.No.	Items of work	Qty.		Rate in		Unit	Amount
				in figure	in words		
1	Consultancy services for proof checking of detailed design, structural drawings of 24 m span RCC T-beam bridge from competent authority such as IIT, NIT or PEC in all respects and submitting the same to higher office for approval.	1.00	Job			Job	

  
**Executive Engineer**  
 Shimla Rural Division  
 HP PW Dhami

### Draft Schedule Of Quantity

Name Of Work :- Construction of Topographical Survey of Cafe at science Technology at Shoghi (SH:- preparation of Contour Plan)

Estimated Cost:-25,000.00  
Earnest Money:- 500.00  
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	preparation of digital Survey Contour plan with drawing complete in all respect in manuscript fromand submission of the samwe to higher office for approval, If any correspondence/ ammendment has desired by this office as well as by head office, the same may be rectified as desired and directed by the Engineer in charge in all respect. After approval the same should be submitted in two set of fair drawing against asain if any coececetion/ ammendment as desired by head office as per the direction of Engineer in charge complete. for the work.	1	Job			per Job	
Total Rs.							25000.00

DNIT Approved for Rs.25,000.00/-only for the year 2021-22 entered at DNIT  
Reg.S. No.....

Executive Engineer,  
Shimla Rural Division,  
HP, P.O.D, Dharmi: *[Signature]*

# DRAFT SCHEDULE OF QUANTITY

NAME OF WORK:- GEOTECHNICAL INVESTIGATION FOR CONSTRUCTION OF ROB ON THE LAND ADJOINING SHIMLA-KALKA ALLWAY LINE AT WARD NO-7 MAJIATH, MUNICIPAL CORPORATION SHIMLA (SH- TOPOGRAPHICAL SURVEY OF ROB AND ROAD)

				Estimated Cost : Rs	99000.00
				Earnest Money : Rs	2000.00
				Time Limit :	One Month
No	Description of Item	Quantity	Rate	Unit	Amount
			In fig.	In word	Per running meter
1	Preparation of Digital Contour survey plan and drawings in all respect and submission of the same to the higher office for approval. If any amendment has desired by the head office, the same may be corrected and directed by Engineer-in-charge in all respect. After the same should be submitted in two no set of fair draing again if any amendment as desired by head office.	1.00	NO		
Total:-					

DNT approved for Rs 99000/- only  
at R.R. No. 1017 for year 2021-22

Executive Engineer,  
Shimla Rural Division,  
H.P. PWD Dhani

## Schedule Of Quantity

**Name Of Work :- Construction of Topographical Survey of Parking at Bailau gang (SH:- Preparation of Contour Plan)**

Estimated Cost:-25,000.00

Earnest Money:- 500.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate	In words		Unit	Amount
		3	4	In figures	6	7	8	
1	preparation of digital Survey Contour plan with drawing complete in all respect in manuscript fromand submission of the samwe to higher office for approval. If any correspondence/ ammendment be rectified as desired as well as by head office, the same may all respect. After approval the same should be submitted in two set of fair drawing against asain if any coececetion/ ammendment as desired by head office as per the direction of Engineer in charge complete. for the work.	1	job			Per job		
<b>Total Rs.</b>								

Executive Engineer,  
Shimla Rural Division,  
HP, P.O.D, Dhani: 1511



### SCHEDULE OF QUANTITY

Name of work:- Improvement of curves on Shimla Nalagarh Road Km. 7/00 to 22/000 (Sh: Improvement of Curve at Rd. 7/510 to 7/550)

Estimated Cost: -Rs 99,900/- only  
Earnest Money : Rs 2000/-only  
Time- One Month

S.No.	Sub head and items of work	Qty.	In figure	Rate		Unit	Amount
				In words			
1	2	3				6	7
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required), the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of JW,one sixth of SR and one third of HR.= 27.75 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decrease in all cases recovered from the contracto @170/- (one hundred seventy only) per cubic metre shall be efaced any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	555.00	Cum			Per cubic metre	
						Total:	

Executive Engineer,  
Shimla Rural Division,  
HP  
D Dhami