

Himachal Pradesh
Public Works Department

Registered

No. PWN/CB/GA/E-27/Tender/2021-22- 7279
To


Dated:- 05/03/2022

The Executive Engineer (IT Cell),
Nigam Vihar Shimla.

Subject: - Publication of Tender Notice.

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting tender for uploading on department website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th, July 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA/As above.


Executive Engineer,
Nurpur Division, HP.PWD,
Nurpur.

**HPPWD
Tender Notice**

Sealed Item rates Tenders on PWD form 6&8 are invited by the Executive Engineer HP.PWD Nurgpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD (B&R), so as to reach in his office on or before **14/3/2022** up to 11.00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative, if any. The tender forms can be obtained from this office against cash payment non-refundable during the working hours on **11/03/2022** up to 4.00 PM and no tender form shall be issued by post. Application for issue of tenders should reach in the office along with all the required documents on or before **12/03/2022**. The earnest money in the shape of FDR of any nationalized Bank in H.P, duly pledged in the name of Executive Engineer, Nurgpur Divn. HP.PWD Nurgpur must accompany with the application. The conditional tender and tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserves the right to reject any tender without assigning any reason.

Sl. No.	Name of work	Estimated cost (Rs.)	Earnest money (Rs.)	Time limit	Cost of tender form (Rs)
1	2	3	4	5	6
1	Construction of road from Main road to village Bardi in G P Suliali (SH: Providing and laying G-I and G-II in km 0/0 to 0/600	471510/-	9500	One month	350/-
2	Construction of road from Main road to village Farundi in G P Loharpura (SH: Providing and laying G-I and G-II in km 0/0 to 0/425	333968/-	6700	One month	350/-
3	Construction of road from Main road to village Farundi in G P Loharpura (SH: Providing and laying G-I and G-II in km 0/425 to 0/850)	333968/-	6700	One month	350/-
4	Construction of road from bridge to Sanoh School in G P Mamun Gurchal (SH:- Providing and laying G-I and G-II in km 0/00 to 0/600)	471510/-	9500	One month	350/-
5	Construction of road from village Radui to Shamshanghat in G P Sadwan (SH: Providing and laying G-I and G-II in km 0/500 to 0/600 and tarring in km 0/0 to 0/350)	480035/-	9600	One month	350/-
6	Construction of road from village Radui to Shamshanghat in G P Sadwan (SH: Providing and laying G-I and G-II in km 0/600 to 0/700 and tarring in km 0/350 to 0/700)	480035/-	9600	One month	350/-
7	Construction of link road from Thathar to Sarnohu road in G P Sukhar (SH: Cement concrete Pavement in km 0/160 to 0/0/265)	477192/-	9500	One month	350/-
8	Construction of link road from Ram Leela Ground to Dhiman Mohalla road in G P Khanni Jhikli (SH: Cement concrete Pavement in km 0/0 to 0/114 Length= 114 mtr	496276/-	10000	One month	350/-
9	Construction of link road from Main road to Pandit Mohalla Mehkar in G P Rit Upparli (SH: Cement concrete Pavement in km 0/0 to 0/128) Length= 128 mtr	498010/-	10000	One month	350/-
10	Construction of link road from Main road to Pandit Mohalla Mehkar in G P Rit Upparli (SH: Cement concrete Pavement in km 0/128 to 0/256) Length= 128 mtr	498010	10000	One month	350/-
11	Construction of road from Raja Ka Bagh via Naglahar to village Charuri km 0/0 to 1/210 (SH:- Providing and laying G-I and G-II in km 0/350 to 0/500 and 0/560 to 1/060)	483698	9700	One month	350/-
12	Construction of road from Main road to village Chandrahan in Gram Panchayat Kandwal (SH:- Providing and laying G-I and G-II in km 0/0 to 0/650	499785	10000	One month	350/-
13	Construction of road from Main road to village Chandrahan in Gram Panchayat Kandwal (SH:- Providing and laying G-I and G-II in km 0/650 to 1/0 and 1/550 to 1/850)	499785	10000	One month	350/-

1. Certified that tender of above works are being called of emergent nature in Exigency of public interest.

Executive Engineer
Nurgpur Division, HPPWD,
Nurgpur.
For on behalf of Governor of HP

SCHEDULE OF QUANTITY

Name of work : Construction of road from Main road to village Bardi in G.P. Sudiali
 SH: Providing and laying G-I and G-II in km 0/0 to 0/600

Estimated cost Rs. 471510.00
 Earnest money Rs. 9500.00
 Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental or as per the entire specification and directions of Engineer-in-Charge.	316.58 cubic meter			Per cubic meter	
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	186.00 cubic meter			Per cubic meter	
3	Providing , laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres,, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	139.50 cubic meter			Per cubic meter	
4						


 Executive Engineer,
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

Name of work : Construction of road from Main road to village Farundi in G.P. Loharpura

SII: Providing and laying G-I and G-II in km 0/0 to 0/425)

Estimated cost Rs. 333968.00

Earnest money Rs. 7000.00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental or as per the entire specification and directions of Engineer-in-Charge.	263.50 cubic meter			Per cubic meter	
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	131.75 cubic meter			Per cubic meter	
3	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres,, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	98.80 cubic meter			Per cubic meter	


Executive Engineer,
Nurpur Division HPPWD
Nurpur

3

SCHEDULE OF QUANTITY

Name of work : Construction of road from Main road to village Farundi in G.P. Loharpura
 SI: Providing and laying G-I and G-II in km 0/425 to 0/850)

Estimated cost Rs. 333968.00
 Earnest money Rs.7000.00
 Time limit:- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental or as per the entire specification and directions of Engineer-in-Charge.	263.50 cubic meter			Per cubic meter	
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	131.75 cubic meter			Per cubic meter	
3	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres., to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	98.80 cubic meter			Per cubic meter	

Executive Engineer,
 Nurpur Division HPPWD
 Nurpur

9

SCHEDULE OF QUANTITY

Name of work : Construction of road from bridge to Sanoh School in G.P. Mamun Gurchal
 SH: Providing and laying G-I and G-II in km 0/00 to 0/600)

Estimated cost Rs. 471510.00
 Earnest money Rs.9500.00
 Time limit :- One month

Sr. No.	Description of items	Rate in		Unit	Amount
		Qty.	Figures Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental or as per the entire specification and directions of Engineer-in-Charge.	316.58 cubic meter		Per cubic meter	
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	186.00 cubic meter		Per cubic meter	
3	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres,, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	139.50 cubic meter		Per cubic meter	

Executive Engineer,
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

Name of work : Construction of road from village Radui to Shamshanghat in G P Sadwan

SH: Providing and laying G-I and G-II in km 0/500 to 0/600 and tarring in km 0/0 to 0/350)

Estimated cost Rs. 480035.00.00

Earnest money Rs. 9500.00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Loosening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental or as per the entire specification and directions of Engineer-in-Charge.	112.00 cubic meter			Per cubic meter	
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	31.00 cubic meter			Per cubic meter	
3	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres,, to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	23.25 cubic meter			Per cubic meter	
4	Providing and applying primer coat with bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer at the rate of 0.70 to 1.00 kg (zero point seven to one point zero kilogram) per square meter, using mechanical means as per technical specifications clause No. 502 including hauling of materials in all leads , lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	1085.00 square meter			Per square meter	

5	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor on the prepared surface of granular base treated with primer and including cleaning of road surface with hydraulic broom and spraying tack coat distributor at the rate of 0.25 to 0.30 kg. (zero point two five to zero point three zero kilogram) per Square metre using mechanical means as per technical specifications clause No. 503 including hauling of materials in all leads, lifts and as per entire satisfactions and directions of Engineer-in-charge including carriage of materials.. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1085.00 square meter			Per square meter
6	Providing and laying 30mm (thirty millimeter) compacted thick bituminous concrete with minimum 40-60 TPH (forty -sixty tonne per hour) hot mix Batch type/ Drum type plant with electronic control grading-II using crushed aggregate 13mm (thirteen millimeter) nominal size of specified grading premixed with bituminous binder VG-30 ((viscosity grade-thirty) @ 5.40 to 5.60% (five point four zero to five point six zero percent) of mix weight transported to site, laid with censor paver finisher hydraulic with censor control to the required grade, level and alignment over a previously prepared surface and rolling complete with smooth Wheel roller 8-10 (eight to ten) tonne capacity for initial break down rolling and vibratory roller 8-10 (eight-ten) tonne capacity or pneumatic tyre roller of 12-15 (twelve- fifteen tonne) with tyre pressure of atleast 0.56 MPa (zero point five six) for intermediate rolling and finish rolling with 6-8 (six to eight) tonne smooth wheeled tandem roller to achieve the desire compaction as per MORTH technical specification clause 509 including hauling of materials in all leads, lifts and as per entire satisfactions and directions of Engineer-in-charge including carriage of materials.. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	32.55 cubic meter			Per cubic meter
			Total		

Executive Engineer,
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work : Construction of road from village Radui to Shamshanghat in G.P. Sadwan

SH: Providing and laying G-I and G-II in km 0/600 to 0/700 and tarring in km 0/350 to 0/700)

Estimated cost Rs. 480035.00.00

Earnest money Rs.9500.00 ~

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in Figures	Words :-	Unit	Amount
1	Loussening leveling and compacting original ground upto a level of 300mm (three hundred millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight -ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental or as per the entire specification and directions of Engineer-in-Charge	112.00 cubic meter			Per cubic meter	
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	31.00 cubic meter			Per cubic meter	
3	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres,, to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	23.25 cubic meter			Per cubic meter	
4	Providing and applying primer coat with bitumen emulsion (SS-1) on the prepared surface of granular base including cleaning of road surface with hydraulic brooms and spraying primer at the rate of 0.70 to 1.00 kg (zero point seven to one point zero zero kilogram) per square meter, using mechanical means as per technical specifications clause No. 502 including hauling of materials in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	1085.00 square meter			Per square meter	

5	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor on the prepared surface of granular base treated with primer and including cleaning of road surface with hydraulic broom and spraying tack coat distributor at the rate of 0.25 to 0.30 kg. (zero point two five to zero point three zero kilogram) per Square metre using mechanical means as per technical specifications clause No. 503 including hauling of materials in all leads, lifts and as per entire satisfactions and directions of Engineer-in-charge including carriage of materials.. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1085.00 square meter			Per square meter
6	Providing and laying 30mm (thirty millimeter) compacted thick bituminous concrete with minimum 40-60 TPH (forty –sixty tonne per hour) hot mix Batch type/ Drum type plant with electronic control grading-II using crushed aggregate 13mm (thirteen millimeter) nominal size of specified grading premixed with bituminous binder VG-30 ((viscosity grade-thirty) @ 5.40 to 5.60% (five point four zero to five point six zero percent) of mix weight transported to site, laid with sensor paver finisher hydraulic with sensor control to the required grade, level and alignment over a previously prepared surface and rolling complete with smooth Wheel roller 8-10 (eight to ten) tonne capacity for initial break down rolling and vibratory roller 8-10 (eight-ten) tonne capacity or pneumatic tyre roller of 12-15 (twelve-fifteen tonne) with tyre pressure of atleast 0.56 MPa (zero point five six) for intermediate rolling and finish rolling with 6-8 (six to eight) tonne smooth wheeled tandem roller to achieve the desire compaction as per MORTH technical specification clause 509 including hauling of materials in all leads, lifts and as per entire satisfactions and directions of Engineer-in-charge including carriage of materials.. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	32.55 cubic meter			Per cubic meter
			Total		


 Executive Engineer,
 Nurpur Division HPPWD
 Nurpur

Name of work :-Construction of link road from Thathar to Sarnoh road in G P Sukhar (SH: Cement concrete Pavement in km 0/160 to 0/0/265)

SCHEDULE OF QUANTITY

Estimated cost Rs. 477192.00
Earnest money Rs. 9600.00
Time limit :- one month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	32.03 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement; two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	64.05 cubic meter			Per cubic meter	
				Total		

Executive Engineer
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY

Name of work :-Construction of link road from Ram Leela Ground to Dhiman Mohalla road in G P Khanni Jhikli
(SH: Cement concrete Pavement in km 0/0 to 0/114 Length= 114 mtr

Estimated cost Rs.496276.00
Earnest money Rs.10000.00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in Figures	Words	Unit	Amount
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres, to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres) sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental	29.93 cubic meter			Per cubic meter	
2	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	38.90 cubic meter			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in- charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	56.16 cubic meter			Per cubic meter	
				Total		

Executive Engineer
Nurpur Division HPPWD
Nurpur

9

SCHEDULE OF QUANTITY

Name of work :-Construction of link road from Main road to Pandit Mohalla Mehkar in G P Rit Upparli
(SH: Cement concrete Pavement in km 0/0 to 0/128) Length= 128 mtr

Estimated cost Rs. 498010.00
Earnest money Rs.10000 .00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental	28.46 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in- charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	84.48 cubic meter			Per cubic meter	
				Total		

Executive Engineer
Nurpur Division HPPWD
Nurpur

b

Name of work :-Construction of link road from Main road to Pandit Mohalla Mehkar in G.P Rit Upparli
(SH: Cement concrete Pavement in km 0/128 to 0/256) Length= 128 mtr

SCHEDULE OF QUANTITY

Estimated cost Rs. 498010.00
Earnest money Rs.10000.00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing, laying, spreading and compacting stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading -III 53mm to 22.4mm (fifty three millimetres to twenty two point four millimetres)sizes, 75mm (seventy five millimetres) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental.	28.46 cubic meter	1320.00	Rupees one thousand three hundred twenty only	Per cubic meter	37567.00
2	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete-as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in- charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	84.48 cubic meter	5400.00	Rupees five thousand five hundred only	Per cubic meter	307422.00
				Total		498010.00

Executive Engineer
Nurpur Division HPPWD
Nurpur

SCHEDULE OF QUANTITY


Name of work : Construction of road from Raja Ka Bagh via Naglahar to village Charuri km 0/0 to 1/210
(SH: Providing and laying G-I and G-II in km 0/350 to 0/500 and 0/560 to 1/060)

Estimated cost Rs. 483698.00

Earnest money Rs. 10000.00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters, at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interstices of coarse aggregate, watering and compacting to the required density grading - I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	214.50 cubic meter			Per cubic meter	
2	Providing . laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	160.88 cubic meter			Per cubic meter	


Executive Engineer,
Nurpur Division HPPWD
Nurpur

12

SCHEDULE OF QUANTITY

Name of work : Construction of road from Main road to village Chandrahan in Gram Panchayat Kandwal
(SH: Providing and laying G-I and G-II in km 0/0 to 0/650)

Estimated cost Rs. 483698.00
Earnest money Rs.10000.00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading – I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	214.50 cubic meter			Per cubic meter	
2	Providing . laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic metres) per ten square metres, to fill up the interspaces of coarse aggregate, watering and compacting to the required density grading –II, 63mm to 45mm (sixty three millimeters to forty five millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental .	160.88 cubic meter			Per cubic meter	

Executive Engineer,
Nurpur Division HPPWD
Nurpur

13

SCHEDULE OF QUANTITY

Name of work : Construction of road from Main road to village Chandrahan in Gram Panchayat Kandwal (SH: Providing and laying G-I and G-II in km 0/650 to 1/0 and 1/550 to 1/850)

Estimated cost Rs. 483698.00
Earnest money Rs. 10000.00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	214.50 cubic meter			Per cubic meter	
2	Providing . laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres,, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	160.88 cubic meter			Per cubic meter	

[Signature]

Executive Engineer,
Nurpur Division HPPWD
Nurpur