

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of applications for the tender Form a/w requisite documents: - 28.03.2022 upto 5.00 PM.
2. Date of issue /sale of tender forms against Cash payment (Non-refundable):- 29.03.2022 upto 4.00 PM.
3. Date of receipt of tenders: - 30.03.2022 upto 10.30 AM.
4. Date of opening of tenders: - 30.03.2022 at 11.00 AM.

Sr.No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	C/o & M/T of link road i/c Bridge to village Kadahe via Pipli from Jogipanga road km. 0/0 to 1/225 (SH: Filling from RD 0/0 to 0/048 in approach of Bridge	247105	5000	Two months	350/-	Class-D
2	C/o & M/T of link road i/c Bridge to village Kadahe via Pipli from Jogipanga road (SH: C/o Balance work of Bridge from RD 0/009 to 0/037.60)	499541	10000	Two months	350/-	Class-D

The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications.(The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand.The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.

Executive Engineer
Bangana Division
HPPWD Bangana.

No.PW/BGN/CB/T-1/2020-21-

15867-897

dated

19-03-22


Cop forwarded to the following for information anmd necessary action:-

1. The Engineer-in-Chief HPPWD. Nirman Bhawan Shimla.
2. All the Chief Engineer in HPPWD.
3. The Superintending Engineer, 15th Circle, HPPWD., Una.
4. All the Assistant Engineer, working under this Division.
5. The B.D.O. Bangana
6. Accounts Branch.
7. Drawing Branch.
8. Various Contractors working under this Division
9. Notice Board.


Executive Engineer,
Bangana Division,
HPPWD Bangana.

Certificate

Certified that the tenders called vide this office letter No. PW/BGN/CB/T-1/2020-21-15867-897 dated 19.03.2022 is emergent nature and in public interest.



Executive Engineer,
HPPWD Division
Bangana.



14

SCHEDULE OF QUANTITY

Name of work:- C/O & M/T of link road i/c Bridge to Village Kadahe via Pipli from Jogipanga road km 0/000 to 1/225 (Sh: Filling from Rd 0/000 to 0/048 in Approach of Bridge)

Sr. No.	Description of work	Quantity	Unit	RATE		AMOUNT
				Figures	Words	
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 and as per the direction of the Engineer-in-Charge, including carriage of material within all leads, lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1387.45	Per cubic metre			
Total in Figures						

Estimated Cost Rs 247105.00
Earnest Money Rs 5000.00
Time Limit: Two Month


Executive Engineer
Bangana Division
P.P.W.D. Bangana

SCHEDULE OF QUANTITY

Name of Work:- C/O & M/T of link road i/c Bridge to Village Kadahe via Pipili from Jogipanga road (SH:- C/O Balance work of Bridge from Rd 0/009 to 0/037.60)

Estimated Cost: 499541.00
Earnest Money: 10000.00
Time Limit: Two month

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs.
				Figures	Words	
1	Earth work in excavation for all type of road structure and all type of on classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) such as retaining walls, breast walls, culverts, drains and parapets etcetera as per drawings and technical specification clause 305.1 and as per direction of the Engineer- In – Charge including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	96.53	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and technical specification clause 800, & 1200 for nominal mix 1 : 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths and the cost of form work in retaining walls, breast walls etcetera as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	233.10	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred millimetre) dia PVC pipe make of (D-plast) / Finolex,) working pressure not less than 4.5 (four point five) kg/cm² extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	20.00	Each			
Total in Figures						

Executive Engineer
Bangana Division
P.P.W.D. Bangan