



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in Email:- ee-bsr-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW-BSR-E-105/2021-22-
To

19601-08

Dated:- 04/03/2022


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Barsar Division
HPPWD Barsar

Copy forwarded with its enclosures for information to:-

1. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
2. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Supdt of C Branch in this office.
6. Notice Board.


Executive Engineer
Barsar Division
HPPWD Barsar.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in Email:- ee-bsr-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041.


NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **11-03-2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **09-03-2022** upto 4.00 P.M. The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on or before **10.03.2022** during office hours till 1.00 P.M. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	C/O Link Road to Village Thankar (SH:- P/L Cement Concrete Pavement at RD 0/180 to 0/254) (Under D.D. Deposit).	Rs. 1,38,641.00	Rs. 2800.00	One Month
2	C/O Link Road from main Road Bahal to Majher Ward No. 5 (SH:- P/L Cement Concrete pavement at Rd. 0/0 to 0/30 & 0/142 to 0/249) (Under D.D. Deposit)	Rs. 2,56,636.00	Rs. 5200.00	One Month
3	C/O Link Road From Khurpari to Village Dasuha Km. 0/0 to 1/0 (SH:- Formation Cutting 5/7 mtr. Wide road from Km. 0/325 to 0/630) (Under OTMNP Head).	Rs. 2,44,936.00	Rs. 4900.00	One Month
4	A/R & M/O Divisional Office Building at Barsar (SH:- P/F AC Split Type 2.00 Ton and water Cooler etc)	Rs. 1,58,300.00	Rs. 3200.00	One Month
5	A/R & M/O PWD Rest House at Bhota (SH:- P/F PVC Water Storage Tank, C.C. Work and Brick Work etc).	Rs. 3,13,633.00	Rs. 6300.00	One Month
6	C/O Mangnoti to H.Basti Sohari Panderi Km. 0/0 to 1/700 (SH:- C/O B/Wall at RD. 0/310 to 0/325, 0/350 to 0/385, R/Wall at RD. 0/450 to 0/462 and Regrading of road at RD. 0/720 to 0/820) (Under SCSP Head).	Rs. 4,74,678.00	Rs. 9500.00	Two Months

7	C/O Link Road From Khurpari to Village Dasuha Km. 0/0 to 1/0 (SH:- Formation Cutting 5/7 mtrs wide road from Km. 0/0 to 0/315) (Under OTMNP Head).	Rs. 2,07,641.00	Rs. 4200.00	One Month
8	A/R & M/O Various Road under HPPWD Sub Division Barsar (Section Bhota) (SH:- Removal of Slips, Maintenance of Drain & Maintenance of Earthen Shoulder at Various Road at Various RDs).	Rs. 3,26,334.00	Rs. 6600.00	One Month
9	A/R & M/O Bridge Over Man Khad at RD 1/705 and Bridge Over Dugh Nallah at RD. 2/300 on Dhaneta Pansai Road (SH:- P/L 25mm thick mastic Asphalt Wearing Course and Painting of Bridge Railing etc)	Rs. 4,31,486.00	Rs. 8700.00	One Month
10	Restoration of Rain Damages on Panyali Kashmir Road to 0/0 to 5/00 (SH:- P/L interlocking Paver Block at RD. 1/800 to 1/918).	Rs. 4,67,643.00	Rs. 9400.00	One Month
11	Restoration of Rain Damages on Jalari Galore Salauni Road 0/0 to 17/00. (SH:- P/L interlocking paver block at Various RDs)	Rs. 4,55,283.00	Rs. 9200.00	One Month
12	A/R & M/O Various Road under HPPWD Sub Division Dhaneta (Section Kangoo) (SH:- Removal of Slips, Maintenance of Drain, Maintenance of Earthen Shoulders Various Road and Various RDs).	Rs. 4,56,644.00	Rs. 9200.00	One Month.
13	A & M/O HPPWD Rest House at Bhota (SH:- P/L Granite Stone Flooring and Dado in Stair Hall and Stair Steps etc).	Rs. 4,92,555.00	Rs. 9900.00	One Month
14	Improvement of Road Safety of Various Road Under HPPWD Sub Division Dhaneta. (SH:- Supply and Stacking a dual direction delineator).	Rs. 1,71,600.00	Rs. 3500.00	One Month

HIM SUCHANA AVAM JAN SAMPARK.



Executive Engineer

Barsar Division

HPPWD Barsar.


On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BSR-E-

105/2021-22-19601-08 dated 04/03/2022


Executive Engineer
Barsar Division
HPPWD Barsar.

Name of Work:- C/O link road to village Thankar

(SH:- Providing and laying cement concrete pavement at RD 0/180 to 0/254)

Under Deposit Head

Schedule of quantity

Job No-1

Estimated Cost Rs:- 138641.00

Earnest Money Rs:- 2800.00

Time Limit :-One Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive of octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	63.20		Cubic metre	Per Cubic Metre	
2	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802,803,1202&1203 as per direction of Engineer-in- Charge . including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	22.57		cubic metre	Per Cubic Metre	
3	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government	22.57		Cubic metre	Per Cubic Metre	
4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can prescribe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	16.93		Cubic metre	Per Cubic Metre	

[Signature]

Executive Engineer
Barsar Division
HPPWD Barsar

Job No-2

Estimated Cost Rs:- 256636.00
Earnest Money Rs:- 5200.00
Time Limit :-One Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing,removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	116.70	Cubic metre			Per Cubic Metre	
2	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802,803,1202&1203 as per direction of Engineer-in- Charge including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	41.79	cubic metre			Per Cubic Metre	
3	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government	41.79	Cubic metre			Per Cubic Metre	
4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can prescribe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred Kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	31.34	Cubic metre			Per Cubic Metre	
							Total:-

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity
Name of work:-C/O Link road from Khurpari to village Dasuha km 0/0 to 1/00
(SH:- C/O Formation cutting in km 0/325 to 0/630(under OTMNP Head)

Job No.-3
Estimated Cost Rs.-244936.00
Earnest Money Rs.-4900.00
Time Limit :- One Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T Figure	Unit	Amount
1	Excavation in hilly area in all heights and depths in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling/ wedging out of rock(where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D technical specification clause 1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all un-useful surplus material to required width of the road or on approved dumping sites by Engineer-in- Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools, equipment and safety measures and incidentals. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in- Charge including entire carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. A recovery of useful stone for 69.15 cum (Sixty Nine point fifteen) cubic metre @Rs300/-(Rupees three hundred) per cubic metre shall be done on pro-rata basis in each running bill form this item	2641.67 cubic metre		Per Cubic Metre	
				Total:-	


Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Job No 4

Name of work:-A/R&M/O Divisonal office building at Barsar

Estimated cost Rs:- 158300.00

(SH):- Providing and fixing AC Split Type 2.00 Ton and water cooler etc.

Earnest money Rs:- 3200.00

Time Limit :- One Month

Sr.No	Discription of item	Quantity	Rate in		Unit	Amount
			Figures	words		
1	Providing and fixing AC Split Type 2.00 (Two) Ton Lloyed (Havell) pipes stand as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, sale tax or other taxes imposed by the Government .	1.00	Numbers		Each	
2	Providing and fixing Voltas 80 litre (eighty litre) water cooler as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, sale tax or other taxes imposed by the Government .	1.00	Numbers		Each	
3	Providing and fixing water purifier HI flow as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, sale tax or other taxes imposed by the Government .	1.00	Numbers		Each	
					Total	

(Signature)

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of Work:- A/R & M/O PWD Rest house at Bhota

SH:- P/F PVC water Storage Tank, C.C work and brick work etc.)

Job No 5

Estimated Cost Rs:- 313633.00

Earnest Money Rs:-6300.00

Time Limit :- One month

Sr.No	Description of item	Figure	Rate	Unit	Amount
1	Excavation in foundation, trenches etcetera in all classification of soil such as pick work jumper work, pick jumper work blasting work and soft rock work in dry or saturated conditions upto any depth and lift including pumping and bailing out water where required including stacking the serviceable and unserviceable materials separately as directed and then returning the stacked soil in 15cm (fifteen centimeters) layers when required into plinth and sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus unserviceable excavated earth within all leads and lifts as directed by the Engineer-in-charge and including entire carriage of material in all leads and lifts disposed materials to be neatly leveled. The rates are inclusive of octroi, royalty malkana, toll tax, sale tax or other taxes imposed by the Government.	7.50	cubic metre	Per cubic metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	65.16	Cubic metre	Per Cubic Metre	
3	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax, GST or any other taxes imposed by the Government	63.00	Cubic metre	Per Cubic Metre	
4	Brick work using Second class common burnt clay buildings in super-structure above plinth level upto all floor level in cement mortar 1:6 (one cement : six sand) and curing complete including carriage of materials within all leads, lifts and other incidental, and as per directions of Engineer-in-Charge. The rate including Royalty, Malkana, Octroi, Toll Tax, GST or any other taxes imposed by the Government.	5.18	cubic metre	per cubic metre	
5	Providing and laying 15mm (fifteen millimeters) thick cement plaster in single coat on the rough side of brick concrete/stone walls for interior plastering upto all floor levels including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (Eighty millimeters) in girth and finished even and smooth in cement mortar 1:6 (One cement : Six sand) and curing complete as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts . The rate including Royalty, Malkana, Octroi, Toll Tax, GST or any other taxes imposed by the Government.	18.00	square metre	per square metre	
6	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including entire carriage of material in all leads and lifts . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	18.00	Square Metre	Per square metre	

7	Finishing wall with APEX exterior grade made of Nerolac , Berger, Asian paint of approved quality or its equalized on undecorated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt dust and other foreign matter etc. including sand paper smooth complete including entire carriage of material in all leads and lifts . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	280.00	square metre		per square metre
8	Distemping two coats with oil bound made of Nerolac , Berger, Asian paint washable distemper of approved brand and manufacture and of required shade on undecorated wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and sand papered smooth complete as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	18.00	square metre		per square metre
9	Steel work in single sections including cutting, hoisting, fixing in position and applying a priming coat of red lead paint In R.S.Joists, channels angles, tees including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	6.00	Per Quantal		per Quantal
10	Providing and fixing PVC storage tank made of sintex triple layer (ISI marked/ Treepal layer) 1000 litre (one thousand) litre with 40mm(forty millimeter) nominal size bore galvanized mild steel scour tube with fitting 25mm (twenty five millimeter) nominal bore galvanized mild steel over flow pipe with fitting and mosquito proof coupling of approved design 15mm(Fifteen millimeter) nominal bore ball valve and mosquito proof PVC cover with locking arrangement including providing pads to size are required and outlet to be including hoisting upto any height including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	1.00	numbers		each
11	Providing and fixing AMC, Unik , Diamond brass full way valve with wheel. 15mm(fifteen millimetre) nominal bore including entire carriage of material in all leads and lifts The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	2.00	numbers		each
12	Providing and fixing 15mm (fifteen millimetre) Nominal bore to wall ceiling and floor galvanized mild steel tube (light grade) tube fitting and clamps including making good the wall , ceiling and floor including entire carriage of material in all leads and lifts The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	20.00	metre		Per Metre
13	Providing and fixing 20mm (Twenty millimetre) Nominal bore to wall ceiling and floor galvanized mild steel tube (light grade) tube fitting and clamps including making good the wall , ceiling and floor including entire carriage of material in all leads and lifts The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	30.00	metre		Per Metre
14	Providing and fixing AMC, Unik , Diamond brass full way valve with wheel. 20mm(twenty millimetre) nominal bore including entire carriage of material in all leads and lifts. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	2.00	numbers		each
15	Supplying and fixing glass panes with putty and nails including removal of broken glass panes including carriage of material within all leads and lifts and other incidentals 4 mm (four millimetre thick) including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	3.60	Square metre		per Square metre

16	Removal of old broken glass panes (any thickness, size, quality or description) from metal frames including punching or drilling out old glazing pins, including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.60	per Square Metre		per Square metre
					Total



Executive Engineer
Barsar Division
HPPWD Barsar



Job No 6

Schedule of quantity

Name of Work:- C/O Mangnotti to Harizan Basti Sohari & Pandiri km 0/0 to 1/700
(SH:- C/O B/wall at RD 0/310 to 0/325 , 0/350 to 0/385 , R/wall at RD 0/450 to 0/462
& Regrading of road at RD 0/720 to 0/820) (under SCSF Head)

Estimated Cost Rs:- 474678.00
Earnest Money Rs:- 9500.00

Time Limit :- Two Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Excavation in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling/ wedging out of rock(where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line , grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D technical specification clause 1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all un-useful surplus material to required width of the road or on approved dumping sites by Engineer-in- Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries , materials , tools ,equipment and safety measures and incidentals . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in- Charge including entire carriage of materials within all leads and lifts . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	612.50 cubic metre			Per Cubic Metre	
2	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	64.86 Cubic metre			Per Cubic Metre	
3	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	191.30 Cubic metre			Per Cubic Metre	
4	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government	7.20 Cubic metre			Per Cubic Metre	

5	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	60.00 Numbers	Each	
			Total:-	9

Executive Engineer
Barsar Division
HPPWD Barsar

Job No:-7
Estimated Cost Rs:-207641.00
Earnest Money Rs:-4200.00
Time Limit :- one Month

Schedule of quantity
Name of work:-C/O Link road from Khurpari to village Dasuha km 0/0 to 1/00
(SH:- C/O Formation cutting in km 0/00 to 0/315) (under OTMNP Head)

Sr. No	Description of item	Quantity	Rates		Unit	Amount
			Figure	words		
1	Excavation in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D technical specification clause 1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful surplus material for filling in road ways, camber, embankments for grade improvements and disposal of all un-useful surplus material including head load or animal transport or mechanical means along Engineer-in-Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools, equipment and safety measures and incidentals. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including entire carriage of materials within all leads and lifts. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government. A recovery of useful stone for 27.40 cum (Twenty Seven point Fourty) cubic metre @Rs300/-(Rupees three hundred) per cubic metre shall be done on pro-rata basis in each running bill form this item	2348.61 cubic metre			Per Cubic Metre	
					Total	


Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:- A/R&M/O on various roads under HPPWD Sub Division Barsar (Section Bhota)
(SH:- Removal of slips, Maintenance of earthen shoulder & maintenance of drain at various road at various RDs)

Job No:- 8
Estimated Cost Rs:-326334.00
Earnest Money Rs:- 6600.00
Time Limit :- One Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Maintenance of earthen shoulder (filling with fresh selected soil making up less of material / irregularities on shoulder in design level by adding fresh approved selected soil and compacting it with appropriate equipment OMC upto a lead of 1000mts as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government .	12900.00 Square metre			Per square Metre	
2	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slopes and disposal all material upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	320.00 cubic metre			Per Cubic Metre	
3	Maintenance of Drain :- Maintenance of drain including erosion, repair clearing , cleaning reshaping regarding decending of side drain as well as catch water drain as per technical specification clause No 1907 including carriage of material and equipments in all leads and lifts with all mode of transport and as per the direction of Engineer-in- Charge. including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	7500.00 Running metre			Per running Metre	

Executive Engineer
Barsar Division
HPPWD Barsar

Name of work:-	Schedule of quantity
A/R&M/O bridge over Man Khad at RD 1/705 and Bridge over Dugh Nallah at RD 2/300 on Dhaneta Pensai road (SH)- Providing and Laving 25 mm thick mastic asphalt wearing course, painting of bridge railing etc.)	


Executive Engineer
Barsar Division
HPPWD Barsar

Job No:- 10
Estimated Cost Rs:-467643.00
Earnest Money Rs:- 9400.00
Time Limit :- One Month

Name of work:- Restoration of rain Damages on Panyali Kashmir road km 0/0 to 5/00
(SHI- ~~PH~~ interlocking paver block at RD 1/800 to 1/918)

Schedule of quantity

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words	Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	125.79	Cubic metre			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	48.38	Cubic metre			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can prescribe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	6.29	Cubic metre			Per Cubic Metre	
4	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 80 mm(Eighty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 NTC make including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana toll tax, GST or other taxes imposed by the Government	483.80	Square metre			Per Square Metre	
						Total:-	

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:- Restoration of rain Damages on Jalari Galore Salouni Bijhari Deotsidh road km 0/0 to 17/00
(SH:- P/L interlocking paver block at various RDs)

Job No:- 11
Estimated Cost Rs:-455283.00
Earnest Money Rs:- 9200.00
Time Limit :- One Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T Figure	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive of octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	144.48	Cubic metre	Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802.803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	33.60	Cubic metre	Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can persibe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802.803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	8.71	Cubic metre	Per Cubic Metre	
4	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 80 mm(Eighty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 NTC make including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	516.00	Square metre	Per Square Metre	
				Total:-	

Executive Engineer
Bansar Division
HPPWD Bansar

Job No:- 12
Estimated Cost Rs:-456644.00
Earnest Money Rs:- 9200.00
Time Limit :- One Month

Schedule of quantity
Name of work:- A/R&M/O on various roads under HPPWD Sub Division Dhaneta (Section Kangoo)
(SH)- Removal of slips, Maintenance of earthen shoulder & maintenance of drain at various road at various RDs)

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Maintenance of earthen shoulder (filling with fresh selected soil making up less of material / irregularities on shoulder in design level by adding fresh approved selected soil and compacting it with appropriate equipment OMC upto a lead of 1000mts as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government .	12960.00	Square metre		Per square Metre	
2	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slopes and disposal all material upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	378.30	cubic metre		Per Cubic Metre	
3	Maintenance of Drain :- Maintenance of drain including erosion, repair clearing , cleaning reshaping regarding deeding of side drain as well as catch water drain as per technical specification clause No 1907 including carriage of material and equipments in all leads and lifts with all mode of transport and as per the direction of Engineer-in- Charge. including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	28000.00	Running metre		Per running Metre	
4	Clearing and grubbing road land clearing and grubbing road land including uprooting wild vegetation grass, bushes, shrubs, saplings and trees of grith upto 300mm (three hundred millimetre) removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned , upto a lead of 1000 metre(one thousand metre) including removal and disposal of top organic soil not exceeding 150mm(one hundred millimetre) in thickness as per Technical Specification Clause 201 including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	45000.00	Square metre		Per Cubic Metre	
				Total		

(Signature)
Executive Engineer
Barsar Division
HPPWD Barsar

HPPWD Barsar

Schedule of quantity

Name of work:-A/R & M/O HPPWD Rest House at Bhotia
(SH:- P/L Granite Stone flooring and dado in stair hall and stair steps etc.)

Job No.-13
Estimated Cost Rs:-492555.00
Earnest Money Rs:-9900.00
Time Limit :- One Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead For thickness of tiles above 25 mm and up to 40 mm as directed by the Engineer-in-Charge.including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	47.79 Square metre			Per square metre	
2	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead as directed by the Engineer-in-Charge.including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	42.90 Square metre			Per square metre	
3	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm (eighteen millimetre) thick stone slab over 20 mm (twenty millimetre) (average) thick base of cement mortar 1:4 (one cement : four coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent. all complete as specified and as directed by the Engineer-in-Charge.including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	47.55 Square metre			Per square metre	
4	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent. including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	43.18 Square metre			Per square metre	

		74	Running metre		Per Running metre	
5	Extra for pre finished nosing to treads of steps of marble stone as directed by the Engineer-in-Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government					
6	Finishing walls with 100% (hundred percent) Premium acrylic emulsion paint having VOC less than 50 (fifty) gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives new work (Two or more coats applied @ 1.43 litre/ 10 sqm (one point forty three litre per ten square metre) . Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point ninety litre per ten square metre) as directed by the Engineer-in-Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	100	Square metre		Per square metre	
						Total


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Job No 14

Schedule of quantity
Name of work:-Improvement of road regarding road safety of various road under HPPWD Sub Division dhaneta
(SH:- Supply &Stacking a dual direction delineator)

Estimated cost Rs:- 171600.00
Earnest money Rs:- 3500.00
Time Limit :- One Month

Sr.No	Discription of item	Quantity		Rate in		Unit	Amount
		Numbers	Figures	words			
1	Supplying and stacking dual direction delineator made of dia 18G (eighteen gauge) MS rectaanugular pipe of sizw 25 x 63mm (twenty five x sixty three millimetre) and of length 600 mm (six hundred millimetre) pipe stove enameled and baket to 120 (one hundred twenty) power coated head made of ABC plastic rectangular moulded with flat face provided with high intensity prismatic reflectors of colour (white/Yellow/Red) of size 100 x 125 mm (one hundred x one hundred twenty five millimetre) with additional to reflective strips of 20mm (twenty millimetre) wide make green light as per the direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, sale tax or other taxes imposed by the Government .	520.00				Each	
						Total	


Executive Engineer
Barsar Division
HPPWD Barsar