

Himachal Pradesh
Public Works Department

Registered

No. PWN/CB/GA/E-27/Tender/2021-22- **7448**
To

Dated:- **10/08/2022**

The Executive Engineer (IT Cell),
Nigam Vihar Shimla.

Subject: - Publication of Tender Notice.

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting tender for uploading on department website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th, July 2021 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA/As above.


Executive Engineer,
Nurpur Division, HP.PWD,
Nurpur.

**HPPWD
Tender Notice**

Sealed Item rates Tenders on PWD form 6&8 are invited by the Executive Engineer HP.PWD Nurgur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD (B&R), so as to reach in his office on or before **19/3/2022** up to 11.00 AM and shall be opened on the same day at 11.30 AM in the presence of intending contractors or their authorized representative, if any. The tender forms can be obtained from this office against cash payment non-refundable during the working hours on **17/03/2022** up to 4.00 PM and no tender form shall be issued by post. Application for issue of tenders should reach in the office along with all the required documents on or before **16/03/2022**. The earnest money in the shape of FDR of any nationalized Bank in H.P, duly pledged in the name of Executive Engineer, Nurgur Divn. HP.PWD Nurgur must accompany with the application. The conditional tender and tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 90 days. The XEN reserves the right to reject any tender without assigning any reason.

Sl. No.	Name of work	Estimated cost (Rs.)	Earnest money (Rs.)	Time limit	Cost of tender form (Rs)
		3	4	5	6
1	2				
1	Construction of link road from Kherian to Jara via Khatoon Harijan Basti in G P Kherian (SH: Providing and laying Cement concrete from km.0/000 to 0/030 , G-I and G-II in km 0/240 0/480 and R/wall at RD 0/261 to 0/265	495690/-	10000/-	One month	350/-
2	Construction of link road from Kherian to Jara via Khatoon Harijan Basti in G P Kherian (SH: Construction of 900mm dia Hume pipe culvert at RD 0/265 and edge wall)	496263/-	10000/-	One month	350/-
3	Construction of link road to SC/ST Basti Sudiyal km 0/0 to 1/500 (SH: Const. of Retaining wall at RD. 1/401 to 1/416 and U-shape drain).	455112/-	10000/-	One month	350/-
4	Construction of link road to SC/ST Basti Sudiyal km 0/0 to 1/500 (SH: Providing and laying cement concrete interlocking paver block km 0/589 to 0/689).	495360/-	10000/-	One month	350/-
5	Construction of link road Harijan Basti Sadwan Khas km 0/0 to 1/765 (SH:- C/O Retaining wall at RD 0/310 to 0/330 including parapets and Providing and laying cement concrete interlocking paver block km 0/680 to 0/700)	396963/-	8000/-	One month	350/-
6	Construction of link road Harijan Basti Sadwan Khas km 0/0 to 1/765 (SH:- C/O V-shape drain with edge wall of 1.50 mtr. Height at RD 1/165 to 1/218 L/S and V-shape drain with edge wall at RD 1/240 to 1/300 Ht. 1.20 mtr. L/S)	384084/-	8000/-	One month	350/-

1. Certified that tender of above works are being called of emergent nature in Exigency of public interest.

Executive Engineer
Nurgur Division, HPPWD,
Nurgur.
For on behalf of Governor of HP.

SCHEDULE OF QUANTITY

Name of work :-Construction of link road from Kherian to Jara via Khatoon Harijan Basti in G P Kherian (SH: Providing and laying Cement concrete from km.0/000 to 0/030 , G-I and G-II in km 0/240 0/480 and R/wall at RD 0/261 to 0/265)

Estimated cost Rs. 495690.00

Earnest money Rs.10000 .00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts , drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	37.20 cubic meter			Per cubic meter	
2	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	15.00 cubic meter			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete grade M-20(M-twenty) nominal mix 1:2:4 (one cement: two sand :four graded /crushed stone aggregate 20mm (twenty millimeters) nominal size for plain /reinforced concrete including cost of form work curing in bed block complete as per drawings and MORD technical specifications clause 802, 803, 1202 and 1203 and as per the direction and entire satisfaction of Engineer-in- charge including carriage of materials within all leads and lifts and other incidentals The rates including octroi, royalty, malkana, toll tax, G S T or any other taxes imposed by the Government.	20.737 cubic meter			Per cubic meter	

4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	37.80 cubic meter			Per cubic meter
5	Back filling with granular materials behind abutment, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	2.70 cubic meter			Per cubic meter
6	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	8.00 Number			Each
7	Loosening leveling and compacting original ground upto a level of 150mm (one hundred fifteen millimetre) below the sub-grade level, watered, graded and compacted in layer to meet requirement of table 300.1 and 300.2 with power road roller 8-10 tonne (eight –ten tonne) capacity for sub grade construction as per M.O.R.D. technical specification rural roads Clause 303.5.2 including hauling of materials in all leads, lifts and other incidental or as per the entire specification and directions of Engineer-in-Charge.	120.96 cubic meter			Per cubic meter
8	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness using template hand packing, rolling with three wheel 80-100 (eighty / hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, with application of stone screening type-A of size 11.2mm (eleven decimal two) millimeters at the rate of 0.27 cum (zero point two seven cubic metres) per ten square metres, and binding materials at the rate of 0.08 cum (zero point zero eight cubic meter) to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –I, 90mm to 45mm (ninety millimeters to forty five millimeters) size, 100mm (hundred millimeters) compacted thickness as per technical specifications clause No. 405 including hauling of material in all leads, lifts within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	80.64 cubic meter			Per cubic meter

9	Providing . laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two cubic metres) per ten square metres., to fill up the intersitices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm (sixty three millimetres to forty five millimetres) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	60.48 cubic meter			Per cubic meter
			Total		


 Executive Engineer
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

Name of work :-Construction of link road from Kherian to Jara via Khaloan Harijan Basti in G P Kherian
(SH: Construction of 900mm dia Hume pipe culvert at RD 0/265 and edge wall)

Estimated cost Rs. 496263.00
Earnest money Rs.10000 .00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	60.67 cubic meter			Per cubic meter	
2	Excavation in soil in hilly area by in ordinary rocks by mechanical means including cutting and trimming of sides slopes and disposing of excavated earth upto any lift and leads as per technical specification clause 1603.2 including shoring and strutting and pumping and bailing out water (surface and sub soil water) complete as per entire satisfaction and as per the direction of Engineer-in-Charge Including carriage of materials within all leads and lifts and other incidental	60.10 cubic meter			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in sub structure for all type of structure complete of plain cement concrete grade M-15 (M-fifteen) nominal mix 1:2½:5 (one cement; two and half sand : five graded creushed stone aggregate 20mm (twenty millimeters) including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 804, 805, 806 , 807 1202 and 1204 as per directions of Engineer-in- charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	33.54 cubic meter			Per cubic meter	
4	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as	46.76 cubic meter			Per cubic meter	

	required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government				
5	Providing and laying to level o slope 900mm (nine hundred millimeters) dia meter reinforced cement concrete pipes NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding the cost of excavation, protection work, back filling concrete and masonry work in head walls and parapets a per drawing and M O R D technical specification clause 1108 and as per direction and entire satisfaction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, malkana, toll tax, sale tax and other taxes imposed by the Government.	7.50 running meter			Per running meter
6	Filling with earth marshy soil in foundation trenches as per drawing and technical specifications clause 305.3.9 and as per the direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	652.20			Per cubic meter
7	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	20.00 Number			Each
				Total	


 Executive Engineer
 Nurpur Division HPPWD
 Nurpur

SCHEDULE OF QUANTITY

Name of work :- Construction of link road to SC/ST Basti Sudiyal km 0/0 to 1/500
(SH: Const. of Retaining wall at RD. 1/401 to 1/416 and U-shape drain)

Estimated cost Rs. 455112.00
Earnest money Rs. 10000.00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	7.50 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 (one cement: five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	126.59 cubic meter			Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement: three sand: six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in- charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	4.05 cubic meter			Per cubic meter	

4	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	50.00 Number		Each	
				Total	


 Executive Engineer
 Nurpur Division HPPWD
 Nurpur


SCHEDULE OF QUANTITY

Name of work :-Construction of link road to SC/ST Basti Sudiyal km 0/0 to 1/500
(SH: Providing and laying cement concrete interlocking paver block km 0/589 to 0/689)

Estimated cost Rs. 495360.00
Earnest money Rs.10000 .00

Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in	Words	Unit	Amount
			Figures			
1	Providing and laying cement concrete 1:4:8 (one cement; four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	32.00 cubic meter			Per cubic meter	
2	Providing and laying of ISI marked inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	320.00 square meter			Per square meter	
				Total		


 Executive Engineer
 Naurpur Division HPPWD
 Naurpur

SCHEDULE OF QUANTITY

Name of work :-Construction of link road Harijan Basti Sadwan Khas km 0/0 to 1/765
(SH: C/O Retaining wall at RD 0/310 to 0/330 including parapets and Providing and laying cement concrete interlocking paver block km 0/680 to 0/700)

Estimated cost Rs. 396963.00
Earnest money Rs.8000 .00
Time limit :- One month

Sr. No.	Description of items	Qty.	Rate in		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	46.40 cubic meter			Per cubic meter	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1: 5: 10 (one cement; five sand : ten graded crushed stone aggregate 40mm (forty millimeters) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and Breast walls etcetera including the cost of form work complete in all respect as per drawing and technical specification clause 802,803,1202,1203 and as per the direction of the Engineer-in-Charge and carriage of material within all leads, lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	75.20 cubic meter			Per cubic meter	
3	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	37.00 Number			Each	

4	Back filling with granular materials behind abutment, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government.	21.60 cubic meter			Per cubic meter
5	Providing and laying cement concrete 1:4:8 (one cement, four sand : eight graded /crushed stone aggregate 40mm(forty millimeters) nominal size mixed and vibrated mechanically and curing complete including the cost of form work in foundation and plinth in all depths as per technical specification clause 802, 803 1202 and 1203 including carriage of materials within all leads and lifts and other incidental charges. The rate including octroi, royalty, Malkana, toll tax, G S T or other taxes imposed by the Government.	6.40 cubic meter			Per cubic meter
6	Providing and laying of ISI marked inter locking concrete block pavement having thickness 80mm (eighty millimeters) over sand base as per drawing and technical specification clause 1504 complete and as per directions of Engineer -in-charge including carriage of materials. The rates is inclusive royalty, toll tax, sale tax or any other taxes imposed by the Government.	64.00 square meter			Per square meter
				Total	


 Executive Engineer
 Murpur Division HPPWD
 Nurpur 2

SCHEDULE OF QUANTITY

Name of work :-Construction of link road Harijan Basti Sadwan Khas km 0/0 to 1/765
(SH: C/O V-shape drain with edge wall of 1.50 mtr. Height at RD 1/165 to 1/218 L/S
And V-shape drain with edge wall at RD 1/240 to 1/300 Ht. 1.20 mtr. L/S)

Estimated cost Rs. 384084.00
Earnest money Rs.8000 .00
Time limit :- One month

Sr. No.	Description of items	Rate in		Unit	Amount
		Qty.	Figures · Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and as per the direction of Engineer-in-Charge including carriage of materials within all leads and lifts.	90.50 cubic meter		Per cubic meter	
3	Providing and laying mechanically mixed and vibrated cement concrete for plain / reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement; three sand; six graded /crushed stone aggregate 40mm) (forty millimeters) nominal size in or under water and curing complete including pumping, or bailing out water , dewatering, removal of slush, as required at site which may arise at the time of laying under water complete for all heights / depths including cost of form work as per drawings and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203 as per directions of Engineer-in-charge and including carriage of material within all leads and lifts and other incidental . The rate including of octroi, royalty, Malkana, toll tax, G.S.T or other taxes imposed by the Government	78.98 cubic meter		Per cubic meter	
4	Providing and laying 100mm (One hundred millimeter) dia P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls extending through the full width of the structures with slope of 1(V): 20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204,3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental ..	111.00 Numbe r		Each	
			Total		

Executive Engineer
Nurpur Division HPPWD
Nurpur