

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2021-22- 12973-74
To

Dated:- 08/03/2022

The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 16.03.2022.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature and in public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.

Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed items rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 16.03.2022 up to 12.30 PM and shall be opened on 16.03.2022 the same day at 12:45 P.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 15.03.2022 for which the applications should reach in this office up to 4.00 PM on 14.03.2022. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	Construction of road from Govt. Pol Technical Collage Rampur Bharapur, Tehsil Paonta Sahib km 0/0 to 4/100(SH:-Providing & laying interlocking tiles from RD 1/495 to 1/525 & 1/550 tto 1/780).	Rs. 496100/-	Rs. 10000 /-	Three Months.	350/-	C & D
2	Construction of road from Govt. Pol Technical Collage Rampur Bharapur, Tehsil Paonta Sahib km 0/0 to 4/100. (SH:-Providing & laying interlocking tiles from RD 1/780 to 1/935).	Rs. 499600 /-	Rs. 10000/-	Three Months.	350/-	C & D
3	(i)A/R & M/O to link road from Haripur Tohana to Rampurghat km.0/0 to 2/100(SH:-Providing and applying 2.5mm.thick road marking strips(retro-reflective)in km.0/0 to 1/600)(ii)A/R & M/O to Paonta Puruwala Singhpora Bhagani Gojjar Dakpathar road (MDR-94)km.0/0 to 26/500.(SH:-Providing and applying	Rs. 259900 /-	Rs. 5000/-	Two Months.	350/-	C & D Work done certificate/Experience in similar nature of work.

	2.5mm thick road marking strips(retro-reflective)on speed breakers at various essential RD's in km.0/0 to 26/500).					
4	A/R & M/O to link road from Bangran Kishankot km.0/0 to 2/750 & link road Nihalgarh to Bhungrani km.0/0 to 2/0 (SH:-Providing and fixing 2.5mm.thick thermoplastic strip between km.0/0 to 2/750 of Bangran Kishankot road and km.0/0 to 1/400 of Nihalgarh Bhungrani road).	Rs. 490300 /-	Rs. 10000/-	Two Months.	350/-	C & D Work done certificat e/Experie nce in similar nature of work.
5	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.2/615 to 2/975).Under MNP.	Rs. 495200 /-	Rs. 10000/-	One Month.	350/-	C & D
6	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.2/445 to 2/615).Under MNP.	Rs. 489100 /-	Rs. 10000/-	One Month.	350/-	C & D
7	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.1/685 to 1/805).Under MNP.	Rs. 482700/-	Rs. 10000/-	One Month.	350/-	C & D
8	C/O link road from Lohgarh to Banda Bahadur Guru Dwara Sahib km 0/0 to 4/200 (SH:-C/O 5/7 mtr.wide road formation cutting from km.1/490 to 1/685).Under MNP.	Rs. 448600 /-	Rs. 10000/-	One Month.	350/-	C & D
9	Construction of link road to Surajpur patlion road km 0/0 to 3/185. (SH:-P/L wet mix Macadam at RD 1/960 to 2/180).Under MNP.	Rs. 2,90,431/-	Rs. 5800/-	Two Months.	350/-	C & D


10	Construction of link road Behral (NH) Rajpoot Basti G.P. Behral (SH:- Excavation in earth work, c/o embankment, P/L CC 1:3:6 in CC edge walls from RD.0/0 to 0/500). under MMGSY	Rs. 497403 /-	Rs. 10000/-	Two Months.	350/	C & D
----	--	---------------	-------------	-------------	------	-------

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number and GST clearance certificate from GST depart.
3. Who possess valid Permanent Account Number.
4. Who Possess valid EPF Number.
5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis.
10. Only two tender form will be issued to one contractor.



Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

Dated:- 08/03/2022

No.PWP/CB-Tender Notice/2021-22- 12975-13024

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
11. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib

Job No - 1

SCHEDULE OF QUANTITY					
Name of work :- C/O Road from Govt. Pol Technical college Rampur Bharapur, Tehsil paonta sahib 0/0 to 4/100(SH:- P/L interlocking tile at RD 1/495 to 1/525 & 1/550 to 1/785)			Estimated cost :- Rs. 496100/- only Earnest Money :- Rs. 10000/- only. Time allowed :- Three months.		
S. No.	Sub-head & item of works	Quantity	Rate		Amount
			Figure	Words	
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge 16.91.2 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern. (Item code 16.91.2 & page no 251)	427.55		Per Sqm metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) (Item code 4.1.3 & Page no 73)	21.02		Per Cum metre	
			Total		

Executive Engineer
Paonta (B&R) Division,
H.P. PWD Paonta Sahib.

Job No - 2.

SCHEDULE OF QUANTITY

Name of work :- C/O Road from Govt. Pol Technical collage Rampur Bharapur to Ghaughat, Tehsil paonta sahib Distt. Sirmour.				Estimated cost :- Rs. 499600/- only		Earnest Money :- Rs. 10000/- only.	
O/O to 4/100(SH)- P/L Interlocking Tile at RD 1/780 to 1/955)				Rate		Unit	
S. No.	Sub-head & item of works	Quantity	Figure	Words	Unit	Amount	
1	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge 16.91.2 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern. (Item code 16.91.2 & page no 251)	409.60			Per Sqm metre		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level (1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) (Item code 4.1.3 & Page no 73)	24.21			Per Cum metre		
					Total		

Executive Engineer
Paonta (B&R) Division,
H.P. PWD Paonta Sahib.

Job No - 3.

SCHEDULE OF QUANTITIES.				
Name of work:- (i)A/R & M/O to link road from Haripur Tohana to Rampurghat km. 0/0 to 2/100 (SH:- Providing and applying 2.5mm.thick road marking strips(retro-reflective)in km. 0/0 to 1/600) (ii) A/R & M/O to Paonta Puruwalla Singhpura Bhagani Gajjar Dakpathar road (MDR-94)km.0/0 to 26/500 (SH:- Providing and applying 2.5mm.thick road marking strips (retro-reflective) on speed breakers at various essential RD's in km. 0/0 to 26/500).		Estimated Cost :- Rs.2,59,900/-ONLY. Earnest Money :- Rs.5,200/-ONLY. Time Allowed :- Two Months.		
S.No.	Sub head and items of work.	Quantity.	Rate in Figures. Words.	Unit. Amount.
1	Providing and applying 2.5mm.(two point five millimetre)thick road marking strips(retro-reflective) of specified shade/colour using hot thermoplasticmaterial by fully/semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour ,T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc., complete, as per direction of Engineer-in-charge and accordance with applicable specifications, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	440.00		Per square metere.
				Total:-Rs.

Executive Engineer,
Paonta B&R Division,
H.P.PWD.Paonta Sahib.

Job 4

SCHEDULE OF QUANTITIES

Estimated Cost:-Rs.4,90,200/- only.			
Earnest Money:-Rs. 9,800/- only.			
Time Allowed:- Two Months.			
Quantity	Figurers.	Rate in Words.	Unit.
Sub head and items of work.			Amount
1. Providing and applying 2.5mm.(two point five milimetre)thick road marking strips(retro-reflective) of specified shade/colour using hot thermoplasticmaterial by fully/semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc., complete, as per direction of Engineer-in-charge and accordance with applicable specifications, including all leads, lifts and carriage of materials, as per the entire satisfaction of Engineer-in-charge.	830.00		Per square metre.
			Total:-Rs.

Executive Engineer
Paonta B&R Division,
U.P.P.W.D., Paonta Sahib.

Job No - S

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwara Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 2/615 to 2/975).

Estimated Cost: 495200/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his on cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 158.11 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,162.20 Cum	Per Cubic Meter			
					Total:	

Executive Engineer
Paonta (B&R) Division,
HP PWD, Paonta Sahib.

Job No-6

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwar Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 2/445 to 2/615).

Estimated Cost: 489100/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his on cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 156.16 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,123.25 Cum	Per cubic metre			
					Total:	

Executive Engineer,
Paonta (B&R) Division,
H.P.W.D. Paonta Sahib.

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwar Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 1/685 to 1/805).

Job No-7

Estimated Cost: 482,673.00/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 154.11 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	3,082.20 Cum	Per cubic metre			
					Total:	482,673.00


Executive Engineer
Paonta (B&R) Division,
HP.PWD, Paonta Sahib.

DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O link road from Lohgarh to Band Bahadur Guru Dwara Sahib km 0/0 to 4/200
(SH: C/O 5/7 mtr. wide road formation cutting from km 1/490 to 1/685).

Job No-8

Estimated Cost: 448500/-
Earnest Money: 10,000/-
Time Allowed: One Month

S.No.	Sub Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hill area in all kind of such as pick work, jumper work, soft and hard rock including chiseling wedging out of rock (where blasting is prohibited) if required and saturated soil; and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer in Charge at site and sorting out useful material and stacking the same in all leads and lift on acquired width of the road and transportation of material for filling in road ways, camber, embankment, grade improvement and disposal of all surplus material in all leads and lifts to the approved dumping site through all modes of transportation including head load or animal transport or mechanical means along with its leveling and fine dressing complete in all height and depth. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-charge. Recovery for useful stone 143.23 cubic meter at the rate of Rs. 170/- per cubic meter shall be made from the contractor.	2,864.60 Cum	Per cubic metre			
					Total:	


Executive Engineer,
Paonta (B&R) Division,
HP PWD, Paonta Sahib.

Job No - 9

SCHEDULE OF QUANTITIES.					
Name of work:- Construction of link road Surajpur Patlon road km. 0/0 to 3/185 (SH:-Providing and laying wet mix macadam (size 53mm. To 0.075mm) at RD. 1/960 to 2/180) Under M.N.P.					
S.No. Sub head and items of work.			Estimated Cost :- Rs.2,90,431/-ONLY. Earnest Money :- Rs.5,800/-ONLY. Time Allowed :-Two Months.		
Quantity	Figures.	Rate in Words.	Unit.	Amount.	
1	110.55		Per cubic metre.		
Providing, laying spreading and compacting graded stone aggregate (size range 53mm. to 0.075mm)(fifty three millimetres to zero point zero seven five millimetre) to wet mix macadam (WMM) specification included premixing the erial with water at OMC in for all leads, lifts, laying in uniform layers with mechanical paver finisher in sub base/base course on well prepared surface and compacting with vibratory roller of 8 to 10 (eight to ten)tonne capacity to hieve the desired density, complete, including all leads, lifts and cartiage of materials, as per the entire satisfaction of Engineer-in-charge.					
NOTE:- The construction materials will be procured by the contractor/ firm from the aganodes given in the list of preferred makes of material for Civil/ Sanitary works strictly in accordance with the ACS(PW) to the Govt. of. HP Letter No.PBW(B)(C)(17)2012 dated 07-08-2018 and cement from the HP Civil Supply Corporation at your own cost.					
Total:-Rs.					

Executive Engineer,
Paonta B&R Division,
J.P. B&R-Paonta Sahib.

Job No-10

Schedule of Quantity						
Name of work:- Construction of link road Behrai (NH) Rajpoot basti G.P. Behrai (SI)- Excavation in earth work, e/o embankment, P/L						
CC 1:3:6 in cc egg walls from RD.0/00 to 0/500).						
Sr.No.	Description of Items	Quantity	unit	Rate in		Amount
				Figure	Words	
						Time: Two months
1	Excavation in soil in hilly areas by mechanical means including cutting trimming of sides slopes and disposing of cut material with lift upto 1.50 mtrs and lead upto 20 mtrs as per technical specification clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	954.00	Per cubic metre			
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	345.00	Per cubic metre			
3	Earth work in excavation for structure as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in metres with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	10.50	Per cubic metre			
4	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clauses 807, 803, 1202 and 1203. PCC (Grade M-100) 3:6 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	13.16	Per cubic metre			
5	Providing weap holes in plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structure with slope of 1 V:20 H towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204, 3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	20.00	Each			
					Total	

Executive Engineer,
Raonla B & R Division
H.P. District Raonla Sahib