

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office 24.03.2022 upto 10:30 AM and shall be opened on the same day at 11:00 AM in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Schedule	
1	Last date for tender receipt of application for tender form	22.03.2022 upto 4:00 PM
2	Last date of sale of tender forms.	23.03.2022 upto 4:00 PM
3	Date of receipt of tender forms	24.03.2022 upto 10:30AM
4	Date of opening of tenders	24.03.2022 at 11:00AM

Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form
1	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km. 87/0 to 127/300 (SH:- C/O PCC R/wall at RD 105/1025 to 105/1040).	494058	9900	One Month	350/-
2	Restoration of rain damages on approach road HPPWD Division Rajgarh (SH:- C/O R/wall at RD 0/130 to 0/142).	4,83,695	9,700	One Month	350/-
3	A/R & M/O to Solan Meenus road Km 9/345 to 46/0 (SH:-Providing and laying patch work i/c G-III between Km 33/0 to 35/0 and 44/0 to 46/0)	4,98,381	10,000	One Month	350/-
4	A/R & M/O to Solan Meenus road Km 9/345 to 46/0 (SH:-Providing and laying patch work between Km 35/0 to 40/0)	4,99,949	10,000	One Month	350/-
5	A/R & M/O to Banethi Bagthan Rajgarh Chandol road Km 48/0 to 82/0 (SH :- Providing & Laying patch work between Km 68/0 to 73/0,)	4,97,088	10,000	One Month	350/-
6	A/R & M/O to Churwadhar Gadol Pirag road km 0/0 to 10/750 (SH :- Providing & Laying patch work between Km 5/0 to 8/0,)	4,99,949	10,000	One Month	350/-
7	A/R & M/O to Dhamander Deothi Majhgaon Tharu road km 0/0 to 14/0 (SH :- Providing & Laying patch work between Km 3/0 to 6/0,)	4,99,038	10,000	One Month	350/-
8	C/O link road to village Gadol Anji Km. 0/0 to 5/0 (SH:- C/O 5/7 mtr wide formation cutting in Km 0/810 to 1/0) Under MNP	2,33,230/-	5000/-	One Month	350/-

Certificate :-It is certified that the tender of above work are exigency/emergent nature and in public interest

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.
5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who dose not have more than two works in hand

The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW(B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right any or all the tenders without assigning any reason.

Executive Engineer
HPPWD Division Rajgarh
Distt Sirmour HP
on behalf of Governor of Himachal Pradesh
Tel. No. 01799-221023
Mail. ee-raj-hp@nic.in


No.PW/RGH/Estt-Tender/2021-22-

10730-10779

Dated:- 17-03-2022

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer,
Rajgarh Division,
HP.PWD. Rajgarh.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 87/0 to 127/300 (SH:- C/O PCC Retaining wall at RD 105/1025 to 105/1040).

Job No.

Estimated cost:-Rs.4,94,058/-

Earnest money:- Rs. 9,900/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	84.70	Per Cubic Metre.			
2	Providing and laying concrete for plain Cement concrete in 1:4:8 (one cement: four sand: eight graded crushed hard stone aggregate 40 (forty) millimeter nominal size) mechanical mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	103.24	Per Cubic Meter.			
3	Providing weep holes in brick masonry/Plain/Reinforced concrete abutment, wing wall/ return wall with 100 mm (one hundred millimeter) dia AC pipe, extending through the full width of the structure with slope of 1: 20 1(V): 20 (H) towards drawing face. Complete as per drawing and technical specifications clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	20.00	Each			

4	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and technical specification clause 1204.3.8 (one thousand two hundred four point three eight) Granular material, including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads and all incidental charges.	10.02	Per cubic meter.		


 Executive Engineer
 Rajgarh Division
 HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on approach road HPPWD Division Rajgarh (SH:- C/O Retaining wall in Km 0/130 to 0/142).

Job No.

Estimated cost:-Rs.4,83,695/-
Earnest money: - Rs. 9,700/-
Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	71.70	Per Cubic Metre.			
2	Providing and laying concrete for plain Cement concrete in 1:4:8 (one cement: four sand: eight graded crushed hard stone aggregate 40 (forty) millimeter nominal size) mechanical mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	102.30	Per Cubic Meter.			
3	Providing weep holes in brick masonry/Plain/Reinforced concrete abutment, wing wall/ return wall with 100 mm (one hundred millimeter) dia AC pipe, extending through the full width of the structure with slope of 1: 20 1(V): 20 (H) towards drawing face. Complete as per drawing and technical specifications clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	29.00	Each			

4	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	1.87	Per cubic meter.		


 Executive Engineer
 Rajgarh Division
 HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work: A/R & M/O to Solan Meenus road km 9/345 to 46/0 (SH:- Providing and Laying patch work between Km. 33/0 to 35/0 & 44/0 to 46/0).

Job No.
Estimated cost-Rs.4,98,381/-
Earnest money: - Rs. 10,000/-
Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) size Grading -III as per Technical Specification Clause 405.by Manual means.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	1.7889	Per Cubic Metre.			
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	23.85	Per Square metre.			
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	1590.00	Per Square metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work: A/R & M/O to Solan Meenus road km 9/345 to 46/0 (SH:- Providing and Laying patch work between Km. 35/0 to 40/0).

Job No.

Estimated cost:-Rs.4,99,949/-
Earnest money:- Rs. 10,000/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) size Grading -III as per Technical Specification Clause 405.by Manual means.including carriage of all labour equipments and materials to various locations through	1.7944	Per Cubic Metre.			
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	23.93	Per Square metre.			
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	1595.00	Per Square metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work: A/R & M/O to Banethi Bagthan Rajgarh Chandol road km 48/0 to 82/0 (SH:- Providing and Laying patch work between Km. 68/0 to 73/0).

Job No.

Estimated cost:-Rs.4,97,088/-
Earnest money:- Rs. 10,000/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 53mm to 22.4mm (fifty three milimetre to twenty two point four milimetre) size Grading -III as per Technical Specification Clause 405.by Manual means.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	1.7889	Per Cubic Metre.			
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	23.85	Per Square metre.			
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	1590.00	Per Square metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh


Job No.

Estimated cost:-Rs.4,99,949/-
Earnest money:- Rs. 10,000/-
Time Limit:- One Month.

SCHEDULE OF QUANTITY

Name of work : A/R & M/O to Churwadhar Gadol Pirag road km 0/0 to 10/750 (SH:- Providing and Laying patch work between Km. 5/0 to 8/0).

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) size Grading -III as per Technical Specification Clause 405.by Manual means.including carriage of all labour equipments and materials to various locations through	1.7944	Per Cubic Metre.			
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	23.93	Per Square metre.			
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	1595.00	Per Square metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh


Job No.

Estimated cost:-Rs.4,99,038/-
Earnest money: - Rs. 10,000/-
Time Limit: - One Month.

SCHEDULE OF QUANTITY

Name of work: A/R & M/O to Dhamander Deothi Majhgaon Tahru road km 0/0 to 14/0 (SH:- Providing and Laying patch work between Km. 3/0 to 6/0).

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) size Grading -III as per Technical Specification Clause 405.by Manual means.including carriage of all labour equipments and materials to various locations through	1.7829	Per Cubic Metre.			
2	Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70- 1.0 (zero point seventy to one point zero) kg/sqm using mechanical means as per Technical Specification Clause 502.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	23.77	Per Square metre.			
3	Repair to pot holes and removal of loose materials, trimming of sides, cleaning of surfaces providing tack coat with bitumen emulsion, 20mm thick premix carpet using cationic bitumen emulsion and seal coat type-B with bitumen emulsion as per technical specification clause 1904.2, 503 and 508.2.including carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	1585.00	Per Square metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work: C/O link road to village Gadol Anjji Km. 0/0 to 5/0 (SH:- C/O 5/7 mtr wide formation cutting in Km 0/810 to 1/0)
Under MNP

Job No.
Estimated cost:-Rs. 2,33,230/-
Earnest money:- Rs. 5,000/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones, whether useful or not, for 36.64 cum (Thirty four point sixty four cubic metre) in all cases, @ rupees 170/- only (Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	1832.13	Per cubic metre.			


Executive Engineer
Rajgarh Division
HPPWd Rajgarh