

Himachal Pradesh
Public Works Department
PW-RD-GA-Tender-2021-22-
To

19054

dated: 7-3-2021


The Executive Engineer (IT Cell)
Nigam Bihar, Shimla-2.

Subject: - Tender notice.

Enclosed please find herewith the tender notice of work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of H.P. letter N. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender & schedule of quantity.


Executive Engineer,
B&R Division, HPPWD,
Rohru.

**Himachal Pradesh
Public Works Department**

"NOTICE INVITING TENDERS"

Sealed item rate tender on form PWD 6&8 are invited by the Executive Engineer Rohru Division HPPWD, on behalf of Governor of H.P. for the following works from the approved and eligible contractors enlisted in HPPWD, So as to reach in this office as per time schedule given below:-

1. Date of receipt of applications for tender forms:- 22-03-2022 upto 1:00PM
2. Date of issue/sale of tender forms:- 22-03-2022 upto 2:00PM to 3.00PM
3. Date of receipt of tender:- 22-03-2022 upto 3:30PM
4. Date of opening of tender:- 22-03-2022 upto 4:00PM

Sr.No.	Name of Work.	Estt. Cost.	E/Money	Time.
1	A/R & M/O of tank Stand for Housing Board at Samala (SH:- C/O 2 No tank stand for flat No G.F. & 1 st Floor 33)	Rs.451717/-	Rs.9100/-	2 month
2	A/R & M/O Bye pass road from Anupam Hotal to Chirgaon Junction km 0/0 to 0/600 (SH:- prov. and Fixing of Gritting over drain at RD 0/063 to 0/096)	Rs.453161/-	Rs.9200/-	2 month
3	C/O Main road Targali Jhaltu to H.B Brasli Dhar road km 0/0 to 4/500 (SH:-C/O R/wall in PCC 1:3:6 at RD 0/090 to 0/105)	Rs.374015/-	Rs.7500/-	1 month
4	R/R damages of Parsa Chhupari road km 0/0 to 10/100 (SH:-C/O B/wall at RD 3/795 to 3/820)	Rs.496869/-	Rs.10000/-	2 month
5	Repair and maintenance of HPPWD Division office Rohru. (SH:- P/F Wood work)	Rs.496395/-	Rs.10000/-	2 month
6	Improvement of link road Tutupani Kuthari Ghasni to Deoli km 0/0 to 10/680 (SH:-C/O R/wall at RD 17/290 to 17/309)	Rs.476987/-	Rs.9100/-	2 month
7	Repair and maintenance of A.E Office & Establishment Branch (Circle) at Rohru. (SH:- P/F Wood panel , PVC Ceiling and polish work etc.)	Rs.494371/-	Rs.10000/-	2 month
8	R/R damages to Sua Degori Bashlog road km 0/0 to 4/0 (SH:- C/O B/wall at RD 2/237 to 2/262)	Rs.462836/-	Rs.9300/-	2 month
9	Repair and maintenance of HPPWD Circle office Rohru. (SH:- P/F Wood work .)	Rs.498223/-	Rs. 10000/-	2Month
10	Repair and maintenance of Sub Division Office at Chirgaon.J.E. Room (SH:- P/F Wood panel , PVC Ceiling and polish work etc.)	Rs.490545/-	Rs.9800/-	2month
11	Improvement of Black Spot Under various road under Rohru S/D (SH:- Providing and Supplying of high intensity Engineering grade prismatic tape/sheeting) (Allocation TKHR Road)	Rs.488250/-	Rs. 10000/-	1Month

Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

Terms and conditions:-The tender document shall be issued only to these contractors/firms who fulfill the following criteria and submit the following document with the application.

1. The Earnest-money for the above works should be submitted with the application for the purchase of the tender-documents.
2. The Contractors should quoted the rates of all the items in the tenders both in figures and words.
3. Income tax & GST No latest clearance certificate.
4. The contrs / firm shall accompany his enlistment/renewal & EPF submit before the award of tender.
5. The contractors should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept/rejected any tender/application or all tenders without assigning any reason.

NO:-PW-RD-GA.-Tender/2021-22--

Copy forwarded for information and wide publicity to:-

1. The Chief-Engineer(S), HPPWD, Shimla-2.
3. The S E 14th Circle HPPWD, Rohru
4. All the E.E.'s under 14th Circle, HPPWD, Rohru
5. All the A.E.'s working under this Division (B&R).
6. The Sub Divisional Magistrate, Rohru.
7. The B.D.O. Rohru and Chirgaon.
8. The Tehsildhar, Rohru/Chirgaon and Tikkar.
9. The Chairman, N.A.C. Rohru.
10. A/B. and D/B. in this Office.
11. Notice-Board.

Executive Engineer,
B&R Division, HPPWD,
Rohru.

Dated:- 7/3/2022

Executive Engineer,
B&R Division, HPPWD,
Rohru.

Schedule of Qty						
					Estimate Cost	451717
					Earnest Money	9100.00
					Time	Two Month
Name of Work:- A/O & M/O of tank Stand for Housing Board at Samala (SH:- C/o two No tank Stand for Flat No G.F & 1st Floor 33)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. in ordinary rochs up to 3 mtr depth	12.00			cum	
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing:1:3:6 (1 cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size)	8.75			cum	
3	Steel work welded in built up sections, trusses and framed work, including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts :-In gratings, framed, guards, bars ladders and railing, brackets and similar works including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	3040.41			Kg	
	Total					


 Executive Engineer
 B&R Division HPPWD
 Rohru

Schedule of Qty						
				Estimate Cost	453161.00	
				Earnest Money	9100.00	
				Time	Two Month	
Name of Work :- C/O BYE pass Road From Anupam Hotal to Chirgaon Junction km 0/00 to 0/600 (SH:- Providing & Fixing of Gritting over Drain at RD 0/063 to 0/096)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Steel work welded in built up sections, trusses and framed work, including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials within all leads and lifts :-In gratings, framed, guards, bars ladders and railing, brackets and similar works including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	3512.88			Kg	
	Total					


 Executive Engineer
 B&R Division HPPWD
 Rohru

Schedule of Qty				Estimated Cost	374015
				Earnest Money	7500
				Time	Two Month
Name of Work :- C/o Main road Targali Jhaltu to H.B Barasli Dhar road km 0/00 to 4/500 (SH:-C/o R/wall in PCC 1:3:6 at RD 0/090 to 0/105)					
	Sub-head and Item of works.	Quantity.	Rate in figures.	Rate in words.	Unit. Amount.
1	Excavation in soil in Hilly Area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	9.75			Per cubic meter.
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.	15.75			Per cubic meter.
3	Providing concrete for plain/reinforced concrete in open foundation/R/B-walls complete as per drawing and technical specification clause 802,803,1202 & 1203 grade (1:3:6 nominal mix) ,1 cement :3 Sand :6 graded stone aggregate 25mm stone agg.	57.45			Per cubic meter.
4	Providing weepholes in brick masonry/ Stone masonry,plain/reinforced concrete aboutment ,wing wall,return wall with 100 mm dia AC pipe extending though the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.7	25.00			Nos
5	Back filling being the retaining wall and wing walls and return walls complete as per drawing and technical specification clause 1204.3.8	9			Per cubic meter.
				Total	



 Executive Engineer
 B&R Division HP.PWD
 Rohru

SCHEDULE OF QUANTITY.

Estimated Cost 4,96,869/-
 Earnest Money 10,000/-
 Time 2 Months

Name of Work:- R/R Damages on Parsa Chuppari Road k.m. 0/0 to 10/100 (SH:- C/O B/wall at R.D. 3/795 to 3/820)

Sub-head and item of works.	Quantity.	Rate in figures.	Rate in words.	Unit.	Amount.
1 Excavation in soil in Hilly Area in all kind of sand by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead and lift as per Technical Specification Clause 1603.1 and as per HPPWD, specification of 1990 Volume-I, or as directed by the Engineer-In-Charge	43.26			Per cubic meter	
2 Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a any lead and lift, dressing of sides and bottom and backfilling in trenches with excavated suitable material useful material available from excavation to be properly stacked and handed over to the department free of cost including all leads and lifts, as per HPPWD, specification of 1990 volume-I or as directed by the Engineer-In-Charge	42.50			Per cubic meter	
3 Providing and Laying concrete concrete 1:6:12 (1cement: 6 sand: 12 graded stone aggregate 40mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts, as per HPPWD, specification of 1990 volume-I or as directed by the Engineer-In-Charge	12.14			Per cubic meter	
4 Random rubble masonry stone masonry (un-coursed/brought to courses) with hard stone of approved quality in foundation in cement mortar 1:6 (1cement: 6 sand) complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 including all leads and lifts, or as per HPPWD, Specification of 1990 Volume-I, as directed by the Engineer-In-Charge	83.34			Per cubic meter	


 Executive Engineer
 B&R, Divn HP PWD
 Rohru.

Schedule of Qty						
				Estimate Cost	496395	
				Earnest Money	10000.00	
				Time	Two Month	
Name of Work:- Repair and maintenance of HPPWD Division office Rohru.(SH:- P/F Wood work .)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	P/F 12mm thick prelaminated board both side Bwp phenol bonded extrior/interior grade sgutter with frame 1st class deodar wood.complete including carriage of materials in all leads and lifts.	123.42			sqm	
	Total					


 Executive Engineer
 B&R Division HPPWD
 Rohru

DRAFT SCHEDULE OF QUANTITY

Estimated Cost 4,76,987/-
Earnest Money 9600/-
Time 2 Months

Name of Work:- Improvement of link road Tutupani Kuthari Ghasni to Deoli k.m. 0/0 to 10/680 (SH:- C/O R/Wall at R.D. 17/290 to 17/309)

	Sub-head and Item of works.	Quantity.	Rate in figures.	Rate in words.	Unit.	Amount.
1	Excavation in soil in Hilly Area in all kind of sand by mechanical/manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead and lift as per Technical Specification Clause 1603 1 and as per HPPWD specification of 1990 Volume-I, or as directed by the Engineer-In-Charge	36.48			Per cubic meter.	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a any lead and lift, dressing of sides and bottom and backfilling in trenches with excavated suitable material useful material available from excavation to be properly stacked and handed over to the department free of cost including all leads and lifts, as per HPPWD specification of 1990 volume-I or as directed by the Engineer-In-Charge	34.39			Per cubic meter.	
3	Providing and Laying concrete concrete 1 6 12 (1cement, 6 sand, 12 graded stone aggregate 40mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts, as per HPPWD, specification of 1990 volume-I or as directed by the Engineer-In-Charge	9.31			Per cubic meter.	
4	Providing and Laying concrete concrete 1 4 8 (1cement, 4 sand, 8 graded stone aggregate 40mm nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including all leads and lifts, as per HPPWD specification of 1990 volume-I or as directed by the Engineer-In-Charge	3.80			Per cubic meter.	
5	Random rubble masonry stone masonry (un-coursed/brought to courses) with hard stone of approved quality in foundation in cement mortar 1 6 (1cement 6sand) complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 including all leads and lifts, or as per HPPWD, Specification of 1990 Volume-I, as directed by the Engineer-In-Charge	34.58			Per cubic meter.	
6	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704 6 & 1302 5 including all leads and lifts, as per HPPWD, specification of 1990 volume-I as directed by the Engineer-In-Charge	58.05			Per cubic meter.	
7	Back filling behind retaining wall, abutment wing wall and return complete as per drawing and technical specification	7.98			per cubic metre	
					Total	

Executive Engineer
B&R, Divn HP.PWD
Rohru.


Schedule of Qty						
			Estimate Cost	494371		
			Earnest Money	9900.00		
			Time	Two Month		
Name of Work :- Repair and maintenance of A.E Office & Establishment Branch (Circle) at Rohru.(SH:- P/F Wood panel , PVC Ceiling and polish work etc.)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Providing wood work in trusses purlins, rafters, posts post plates, wall plates and the like wrought framed, hoisted and fixing in position.	0.47			cum	
2	Providing and fixing plain lining with tongued and groved jointing and screws (frame work and cover fillets to be measured and paid for separately with.	43.68			sqm	
3	Providing and fixing PVC ceiling with tongued and grooved jointing and screws (frame work and cover fillets to be measured and paid for separately)	15.12			sqm	
4	P/F 12mm thick prelaminated board both side Bwp phenol bonded extrior/interior grade sgutter with frame 1st class deodar wood.	59.60			sqm	
5	Polishing two coats with french polish on new wood and wood based surfaces to given an even surface including cleaning the surface of all dirt, dust and sand papered smooth and including a coat of wood filler.	43.68			sqm	


 Executive Engineer
 B&R Division HPPWD
 Rohru


SCHEDULE OF QUANTITY

Estimated cost Rs 462836/-
EARNEST MONEY Rs 5632/-
TIME : Two month


Name of work - R/R damages to Shua Degori Bashlog road km 0/0 to 4/0(SH- C/O B/wall at RD 2/2347 to 2/262)						
Sr No	Description of Items	Quantity	Rate in Figure.	Rate in Words	unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per drawing and Technical Specification Clause 1603.1 and as per the direction of the Engineer-in-Charge including carriage of material through all modes of transportation within all leads and lifts and other incidentals.	60.50			per cubic metre	
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in ordinary rocks up to 3 mtr depth within all leads and lifts as per directions of Engineer in charge	44.75			per cubic metre	
3	Providing and laying mechanical mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:6:12 (One cement: six sand : twelve graded crushed stone aggregate) 40 mm (forty millimetre) nominal size oal specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material through all modes of transportion with in all leads and lifts and other incidentals.	12.00			per cubic metre	
4	Random masonry /stone masonry uncoursed brought to courses with hard stone of approved quality in foundation and plinth in cement mortar 1:6(1cement :6sand)/complete as per drawing and technical specification clause 702,704 1202 and 1203 HP/PWD specification 1990 volume-I within all leads and lifts as per direction of Engineer in charge	82.75			per cubic metre	
Total:-						


Executive Engineer
B&R Divn HP.PWD
Rohru

Schedule of Qty						
			Estimate Cost	498223		
			Earnest Money	9900.00		
			Time	Two Month		
Name of Work :- Repair and maintenance of HPPWD Circle office Rohru.(SH:- P/F Wood work .)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	P/F 12mm thick prelaminated board both side Bwp phenol bonded extrior/interior grade sgutter with frame 1st class deodar wood.complete including carriage of materials in all leads and lifts.	102.87			sqm	
2	Providing and fixing Steel Legs complete including carriage of materials in all leads and lifts:-					
		25.00			each	
3	Providing and fixing powder coated Aluminium tower bolts (Berrel type) transparent or dyed to required shade and colour with screws etc. complete including carriage of materials in all leads and lifts:-					
	150 X 10 mm	15.00			each	
4	Providing and fixing powder coated Aluminium handles transparent or dyed to required colour or shade with necessary screws etc. complete including carriage of materials in all leads and lifts :-					
	125 mm :-	30.00			each	
5	providing and fixing Channel with necessary screws etc.complete including carriage of materials in all leads and lifts :-					
	450mm:-	5.00			each	
6	Providing & fixing 150 mm M.S. single acting spring hinges bright finished with necessary screws etc. complete including carriage of materials in all leads and lifts :-	50.00			each	


 Executive Engineer
 B&R Division HPPWD
 Rohru

Schedule of Qty						
				Estimate Cost	490545	
				Earnest Money	9900.00	
				Time	Two Month	
Name of Work :- Repair and maintenance of Sub Division office at Chirgaon (Je's Room).(SH:- P/F Wood panel. PVC Ceilling and Polish work etc.)						
Sr.No.	Sub-Head and Item of works	Quantity.	Rate in figures.	Rate in words.	Unit	Amount
1	Providing wood work in trusses purlins, rafters, posts post plates, wall plates and the like wrought framed, hoisted and fixing in position.	0.27			cum	
2	Providing and fixing plain lining with tongued and groved jointing and screws (frame work and cover fillets to be measured and paid for separately with.	42.39			sqm	
3	Providing and fixing PVC ceiling with tongued and grooved jointing and screws (frame work and cover fillets to be measured and paid for separately)	14.95			sqm.	
4	Providing and fixing 9mm thick commercial board shutters for cup boards including fixing with nickel plated piano hinges with screws etc complete including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	42.39			sqm	
5	P/F 12mm thick prelaminated board both side Bwp phenol bonded extrior/interior grade sgutter with frame 1st class deodar wood.	52.48			sqm	
6	Polishing two coats with french polish on new wood and wood based surfaces to given an even surface including cleaning the surface of all dirt, dust and sand papered smooth and including a coat of wood filler.	42.39			sqm	


 Executive Engineer
 B&R Division HPPWD
 Rohru

SCHEDULE OF QUANTITY						
Name of work:- Improvement of Black Spot Under various road under Rohru S/D (SH:- Providing and Supplying of high intensity Engineering grade prismatic tape/sheeting) (Allocation TKHARoad)						
			Estimated Cost. Earnest Money Time	488250/- 9500/- 2 month		
Sr No	Sub Head/items of work.	Qty	Rate in figures	Rate in words	Unit.	Amount
1	Providing and Supplying of high intensity Engineering grade prismatic sheeting on the front side of existing W metal beam crash barrier size 300mm x 450mm in yellow and white colour at site within all leads and lifts and as per the direction of Engineer-in-Charge.	465.00			Per running Meter	


 Executive Engineer,
 B&R Division,HPPWD.,
 Rohru.