

# SCHEDULE OF QUANTITY


Estimated Cost Rs. :- 213997.00  
Earnest Money Rs. :- 4280.00

Time:- One Month.  
Signature: [Signature]

Name of work: - Construction of retaining wall near exit road of Armsdale building below stand for transformer at HP Secretariat Chotta Shimla under Shimla Smart City

Sl. No.	Items of work	Quantity	Rate		Unit.	Amount.
			In figures	In words		
1	Excavation in drains and channels etc. in all kinds of earth work including spade work, pick work, jumper work, blasting work and chiselling/ wedging out of rock etc. including dressing of sides and bed and disposing of excavated earth upto all leads and lifts and disposed earth to be levelled and neatly dressed as directed by Engineer-in-charge within all leads and lifts including clearing of jungle.	7.10 Cum			Per cubic metre	
2	Providing and laying cement concrete 1:5:10 (1 cement : 5 Sand :10 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth including carriage of materials within all leads and lifts.	2.93 Cum			Per Cubic metre	
3	Random rubble masonry / polygonal rubble masonry (uncoursed / brought to courses) with hard stone of approved quality in foundation and plinth in cement mortar 1:6 (1 cement :6 sand) in breast walls and retaining walls including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	44.96 Cum			Per Cubic metre	
4	Stone filling behind retaining wall per HP.PWD specification 1990 Volume - I including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	20.47 Cum			Per Cubic metre	
5	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 110mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification Clauses 614, 709, 1204.3.7 including carriage of materials within all leads and lifts as per direction of Engineer-in-charge.	22.80 Rmt.			Per Running metre	
6	Providing and laying cement concrete 1:2:4 (1 cement:2 Sand: 4 graded stone aggregate 20mm nominal size) and curing complete excluding cost of form work in foundation and plinth including carriage of materials within all leads and lifts.	1.39 Cum			Per cubic metre.	
<b>Total</b>						

- i Rates should be quoted for all leads, lifts and all heights irrespective of any floor level etc.  
ii Sample of all the materials to be used on work shall be get approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of Indian standards.

  
Executive Engineer  
Shimla Division No.III  
HP PWD. Shimla-3.

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

NO.SD-III-CB-Tender/2021-22- 33725  
To


Dated:- 10-3-22

The Executive Engineer(IT Cell)  
Nigam Vihar, Shimla-2

Subject:- Tender Notice

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on department website as per notification of Principal Secretary (PW) to the Govt. of HP vide letter No.PBW(B)A(3)1/2020 dated 16<sup>th</sup> July, 2021 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:- as above

  
Executive Engineer,  
Shimla Division No-III,  
HP.PWD.Shimla-3



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
\*NOTICE INVITING TENDER\***

Sealed item rate tenders on form No. 6&8 are hereby invited by the Executive Engineer, Shimla Division No. III, HP.PWD, Shimla-3 on behalf of the Governor of H.P. for the following works from the eligible Contractors/Firms enlisted in HP.PWD, so as to reach in his office on or before 17-03-2022 up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending Contractors/Firms or their authorized representatives. The tender form can be had from his office against cash payment (non-refundable) on any working day up to 4.00 P.M. on 16-03-2022 and the application for issue of tender form shall be received up to 4.00 P.M. on 16-03-2022.

The earnest money in the shape of National saving Certificate/Time deposit account/saving account in any of the post office in HP, duly pledged in favour of Executive Engineer, Shimla Division No-III must accompany with the application form for the tender offer. Conditional tender and the tender received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tender without assigning any reason there to. Other conditions are applicable as perform No. 6&8. The offer shall remain open for 30 days.

Sr. No	Name of work	Estimated Cost	Earnest money	Time	Form No	Cost of form
1	Construction of retaining wall near exit road of Armsdale building below stand for transformer at H.P Secretariat Chotta Shimla. <i>under Smart City.</i>	Rs.2,13,997/-	Rs.4280/-	One Month	6&8	350/-

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

**Terms & Conditions:-**

- The contractor/firm shall have his GST No. and attested copy of the same be attached with the application for issue of tender form.
- The contractor/firm should attach attested copy of registration/renewal.
- Copy of PAN card be attached with the application form

*[Signature]*  
Executive Engineer,  
Shimla Division No-III,  
HP.PWD Shimla-3.

Dated:- 10-3-22

**NO.SD-III-CB-Tender/2021-22-**

Copy forwarded for the following for information and necessary action to:-

- The Engineer-in -Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla-2.
- The Deputy Commissioner Distt. Shimla-1.
- The Superintending Engineer 4th Circle in H.P, PWD Shimla with the request to issue necessary certificate regarding display of above tender notice in the notice board of circle office in view of the Principal Secretary (PW) to the H.P notification No.PBW (B) A (3)1/2020.Dated:-Shimla-2 the 07January, 2021 and even file No.PBW(B)A(3)1/2020 Dated 16 July,2021 Please.
- The Executive Engineer, IT wing to the Engineer-in -Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla- 2 along with schedule of Quantity through (e-mail) for taking necessary action in view of principal Secretary(PW) to the Government of Himachal Pradesh notification No.PBW (B)A(3)1/2020 dated 16<sup>th</sup> July,2021.
- The Municipal Commissioner M.C. Shimla.
- All the Assistant Engineers working under this Division.
- The president contractor/association Shimla.
- Notice board

*[Signature]*  
Executive Engineer,  
Shimla Division No-III,  
HP.PWD Shimla-3.