

Himachal Pradesh
Public Works Department

No:- PW/TDD/GA/NIT/2021-22-
To

19414-15

Registered

Dated:- 02-03-2022.

✓ The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar Shimla-2.

Subject:-

Publication of tender Notice.

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting tender for uploading on department HPPWD website as per notification Pr. Secy (PW) to the Govt. of H.P. letter No. PBW(B) A(3) 1/2020 dated Shimla-2 the 16th July 2021 as the work mentioned in the tender notice are urgent in nature in public interest and required immediate action.

DA/Notice inviting tender, Schedule of Quantity and Certificate

Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi.

Copy forwarded to the Computer Cell o/o Executive Engineer (IT Cell), Nigam Vihar Shimla-2 for information and further necessary action please.

Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi.

NOTICE INVITING TENDER

Short terms tenders of Form 6 & 8 hereby invited by the Executive Engineer, Tauni Devi Division, HP:PWD., Tauni Devi on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 09.03.2022 upto 1.00 PM.
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable):- 09.03.2022 (2.00 PM to 5.00 PM),
3. Date of receipt of Tender:- 10.03.2022 at 11.00 AM. 4. Date of opening of Tender:- 10.03.2022 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	(i) A/R & M/O Murli Manohar Temple at Sujanpur Tihra Distt. Hamirpur (H.P) (SH:- White Washing, painting, distempering etc. (ii) A/R & M/O Holi Mela Stage at Sujanpur Tihra Distt. Hamirpur (H.P) (SH:- Painting, distempering)	282801	5700	Two Months	Rs. 350/-	Class-D
2	A/R & M/O various roads under Sujanpur Section-II in sub-Division Sujanpur.(SH:- Repair of pot holes on Sujanpur to Sandhol road km. 0/0 to 1/500).	497083	10000	Two Months	Rs. 350/	Class-D
3	A/R & M/O various roads under Sujanpur Section-II in sub-Division Sujanpur.(SH:- Repair of pot holes on link road Sidhu Chowk to bus stand and Mini Secretariat Km 0/0 to 0/600)	498190	10000	Two Months	Rs. 350/	Class-D
4	Repair and maintenance on various road under Sujanpur Sub-Division (Chabutra section)(SH:- Hiring of JCB/front end loader for removal of slips dressig of beams, clearance of drain).	98100	2000	Two Months	Rs. 350/	Class-D
5	C/O link road Chalokhar Balh Swahal road Km 0/0 to 3/0.(SH:-P/L interlocking paver block at RD 1/735 to 1/795) (Under MMGSY)	405373	8100	Two Months	Rs. 350/	Class-D
6	C/O link road to house of Sh. Rangila Ram Freedom Fighter village Lag Devi.(SH:- C/O cement concrete rigid pavement at RD. 0/259 to 0/302.50).(Deposit Work)	397977	8000	Two Months	Rs. 350/	Class-D
7	Improvement of Black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915. (SH:- Improvement of curves at RD. 6/461.40 to 6/467.70).	497106	10000	Two Months	Rs. 350/	Class-D
8	C/O link road from Bhatlamber (Shiv Mandir) to Kheri via Lower Dudhla from Km 0/0 to 1/0.(SH:-C/O PCC R/Wall at Km 0/180 to 0/197) (Under MMGSY)	486996	9800	Two Months	Rs. 350/	Class-D
9	C/O link road from Ropra to Guhal Km 0/0 to 2/0.(SH:- C/O 600mm dia hume pipe culvert at RD 1/180) (Deposit Work)	92701	1900	Two Months	Rs. 350/	Class-D

10	C/O link road to village Dhanwana km. 0/0 to 0/415.(SH:- formation cutting 5/7mtr. Wide road in km. 0/225 to 0/415).(Under Minor Works).	99799	2000	Two Months	Rs. 350/	Class-D
----	--	-------	------	------------	----------	---------

The earnest money in the shape of National Saving Certificate/ Time Deposit/ Saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

SPECIAL CONDITIONS:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertained considered in any case.
4. (i) No Violation of Social distancing.
(ii) Mandatorily wearing of face cover by everyone.
(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.



Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi.
For and on behalf of Governor of HP.

No:-PW/TDD/GA/NIT/2021-22- 19364-413

Dated:- 02.03.2022.

Copy forwarded for information & necessary action to:-


1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ), HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HP:PWD., Hamirpur. It is requested to display the notice in the Notice Board please.
4. All the Superintending Engineers/ Executive Engineers in HP:PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Tauni Devi.
7. The B. D. O. Tauni Devi.
8. The Municipal Committee, Hamirpur.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. Lok Mitra, Tauni Devi.
12. Various Contractors/ Firms.


Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi.

A certificate of exigencies/ emergencies

Certified that the tenders called vide this office letter No. No:-
PW/TDD/GA/NIT/2021-22- 19364-413 dated 02.03.2022 are in exigency/ emergency situation and as per
in public interest/ demands require immediate action uploaded in HPPWD website:-

Sr. No.	Name of Road
1	(i) A/R & M/O Murli Manohar Temple at Sujanpur Tihra Distt. Hamirpur (H.P) (SH:- White Washing, painting, distempering etc. (ii) A/R & M/O Holi Mela Stage at Sujanpur Tihra Distt. Hamirpur (H.P) (SH:- Painting, distempering)
2	A/R & M/O various roads under Sujanpur Section-II in sub-Division Sujanpur. (SH:- Repair of pot holes on Sujanpur to Sandhol road km. 0/0 to 1/500).
3	A/R & M/O various roads under Sujanpur Section-II in sub-Division Sujanpur. (SH:- Repair of pot holes on link road Sidhu Chowk to bus stand and Mini Secretariat Km 0/0 to 0/600)
4	Repair and maintenance on various road under Sujanpur Sub-Division (Chabutra section) (SH:- Hiring of JCB/front end loader for removal of slips dressig of beams, clearance of drain).
5	C/O link road Chalokhar Balh Swahal road Km 0/0 to 3/0. (SH:- P/L interlocking paver block at RD 1/735 to 1/795) (Under MMGSY)
6	C/O link road to house of Sh. Rangila Ram Freedom Fighter village Lag Devi. (SH:- C/O cement concrete rigid pavement at RD. 0/259 to 0/302.50). (Deposit Work)
7	Improvement of Black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915. (SH:- Improvement of curves at RD. 6/461.40 to 6/467.70).
8	C/O link road from Bhatlamber (Shiv Mandir) to Kheri via Lower Dudhla from Km 0/0 to 1/0. (SH:- C/O PCC R/Wall at Km 0/180 to 0/197) (Under MMGSY)
9	C/O link road from Ropra to Guhal Km 0/0 to 2/0. (SH:- C/O 600mm dia hume pipe culvert at RD 1/180) (Deposit Work)
10	C/O link road to village Dhanwana km. 0/0 to 0/415. (SH:- formation cutting 5/7mtr. Wide road in km. 0/225 to 0/415). (Under Minor Works).


Executive Engineer,
Tauni Devi Division,
HP:PWD., Tauni Devi.

Schedule of Quantity

NAME OF WORK:- (i) A/R & M/O Murti Manohar Temple at Sujapur Thira Dist. Hamirpur (H.P) (SH:- White Washing, painting, distemping etc)(ii) A/R & M/O Holi Mela Stage at Sujapur Thira Dist. Hamirpur (H.P)(SH:- Painting, distemping)

Estimated Cost:- Rs.282801.00
Earnest Money:- Rs.5700.00
Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	White washing with lime to give an even shade (three or more coats) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	514.27			Per square metre	
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade (two or more coats) over and including water thinnable priming coat with cement primer as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	651.20			Per square metre	
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1103.72			Per square metre	
4	Finishing walls with water proofing cement paint of required shade (Two or more coats applied @ 3.84 kg/10 sqm)(three point eighty four kilogram per ten square metre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	485.96			Per square metre	
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Two or more coats applied on walls @ 1.25 ltr/10 sqm (one point twenty five litre per ten square metre)over and including one coat of Special primer applied @ 0.75 ltr /10 sqm(zero point seventy five litre per ten square metre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	531.11			Per square metre	


	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm(zero point ninety litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm(zero point seventy five litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	182.52		Per square metre	
7	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm (zero point ninety litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/10 sqm(zero point eighty litre per ten square metre) of approved brand and manufacture as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.	577.23		Per square metre	
8	Providing and fixing expanded metal 20x60 mm(twenty into sixty millimetre) strands 3.25 mm(three point twenty five millimetre) wide and 1.6mm(one point six millimetre) thick for windows etc.including 62 x19 mm(sixty two into nineteen millimetre) beading of 11 nd class teak wood and priming coat with approved steel primer all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	19.20		Per square metre	
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting,hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	196.88		Per Kilogram	
10	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundations and plinth in Cement mortar 1:3 (one cement : three coarse sand) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	4.80		Per square metre	

15 mm(fifteen millimetre) cement plaster on rough side of single or half brick wall of mix 1:4 (one cement: four coarse sand) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.

Terms and Condition

1. Work shall be executed as per PWD specification.

9.60				Per square metre	
				Total	


Executive Engineer,
Tauni Devi Division
APPWD: Tauni Dev

Schedule of Quantity

STATE OF WORK:- A/R & M/O various roads under Sujapur Section-II in sub-Division Sujapur. (SH:- Repair of pot holes on Sujapur to Sandhol road Km 0/00 to 1/500)

Estimated Cost:- Rs.497083.00

Earnest Money:- Rs.10000.00

Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point zero seven five millimetre) to wet mix macadam (W.M.M) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.37			Per cubic metre	
2	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. On W.B.M / W.M.M @ 0.4kg/sqm(zero point four killogram per square metre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2200.34			Per square metre	
3	2 cm premium carpet surfacing with 1.8 cum(one point eight cubic metre) and 0.90 cum(zero point nine zero cubic metre) of stone chippings of 13.2 mm(thirteen point two millimetre) size and 11.2 mm(eleven point two millimetre) size respectively per 100 sqm(one hundred square metre) and 52 kg(fifty two kilogram) and 56 kg(fifty six kilogram) of hot bitumen per cum of stone chippings of 13.2 mm(thirteen point two millimetre) and 11.2 mm(eleven millimetre) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6(six) to 9(nine) tonne capacity etc. complete (tack coat to be paid for separately) With paving Asphalt grade VG - 10 heated and then mixed with solvent at the rate of 70 grams per kg(seventy grams per killogram) of asphalt as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2200.34			Per square metre	

... and laying seal coat of premixed fine aggregate (passing 2.36 mm(two point three six millimetre) and retained on 180(one hundred eighty) micron sieve) with bitumen using 128 kg(one hundred twenty eight kilogram) of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum(zero point six zero cubic metre) of fine aggregate per 100 sqm(one hundred square metre) of road surface, including rolling and finishing with road roller all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.

Terms and Condition

1. Work shall be executed as per PWD specification.

2200.34					Per square metre	
					Total	

Executive Engineer,
Tauni Devi Division,
MPPWD: Tauni Devi

Schedule of Quantity

NAME OF WORK:- A/R & M/O various roads under Sujapur Section-II in sub-Division

Sujapur.(SH:- Repair of pot holes on link road Sidhu Chowk to bus stand and Mini Secretariat

Km 0/0 to 0/6001

Estimated Cost:- Rs.498190.00

Earnest Money:- Rs.10000.00

Time:- Two Months

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm(fifty three millimetre) to 0.075 mm(zero point zero seven five millimetre) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8(eight) to 10(ten) tonne capacity to achieve the desired density, complete as per technical specification clause 302.3 direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	10.99			Per cubic metre	
2	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom On W.B.M / W.M.M. @ 0.4kg/sqm(zero point four kilogram per square metre) as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2138.12			Per square metre	
3	2 cm premix carpet surfacing with 1.8 cum(one point eight cubic metre) and 0.90 cum(zero point nine zero cubic metre) of stone chippings of 13.2 mm(thirteen point two millimetre) size and 11.2 mm(eleven point two millimetre) size respectively per 100 sqm(one hundred square metre) and 52 kg(fifty two kilogram) and 56 kg(fifty six kilogram) of hot bitumen per cum of stone chippings of 13.2 mm(thirteen point two millimetre) and 11.2 mm(eleven millimetre) size respectively, including a tack coat with hot straight run bitumen, including consolidation with road roller of 6(six) to 9(nine) tonne capacity etc. complete (tack coat to be paid for separately) With paving Asphalt grade VG - 10 heated and then mixed with solvent at the rate of 70 grams per kg(seventy grams per kilogram) of asphalt as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2138.12			Per square metre	

providing and laying seal coat of premixed fine aggregate (passing 2.36 mm(two point three six millimetre) and retained on 180(one hundred eighty) micron sieve) with bitumen using 128 kg(one hundred twenty eight kilogram) of bitumen of grade VG - 10 bitumen per cum of fine aggregate and 0.60 cum(zero point six zero cubic metre) of fine aggregate per 100 sqm(one hundred square metre) of road surface, including rolling and finishing with road roller all complete as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents. The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.

2138.12

Per square
metre

Total

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
MPPWD, Tauni Devi.

Schedule of Quantity


Estimated Cost:- 98100.00
Earnest Money:- 2000.00
Time:- Two Months.

NAME OF WORK:- Repair and maintenance on various road under Sujapur Sub-Division(Chabutra Section) .(SH:- Hiring of JCB/front end Loader for removal of slips dressing of beams, clearance of drain).

Sr.N o.,	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Hiring of J.C.B. (front end loader 1 cum capacity) for removal of slips including transportation P.O.L. repair and other charges operator and helper shall also be deployed by the contractor working hours will be 9:00AM to 5:00 PM. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	109.00 hours			Per hour	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HB/PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 405373.00
Earnest Money:- 8100.00
Time:- Two Months.

NAME OF WORK:- C/O link road Chalokhar Balh Swahal road km. 0/0 to 3/0. (SH:- P/L interlocking paver block at RD. 1/735 to 1/795) (Under MMGSY).

Sr.N o.,	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m,(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	17.28			Per Cum.	
2.	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. With material conforming to Grade-II (size range 53 mm to 0.075 mm)(Fifty three millimeter to zero point seven five millimeter) having CBR Value-25 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	18.60			Per Cum.	
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	28.80			Per Cum.	
4	Centering and shuttering including strutting, propping etc. and removal of form work for : Retaining walls, return walls, walls (any thickness) including attached plasters, buttresses, plinth and string courses filets, kerbs and steps etc. as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	72.00			Per Sqm.	
5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness and size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in- Charge. 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	186.00			Per Sqmt.	
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	0.72			Per Cum.	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

Executive Engineer,
Tauni Devi Division,
B.P.PWD., Tauni Devi

Schedule of Quantity

Estimated Cost:- 397977.00
Earnest Money:- 8000.00
Time:- Two Months.

NAME OF WORK:- C/O link road to house of Sh. Rangila Ram Freedam Fighter village Lag Devi,(SH:- C/O cement concrete rigid pavement at RD. 0/259 to 0/302.50). **(Deposit Work)**

Sr. No.,	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m.(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	76.34			Per Cum.	
2.	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density as per direction of Engineer-in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	13.05			Per Cum.	
3.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one Cement : three coarse sand): six graded stone aggregate 40 mm(forty millimeters nominal size), as per direction of Engineer- in -Charge, including entire carriage of material within all leads and lifts and other incidentals.	55.13			Per Cum.	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate 20 mm nominal size) (twenty millimeters nominal size), as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals	13.05			Per Cum.	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauri Devi Division,
HP.PWD., Tauri Devi.

Schedule of Quantity


Estimated Cost:- 497106.00
Earnest Money:- 10000.00
Time:- Two Months.

Name of Work:- Improvement of Black spot on Tauni Devi Uhal Kakkar Bajrol Jungle Beri road km. 0/0 to 30/915. (SH:- Improvement of curves at RD. 6/461.40 to 6/467.70).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm. (thirty centimeter) in depth, 1.5m (one point five meter) in width as well as 10 sqm. (ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50m (fifty meter) and lift upto 1.5m (one point five metre) as directed by Engineer-in-Charge. Hard rock (blasting prohibited), including entire carriage of material within all leads and lifts and other incidentals.	761.44			Per cubic Metre.	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
MP:PWD., Tauni Devi

Schedule of Quantity
NAME OF WORK:- C/O link road from Bhatlamber (Shiv Mandir) to Kheri via Lower Dudhla from Km 0/0 to 4/0.(SH:- C/O PCC R/Wall at Km 0/180 to 0/197)(UNDER MMGSY)

NAME OF WORK:- C/O link road from Bhatlamber (Shiv Mandir) to Kheri via Lower Dudhla from Km 0/0 to 4/0.(SH:- C/O PCC R/Wall at Km 0/180 to 0/197)(UNDER MMGSY)					Estimated Cost:- Rs.486996.00	
					Earnest Money:- Rs.9800.00	
					Time:- Two Months	
Sr. No.	Description of Items	Qty.	In Fig.	Rate In Words	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm(thirty centimetre) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m(fifty metre) and lift upto 1.5 m(one point five metre), as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	68.85			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (one cement : five fine sand : ten graded stone aggregate 40 mm(forty millimetre) nominal size)as directed by Engineer-in-charge all kinds of soil including entire carriage of material within all leads, lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	89.93			Per cubic metre	
3	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A,including jointing with seal ring conforming to IS : 5382, leaving 10 mm(ten millimetre) gap for thermal expansion, (i) Single socketed pipes. B1200 110 mm(one hundred ten millimetre) diameter as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	35.00			per running metre	
4	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, (any thickness) including attached pilasters,buttresses, plinth and string courses fillets, kerbs and steps etc as per the direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents.The rates are inclusive octrol, royalty, Malkana,toll tax, GST or other taxes imposed by the Government.	180.00			Per square metre	
Government						Total

Terms and Condition

1. Work shall be executed as per PWD specification.


Executive Engineer,
Tauni Devi Division,
HPPWD: Tauni Dev.

Schedule of Quantity

NAME OF WORK:- C/O link road from Ropa to Guhal km. 0/0 to 2/0. (SH:- C/O 600mm dia hume pipe culvert at RD. 1/180). **(Deposit work).**

Estimated Cost:- 92701.00.
Earnest Money:- 1900.00
Time:- Two Months.

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m(one point five metre) in width as well as 10 sqm(ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m,(one point five metre) as directed by Engineer-in-charge. All kinds of soil, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	27.09			Per Cum.	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (one cement: three sand: six graded stone aggregated 20mm (twenty millimeters) nominal size, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	1.48			Per Cum.	
3	Providing and laying mechanically mixed and vibrated cement concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal 1:2.5:5 (one cement: two and half sand: five stone aggregate 20mm(twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification clause 802.803.1202 and 1203, as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.	12.66			Per Cum.	
4	Cement concrete flooring 1:2:4 (one cement : two sand: four graded crushed stone aggregate 20 mm (twenty millimeters nominal size) laid in one layer finished with a floating coat of neat Cement as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	2.76			Per Sqmt.	
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 600 mm dia R.C.C. pipe. as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.	5.00			Per Rmt.	
					Total:-	

Terms and Condition:-

1. Work shall be executed as per PWD specification.

 Executive Engineer,
Tauni Devi Division
HP.PWD., Tauni Devi.

Schedule of Quantity

Estimated Cost:- 99799.00
 Earnest Money:- 2000.00
 Time:- Two Months.

Name of Work:- C/O link road to village Dhanwanana km. 0/0 to 0/415. (SH:- formation cutting 577 mtr. wide road in km. 0/225 to 0/415). (Under Minor Works)

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount.
			In fig.	In Words.		
1.	Excavation in hilly areas in all heights and depths and in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling /wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the technical specification clause 302.1603.1, 1603.2 sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful material for filling in road ways, camber, embankment for grade improvement and disposal of all un-useful material to required width of the road or on approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and carriage of machineries materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and or labour if required. Any loss to the public/private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts.	761.53			Per cubic Metre.	
	Total:-					

Terms and Condition:-

1. Work shall be executed as per PWD specification.


 Executive Engineer,
 Tauni Devi Division,
 HP:PWD., Tauni Devi