

**Himachal Pradesh
Public works Department**
NO-PW-JDT-EA-I Tender NIT/2022-23:-

1125-27

Dated:- 29/04/22

To,

The Executive Engineer (IT Cell)
Nigam Bihar Shilma-2

Subject:-

Publishing of Tender notice

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Pr. Sec.(PW)to the Govt.of HP letter No-PBW(B)A9(3)1/2020dated Shilma -2the 16th july 2021 as the work mentioned in the tender notice are urgent in nature and public interest

DA:- Notice Inviting Tender

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Copy forwarded the Superintending Engineer 10th Circle
Bilaspur HP PWD Bilaspur for information please

Copy forwarded to the Computer Cell O/O Executive Engineer
(IT Cell) Nigam Bihar Shimla -2 for information and further necessary action action

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Short terms tenders on form 6 & 8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender

Form a/w requisite documents:-

10/05/2022 up to 02:30 PM

2. Date of issue/sale of Tender forms against

Cash payment (Non-refundable):-

11/05/2022 up to 03:00 PM

The tender shall be received up to **11:00A.M. on 12/05/2022** and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on **12/05/2022.**

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta a must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

S.No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit	D class
1.	R/R damages in Ghumarwin Berthin Shahtalai MDR km 0/0 to 31/0 (SH:- Repair to pot holes in km 30/0 to 31/0)	346215/-	6900/-	350/-	Two Month	D
2.	C/O Rest House at Jhandutta Distt. Bilaspur HP (SH:- C/O Building Portion , Water supply & Sanitary installation, RWH system and Site development & etc.(SH:- Preparation of detailed / working estimate) N.R Building	77500/-	1600/-	350/-	Three Month	D
3.	C/O Community Bath rooms Near GPS Vijaypur Sungal road (SH:-C/O two Bath rooms Near GPS Vijaypur.) Deposit Work	258577/-	5200/-	350/-	Three Month	D
4.	A/R & M/O Mallari to Kallar road km 0/0 to 6/0 (SH:- Repair Of pot holes in km 4/0 to 5/435)	93344/-	1900/-	350/-	Three Month	D
5.	R/R damages on Various roads under Sub-Division Jhandutta (Section Gehrwin) (SH:- Hiring of Tractor with Trolly including Labour Hiring)	98750/-	2000/-	350/-	Three month	D
6.	M/T on link road Balhseena to House of Sh. Jugdev Singh Captain Balhseena km 0/00 to 0/328 (SH:- P/L 20 mm thick premix carpet surface at RD 0/0 to 0/328) Under D.C. Deposit	229247/-	4600/-	350/-	Three month	D
7.	Addition/ Alteration /Renovation of veterinary Hospital Jhandutta Distt. Bilaspur HP (SH:- C/O V.O Room) Under Deposit work	499340/-	10000/-	350/-	Three month	D
8.	R/R damages on various roads under Sub-Division Jhandutta (SH:-Hiring of Tractor with Trolly including Labour Hiring and White washing on parapets.)	102359/-	2000/-	350/-	One month	D
9.	C/O B.J.S.M road km 0/0 to 20/00 (SH:- C/o R/Wall at RD 16/977 to 16/990) Under OTMNP	228456/-	4600/-	350/-	Three month	D
10	C/O Nekhlehra to Lulhar via Pasol road km 0/0 to 5/525 (SH:- P/L of WMM from RD 0/00 to 1/123) Under NABARD	496727/-	9900/-	350/-	Two month	D

11	C/O Nekhlehra to Lulhar via Pasol road km 0/0 to 5/525 (SH:- P/L of WMM from RD 1/123 to 2/250) Under NABARD	498501/-	10000/-	350/-	Two month	D
12	C/O Kotlu Sunhani road km 0/0 to 4/500 (SH:- C/O B/wall at RD 2/732 to 2/739, C/O R/wall at RD 2/782 to 2/790, Edge wall at junction point toward sargal side & C/O 600 mm dia RCC HPC at RD 1/095)	176483/-	3500/-	350/-	Three month	D
13	C/O Bachretu to Naghiar road km 0/0 to 5/000 (SH:- C/O B/Wall at RD 3/107 to 3/122 & R/Wall at RD 3/121 to 3/129) Under SCSP.	136006/-	2700/-	350/-	Three month	D
14	R/R damages on various roads under Berthin Sub- Division HPPWD Berthin (Section- Berthin) (SH:- Hiring of Tractor with Trolly including Labour Hiring)	99650/-	2000/-	350/-	Two Month	D
15	C/o link road to village Kahli G.P Gehrwin KM 0/0 to 0/500. (SH:- C/O B/wall & P/F Pipe railing C.C. 1:3:6 (Turning Point) at RD 0/330 to 0/345) Under OTMNP.	234908/-	4700/-	350/-	Three Month	D
16	Imp. Of Gehrwin Behna Jattan road km 0/0 to 2/500 (SH:- Imp. Of Sharp curve at RD 6/375 to 6/450 & RD 7/105 to 7/180)	99421/-	2000/-	350/-	One Month	D
17	C/O Talai to Dhani road km 0/0 to 7/0 (SH:- C/O cement concrete Paver Block at RD 4/075 to 4/191)	491434/-	9800/-	350/-	Three Month	D
18	C/O Talai to Dhani road km 0/0 to 7/0 (SH:- C/O cement concrete Paver Block at RD 3/960 to 4/075)	487208/-	9700/-	350/-	Three Month	D

TERMS & CONDITIONS:

1The tender forms will not be issued to those contractors whose performance is not found Satisfactory.

2. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.

3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.

4. Application without all documents will not be entertained.

5. Proxy Application will not be entertained.

Executive Engineer
Jhandutta Division
HPPWD Jhandutta.

No-PW-JDT-CB-Tender NIT/2022-23:-

1114-24

Dated:- 29/04/2022

Copy forwarded to the following for information and necessary action Please:-

1. The Engineer -in-Chief HP PWD Nirman Bhawan Shimla
2. All the Chief Engineer in HP PWD
3. The Superintending Engineer 10th Circle HP PWD Bilaspur
4. All the Assistant Engineer Working under this Division
5. The B.D.O Jhandutta
6. A/B & D/B in this office
7. Various Contractors working under this office
8. Notice Board

Executive Engineer
Jhandutta Division
HPPWD Jhandutta


Certificate

**Certified that the tenders called vide this office letter
No. PW-JDT EA-I-Tender /2022-23- 1114-24 dated
29/04/22 is emergent nature and in Public interest**

Executive Engineer
Jhandutta Division
HPPW, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damages in Ghumarwin Berthin Shahatalai MDR km 0/0 to 31/0 (SH:- Repair to pot holes in KM 30/0 to 31/0)		SCHEDULE OF QUANTITIES				
		Estimated cost:- ₹		346215.00	Only	
		Earnest Money:- ₹		6900.00	Only	
		Time allowed:- Two Month				
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount
1	Repair to pot holes by removal of failed material, trimming the sides to vertical and levelling the bottom, cleaning the same with compressed air or any appropriate method filled with 75mm B.M., applying bitumen emulsion prime coat at the bottom and bitumen emulsion tack coat on sides and on bottom as per technical specifications Clauses 502, 503 and 504. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	19.37			Per Cubic metre	
2	Patch repair on already filled pot holes with 75 mm BM with 20 mm premix carpet and seal coat Type B as per drawings and technical specification Clause 1904.2, 508 and 510 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	258.07			Per square metre	
3	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2, 503 and 508.1.. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	966.86			Per square metre	
Total:-						


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :-Construction of Rest House at Jhandutta Distt Bilaspur HP. (SH:- Construction of Building Portion, Water Supply & Sanitary installation , RWH system and Site Development & etc.) (SH:- Preparation of Detailed /working estimate). NR Building		Estimated cost:- ₹ 77500.00				Only
		Earnest Money:- ₹ 1600.00				Only
		Time allowed:- Three Month				
Sr. No.	Description of Items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Prapration of detailed estimate for the Construction of Rest House at Jhandutta Distt Bilaspur HP. (SH:- Construction of Building Portion, Water Supply & Sanitary installation , RWH system and Site Development & etc.) and obtaining necessary approval from compiant authority as per direction of Engineer- in -charge. The rate includes, octry, malkana. toll tax, goods & Service tax, building and other construction worker, welfare cess royalty or any other tax, leavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00			Per estimate	
Total:-						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

NAME OF WORK:- C/o Community Bath rooms Near GPS vijaypur Sungal road (SH:- C/o two Bathrooms Near GPS Vijaypur. Deposit Work.

NAME OF WORK:- C/o Community Bath rooms Near GPS vijaypur Sungal road (SH:-						Estimated cost:- ₹ 258577		Only
C/o two Bathrooms Near GPS Vijaypur. Deposit Work.						Earnest Money:- ₹ 5200		Only
						Time allowed:- three month		
Sr. No.	Description of iteams	Quantity	Rates in		Unit	Amount		
			Figures	words				
1	Excavaion in foundation trenches etc. earth work in all classification of soil such as pick work, jumper work, blasting work, pick jumper blasting work, blasting work in soft and hard rock, saturated soil, any other mixed variety of soil in dry or saturated conditions up to any depth and lifts up to any height, de-watering, including/ chiseling/ wedging out rocks where blasting is prohibited, de-watering including pumping or bailing out water where required and removal of slush which may arise during the execution including stacking the serviceable and unserviceable material separately as directed. Then returning the stacked soil in 15 cm (Fifteen centimeter) layer when required in to plinths and side of foundation etcetra consolidating each deposited layer by ramming and watering and then desposing of all surplus unserviceable/excavated earth with in all leads and lifts and carriage of material tools, machinery as per direction of Engineer-In-Charge As per HP.PWD specification 1990 vol-I clause 7.1 with in all leads and lifts and other incidentals. The rate includes, octroi, Malkhana, Toll tax , Goods and Service Tax, building and other constrecution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.52			Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (One cement: Four sand: Eight graded crushed stone aggregate 40 mm (forty millimeters nominal size with cement contants not less than 170 kg/per cum (One hundred seventy kilogram) per cubic meter machanical mixed and curing complete, excluding cost of form work in foundation and plinth as per HP.PWD Specification clause 9.3.1. including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	48.62			Per cubic metre			
same								

3	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in Foundations, footings bases of columns and the like and mass concrete including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.60				Per cubic metre	
4	Providing Tor steel Fe-500D or SAIL/ TISCO/ Jindal reinforcement for Reinforced Cement Concrete work including bending, binding and placing in position complete in all heights including cost of binding wires completed and other incidentals due for its completion for all floors level as per HP.PWD Specification clause 2.28.2. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same. As per HP.PWD specification 1990 vol-1 clause 2.28.1.	262.09				Per Kilogram	
5	Providing form work with steel plates 3.15 mm (Three point fifteen millimetres) thick welded with angle iron in frames, 30x30x5mm (Thirty into Thirty into five millimetres) so as to give a fair finish including centering, shuttering, strutting and propping etcetra with wooden battens and ballies upto any height of propping and centering below supporting floor to ceiling up to all floor level and removal of the same for insitu reinforced concrete and plain concrete work as per HP.PWD Specification 1990 vol-1 clause 8.1. including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.32				Per square metre	
i	Sides and soffits of beams, beam haunchings, cantilevers, bressumers and lintels upto any depth in all heights from floor.	20.16				Per square metre	
ii	Flat surfaces such as soffits of suspended floors, roofs, landings and the like, floors etc. upto any thickness.	18.00				Per running metre	
iii	Edges of slabs and breaks in floors and walls up to any width.						

6	Providing and laying cement concrete 1:1.5:3 (1 cement : 1.5 sand : 3 graded stone aggregate 20mm. nominal size) and curing complete excluding cost of form work and reinforcement for reinforced concrete work in Suspended floors roofs, landings and shelves and their supports, balconies, beams, girders, bressumers and cantilevers upto floor two level. including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, welfare cess royalty or any other tax, levy or cess in building and other construction worker, shall not entertain any claim whatsoever in this respect of the same.	2.02				Per cubic metre	
7	Second class brick work using common burnt clay building bricks of approved kiln in super structure upto all height and depth in cement mortar 1:6 (one cement : six sand) including curing complete and including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	9.84				Per cubic metre	
8	6mm (six millimeter) thick cement plaster to ceiling with cement mortar 1:3 (one cement : three sand) including curing and including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.42				Per square metre	
9	15mm (Fifteen millimeter) cement plaster in single coat on fair side of brick/concrete/stone walls for exterior plastering upto floor all level including arrises, internal rounded angles, internal rounded angles, chamfers and or rounded angles not exceeding 80mm (eighty millimeter) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including curing and including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	89.11				Per square metre	

10	Stone filling under floor including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.65				Per cubic metre	
11	Providing and fixing 10mm (ten millimetre) thick antiskid water proof stain and impact resistant heavy duty vitrified tiles nico or equivalent 600x600x10mm (six hundred into six hundred into ten millimetre) manufactured of approved shade and colour in flooring treads of steps and landings laid over 12mm (twelve millimetre) thick cement mortar 1:3 (one cement : three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.02				Per square metre	
12	White glazed tiles 6mm (six millimetre) thick in flooring, treads of steps and landing laid on a bed of 12mm (twelve millimetre) thick cement mortar 1:3 (one cement : three sand) and jointed with cement slurry complete upto all floor level in all respect including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.69				Per square metre	
13	Distemping (two coats) with oil bound washable distemper of approved brand and manufacture Nerolic, Berger, Assian paint and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth. Priming coat with distemper primer including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same as per HP.PWD specification 1990 volume-1 clause 16.	28.64				Per square metre	

14	Finishing wall with weather proof exterior grade emulsion of approved design (appuxitima) or its equivalent on undecorated wall surface (Two coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constrction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.05				Per square metre	
15	Providing second class deodar wood work in frames of doors, windows, clere story windows and other frames wrought framed and fixed in position including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.16				Per cubic metre	
16	Providing and fixing 40mm (forty millimeter) thick second class deodar wood panelled glazed or panelled and glazed shutter for doors, windows and clere story windows including black enamelled iron butt hinges with necessary screws including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.77				Per square metre	
17	Providing and fixing anodized heavy duty aluminum sliding door bolt anodized 300x16mm (Three hundred into sixteen millimeter) transparent or died to required colour and shade with bolts and nuts screws etcetra as approved by the Engineer-In-Charge complete including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	

18	Providing and fixing mat finish aluminum heavy duty handles anodized 125mm (One hundred twenty five millimetre) transparent or dyed to required shade and colour with necessary screws etcetra as approved by the Engineer-In-Charge including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00				Each	
19	Providing and fixing heavy duty aluminum tower bolts (Barrel type) anodized 300x10mm (Three hundred into ten millimetre) transparent or dyed to required shade and colour with screws etcetra as approved by the Engineer-In-Charge complete in all respect including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.00				Each	
20	Applying priming coat over new wood and wood based surface after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting with ready mixed paint brushing wood primer pink complete including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.55				Per square metre	
21	Painting two coats (excluding priming coat) on new wood and wood based surfaces, with white enamel paint to give an even shade including cleaning the surface of all dirt, dust and other foreign matter, sand papering and stopping including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.55				Per square metre	

22	Providing and fixing 15mm (fifteen millimetre) diameter C.P.brass bib tap heavy duty with capstan head including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	
23	Providing and fixing bath shower including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	
24	Providing and fixing to wall, ceiling and floor galvanized mild steel tubes (medium grade) tube 15mm (fifteen millimeter nominal size) fitting and clamps including making good the walls, ceiling and floor complete in all respect including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00				Per running metre	
25	Providing and fixing PVC 1000 ltr. (one thousand litre) water storage tank of ISI : 12701 marked, G.I. inlet and outlet connection, 15 mm nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting upto all height above ground level including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00				Each	
26	Providing and fixing PTMT grating round of approved quality and colour 100 mm nominal dia. including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	


27	ding Providing and fixing and fixing to wallPTMT ceilingsoap and floor dish with holder of approved quality and colour with steel screws and rawal plugs including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	
28	Providing and fixing 600mm x 20mm C.P. Brass Towel rail complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	
29	Providing and fixing 110mm x 75 mm (one hundred ten into seventy five millimetre) diameter PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etcetra complete in all respect including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Each	


 Executive Engineer,
 Jhandutta Division,
 H.P.W.D., Jhandutta.

SCHEDULE OF QUANTITY


Name of Work :- A/R & M/O Mallari to Kallar road km 0/0 to 6/0 (SH:- Repair of Pot holes in km 4/0 to 5/435)

holes in km 4/0 to 5/435)									
maunari to Kallar road km 0/0 to 6/0 (SH:- Repair of Pot									
Sr. No.	Description of iteams	Estimated cost:- ₹ 93344.00							
		Quantity		Earnest Money:- ₹ 1900.00		Only		Only	
		Time allowed:- Three Month		Rate		Unit		Amount	
		Figures	words						
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906,including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	272.75				Per Square Meter			
2	Repair to pot holes and removal of loose material, trimming of sides, clearing of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	409.10				Per Square Meter			
Total:-									


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damages on various roads under Sub- Division Jhandutta (Section Gehrwin) (SH:- Hiring of Tractor with Trolly including Labour Hiring)		Estimated cost:- ₹ 98750.00		Only		
		Earnest Money:- ₹ 2000.00		Only		
		Time allowed:- Three Month				
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Hiring of tractor with trolly for Shifting of materials carriage/ shifting of excavated material or any type of materials as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer- in- Charge.	20.00			Per day	
2	Hiring of labour for loading and unloading of material from tractor trolly and cleaning of road surface making ready the road surface to repair of pot holes etc as per the direction of Engineer- in- Charge.	205.00			Per day	
Total:-						


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :-M/T on link road Balhseena to House of Shri Jugdev Singh Captain Balhseena Km 0/00 to 0/328 (SH:- P/L 20 mm thick premix Carpet surface at RD 0/0 to 0/328), Under D. C. Deposit.		Estimated cost:- ₹ 229247.00			Only	
		Earnest Money:- ₹ 4600.00			Only	
		Time allowed:- Three Month				
Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Preparation of sub-grade by dressing to camber (Earth work for the cutting involved for sub-grade to be measured and paid for separately) depending upon the classification of soil complete as per HP.PWD., Specification as per direction of Engineer-in-charge. including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	48.00			Per square metre	
2	Consolidation of sub-grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP.PWD., specification as per direction of Engineer-in-charge. including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	48.00			Per square metre	
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 1 as per Technical Specification Clause 405, including carriage of material in all leads and lifts as per the direction of Engineer-in Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.25			Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty to one hundred kilonewtons) in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading -II as per MORD Technical Specification Clause 405, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	3.54			Per Cubic metre	

5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spreading primer at the rate of 0.70-1.0 kg per square metre (Zero point seven zero to one point zero kilogram) as per table 500.1(a) of MORD technical specification 2014, by mechanical means as per technical specification clause 502 of MORD technical specification 2014, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	1050.00			Per Square Metre	
6	Providing and applying tack coat with bitumen emulsion (RS-1) (one) using emulsion distributor at the rate of 0.20 to 0.25 kg (Zero point twenty to zero point twenty five) kilogram per Square metre as per table 500.2 of MORD technical specification 2014, on the prepared bituminous surface cleaned with hydraulic broom as per technical specification clause 503 of MORD technical specification 2014, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	1050.00			Per Square Metre	
7	Providing laying and rolling of open graded premix carpet of 20 mm (twenty millimeter) thickness composed of 13.2 mm to 5.6 mm (thirteen point two to five point six millimeter) aggregate either using penetration grade bitumen of emulsion to required line grade and level to serve as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with three wheel 80-100 KN (eighty to one hundred kilonewtons) static roller capacity, as per mord 2014 clause 506.1, finished to required level and grades to be followed by seal coat of type-B as per technical specification clause 508. (By mechanical means) Bitumen (S-90) (Ninety) including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government	1050.00			Per Square Metre	
8	Providing and laying seal coat for sealing the voids in bitumen surfaced laid to the specified levels, grade and cross fall using Type -C as per technical specification clause 508.3.4 of mord 2014 including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	1050.00			Per Square Metre	
Total:-						

Executive Engineer,
Jhاندута Division
HPPWD, Jhاندута

SCHEDULE OF QUANTITY

Name of Work :- Addition / Alteration/ Renovation of veterinary Hospital Jhandutta Distt. Bilaspur HP (SH:- C/o V.O. Room.) Under Deposit work.							Estimated cost:- ₹ 499340.00		Only
							Earnest Money:- ₹ 10000.00		Only
							Time allowed:- Three Month		
Sr. No.	Description of items	Quantity	Rate		Unit	Amount			
			Figures	words					
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto all, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a all lead. All kinds of soil. incidentals, lift up to any height stacking excavated soil up to all leads and lifts clear from the edge of excavation and then returning the stacked soil in fifteen centimetre thick layer when required into plinths, sides of foundation etcetra consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respect.	13.51			Per cubic metre				
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level in 1:4:8 (one Cement into four coarse sand) :into eight graded stone aggregate 40 mm (forty millimeter) nominal size) mechanically mixed, vibrated and curing complete excluding cost of form work in foundation and plinth including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.37			Per cubic metre				
3	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with Cement mortar 1:6 (one cement into six coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.86			Per cubic metre				

4	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0				0	
a	Foundations, footings, bases for columns	34.24				Per square metre	
b	Lintels, beams, plinth beams, girders, bressumers and cantilevers	29.16				Per square metre	
c	Suspended floors, roofs, landings, balconies and access platform	32.79				Per square metre	
d	Edges of slabs and breaks in floors and walls Under 20 cm wide	28.57				Per running metre	
.5 a	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement into one point five coarse sand) into three graded stone aggregate 20 mm (twenty millimeter) nominal size), including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.56				Per cubic metre	
b	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, filets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement 1:1.5:3 (one cement into one point five coarse sand) : three graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.98				Per cubic metre	


c	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Mild steel and Medium Tensile steel bars including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1610.86				Per kilogram	
6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.17				Per cubic metre	
7	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 (three) ply veneering with vertical grains or cross bands and face veneers on both faces of shutters, 35 mm (thirty five millimeter) thick including ISI marked Stainless Steel butt hinges with necessary screws including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.47				Per square metre	
8	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (one point four millimeter) in both directions with wire of dia 0.63 mm (zero point six three millimeter), for doors, windows and clerestory windows with hinges and necessary screws Kiln seasoned and chemically treated hollock wood including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.34				Per square metre	

9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in: Cement mortar 1:6 (one cement into six coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.28				Per cubic metre	
10	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement into six fine sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	122.2				Per square metre	
11	6 mm cement plaster of mix 1:3 (one cement into three fine sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.03				Per square metre	
12	Applying priming coat With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.47				Per square metre	
13	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	189.23				Per square metre	

14	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm (three hundred into three hundred millimeter) or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimeter) thick Cement Mortar 1:4 (one Cement into four Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram per square meter) including pointing the joints with white cement and matching pigments etc., complete, including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	21.76				Per square metre	
15	Cement plaster skirting up to 30 cm (thirty centimeter) height, with cement mortar 1:3 (one cement into three coarse sand), finished with a floating coat of neat cement. 18 mm (eighteen millimeter) thick including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3.22				Per square metre	
16	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete in 200 X 10 mm (two hundred into ten millimeter) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10				Each	
17	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete in 125 mm (one hundred twenty five millimeter) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10				Each	

18	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (one hundred into one hundred into seventy five millimeter) (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (one cement into two coarse sand into four graded stone aggregate 20 mm (twenty millimeter) nominal size), i/c necessary excavation, foundation concrete 1:5:10 (one cement into five fine sand into ten graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (one cement into three coarse sand) 12 mm (twelve millimeter) thick, finished with a floating coat of neat cement complete as per standard design With common burnt clay F.P.S.(non modular bricks of class designation 7.5 (seven point five) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1				Each	
19	Providing and fixing soil, waste and vent pipes 100 mm (one hundred millimeter) dia Sand cast iron S & S pipe as per IS: 1729 including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.5				per running meter	
20	Providing and fixing toilet paper holder C.P. brass including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1				Each	

21	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support i/c fittings & fixtures for tank shall be paid separately including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1000			per liter	
22	Providing and fixing wash basin with C.I. brackets, 15 mm (fifteen millimeter) dia CP Brass single hole basin mixer of approved quality and make, including painting of fittings and brackets, cutting and making good the walls wherever required White Vitreous China Wash basin size 550 X 400 mm (five hundred fifty into four hundred millimeter) with a 15 mm (fifteen millimeter) CP Brass single hole basin mixer including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1			Each	
23	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm (one hundred millimeter) sand cast Iron P or S trap, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1			Each	
Total:-						


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- R/R damages on various roads under Sub- Division Jhandutta
(SH:- Hiring of Tractor with Trolly including Labour Hiring and White washing on parapets).

SCHEDULE OF QUANTITIES						
Name of Work :- R/R damages on various roads under Sub-Division Jhandutta (SH:- Hiring of Tractor with Trolley including Labour Hiring and White washing on parapets).		Estimated cost:- ₹ 102358.00		Only		
		Earnest Money:- ₹ 2000.00		Only		
		Time allowed:- One Month				
Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Hiring of tractor with trolley for Shifting of materials carriage/ shifting of excavated material or any type of materials as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in-Charge.	40.00			Per day	
2	Hiring of labour for loading and unloading of material from tractor trolley and cleaning of road surface making ready the road surface to repair of pot holes etc as per the direction of Engineer-in-Charge.	135.00			Per day	
3	White washing with lime two coats on parapet walls, drains,B/walls and Bitumen drums etc, including preparation of surface by cleaning scraping etc,including thoroughly brooming the surface and remove all dirt, dust, mortar dirt and other foreign matter including carriage of materials by mechanical means with in all leads and lifts and as per MORTH Specifications and as per direction of the Engineer-in-charge.	438.75			Per square meter.	
Total:-						

Executive Engineer,
Jhandutta Division
HPPWD Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- C/o B. J. S.M. road Km 0/0 to 20/00 (SH:- C/o R/Wall at RD 16/977 to 16/990). Under OTMNP.

Name of Work :- C/o B. J. S.M. road Km 0/0 to 20/00 (SH:- C/o R/Wall at RD 16/977 to 16/990). Under OTMNP.							Estimated cost:- ₹ 228456.00		/-Only		
							Earnest Money:- ₹ 4600.00		/-Only		
							Time allowed:- three Month				
Sr. No.		Description of items	Quantity	Rate		Unit	Amount				
			Figures	words							
1		Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	39.65			Per Cubic Meter					
2		Providing and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement isto four sand isto eight graded stone aggregate 25 mm,(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	88.40			Per cubic metre					
3		Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.54			Per Cubic Meter					
4		Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	24.00			Each					
Total:-											

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- C/o Nekhlera to Lulhar via Pasol road Km 0/0 to 5/525 (SH:- Providing and laying of W/M from RD 0/00 to 1/123) Under NABARD.

Name of Work :- C/o Nekitera to Lullhar via Pasol road Km 0/0 to 5/525 (SH:- Providing and laying of W/MM from RD 0/00 to 1/123) Under NABARD.						
Sr. No.	Description of items	Quantity	Estimated cost:- ₹ 496727.00			
			Earnest Money:- ₹ 9900.00			
			Time allowed:- Two Month			
		Figures	Rate	Unit	Amount	
			words			
1	Scarifying the existing bituminous road surface to a depth of 150 mm (one hundred fifty) and disposal of scarified material with a lift upto all lead as per Technical Specification Clause 301.4. including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1370.06		Per square meter		
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 kN (eighty to one hundrey Kilonewton) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406. including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	565.99		Per cubic metre		
Total:-						

Executive Engineer
Jhandutta Division
HPPWD Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- C/o Nekhlara to Lulhar via Pasol road Km 0/0 to 5/525 (SH:- Providing and laying of WMM from RD 1/123 to 2/250) Under NABARD.

SCHEDULE OF QUANTITY						
Name of Work :- C/o Nekhlera to Luhar via Pasol road Km 0/0 to 5/525 (SH:- Providing and laying of W/M from RD 1/123 to 2/250) Under NABARD.				Estimated cost:- ₹ 498501.00		Only
				Earnest Money:- ₹ 10000.00		Only
				Time allowed:- Two Month		
Sr. No.	Description of items	Quantity	Figures	Rate	Unit	Amount
1	Scarifying the existing bituminous road surface to a depth of 150 mm (one hundred fifty) and disposal of scarified material with a lift upto all lead as per Technical Specification Clause 301.4, including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1374.94			Per square meter	
2	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100 kN (eighty to one hundred Kilonewton) weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406, including carriage of materials within all leads and lifts complete in all respect. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	568.01			Per cubic metre	
Total:-						

Executive Engineer
Jhandauta Division
HPPWD, Jhandauda

SCHEDULE OF QUANTITY

Name of Work :- Construction of Kotlu Sunhani road Km 0/0 to 4/500. (SH:- Construction of B/wall at RD 2/732 to 2/739, C/o R/wall at RD 2/782 to 2/790, Edge wall at Junction point toward sargal side & C/o 600 mm dia RCC Hume pipe culvert at RD 1/095). Under OTMNP.

Name of Work :- Construction of Kotlu Sunhani road Km 0/0 to 4/500. (SH:- Construction of B/wall at RD 2/732 to 2/739, C/o R/wall at RD 2/782 to 2/790, Edge wall at Junction point toward sargal side & C/o 600 mm dia RCC Hume pipe culvert at RD 1/095). Under OTMNP.							Estimated cost:- ₹ 176483.00		Only	
							Earnest Money:- ₹ 3500.00		Only	
							Time allowed:- Three Month			
Sr. No.		Description of items		Quantity	Rate		Unit	Amount		
				Figures	words					
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.			30.84			Per Cubic Meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone age. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.			76.60			Per Cubic Meter			
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.			28.00			Each			
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one into two) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 600 mm (six hundred millimeter) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.			7.50			Per running Metre			
Total:-										

Executive Engineer,
Jhantuta Division
HPPWD, Jhantuta

SCHEDULE OF QUANTITY

Name of Work :- Construction of Bachretu to Nagghiyar road Km 0/0 to 5/000 (SH:- C/O B/Wall at RD 3/107 to 3/122 & R/wall at RD 3/121 to 3/129) Under SCSP.

Estimated cost:- ₹ 136006.00	Only
Earnest Money:- ₹ 2700.00	Only
Time allowed:- Three Month	

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in-charge. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	19.20			Per Cubic Meter	
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.79			Per Cubic Meter	
3	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone age: 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	58.79			Per Cubic Meter	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1.00			Per Cubic Meter	
5	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe extending through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	38.00			Each	
Total:-						


 Executive Engineer
 Jharkhand Division
 HPPWD Jharkhand

SCHEDULE OF QUANTITY

Name of Work :- Construction of Bachretu to Nagghiyar road Km 0/0 to 5/000 (SH:- C/O B/Wall at RD 3/107 to 3/122 & R/wall at RD 3/121 to 3/129) Under SCSP.		Estimated cost:- ₹ 136006.00	Only
		Earnest Money:- ₹ 2700.00	Only
Time allowed:- Three Month			

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in-charge. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	19.20			Per Cubic Meter	
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.79			Per Cubic Meter	
3	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone age: 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	58.79			Per Cubic Meter	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1.00			Per Cubic Meter	
5	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment, wing wall return wall with 100 mm dia PVC pipe extending through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	38.00			Each	
Total:-						

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITIES						
Name of Work :- R/R damages on various roads under Berthin Sub- Division HPPWD Berthin (Section- Berthin) (SH:- Hiring of Tractor with Trolley including Labour Hiring)		Estimated cost:- ₹		99650.00	Only	
		Earnest Money:- ₹		2000.00	Only	
		Time allowed:- Two Month				
Sr. No.	Description of iteams	Quantity	Rate		Unit	Amount
			Figures	words		
1	Hiring of tractor with trolly for Shifting of materials carriage/ shifting of excavated material or any type of materials as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in-Charge.	30.00			Per day	
2	Hiring of labour for loading and unloading of material from tractor trolly and cleaning of road surface making ready the road surface to repair of pot holes etc as per the direction of Engineer- in- Charge.	169.00			Per day	
Total:-						

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road to village Kahli GP Gehrwini Km 0/0 to 0/500.
(SH:- C/O B/wall & P/F pipe railing C.C. 1:3:6 (Turning Point) at RD 0/330 to 0/345).
Under OTMNP.

Name of Work :- Construction of link road to village Kahli GP Gehrwain Km 0/0 to 0/500. (SH:- C/O B/wall & P/F pipe railing C.C. 1:3:6 (Turning Point) at RD 0/330 to 0/345). Under OTMNP.		Estimated cost:- ₹ 234908.00		Only	
		Earnest Money:- ₹ 4700.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
			Figures	words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	32.32			Per Cubic Meter
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	40.51			Per Cubic Meter
3	Providing weep holes in brick masonry/stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	24.00			Each
4	Providing and Laying cement concrete M-10 (Ten) graded crushed stone aggregate. 40 mm (forty millimetre) nominal size with minimum cement contents 260kg (two hundred sixty) kilogram, per cubic metre and curing complete, including cost of form work for plain /reinforce concrete in structures like U-shape drain, V- Shape drain, culverts, drains and other structure as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts, shoring and shuttering and curing complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.48			Per cubic metre

5	Providing and fixing in position pipe railing consisting of IS Rolled steel joist posts designation IS MB 100 (100x75) at 2.5 m interval and three rows of 50 mm dia steel pipes (light) including fixing in position on bridge deck complete as per drawing and technical specifications Clause 1208.2 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	45.00				Per running metre	
6	Providing concrete for plain /reinforced concrete in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203. Plain cement concrete 1:2:4 (one cement : two sand : four graded/crushed stone aggregate 20 mm (twenty millimetre) nominal mix. including carriage of materials . within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	16.81				Per cubic metre	
Total:-							

Executive Engineer,
Jhandutta Division
HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :-Improvement of Gehrwini Behnajatn road km 0/0 to 2/500
(SH:- Improvement of sharp Curve at RD 3/375 to 6/450 & 7/105 to 7/180)

(SH:- Improvement of sharp Curve at RD 3/375 to 6/450 & 7/105 to 7/180)		Estimated cost:- ₹		99421.00	Only
		Earnest Money:- ₹		2000.00	Only
		Time allowed:- one Month			
		Quantity	Unit	Figures	Rate
Sr. No.	Description of items				
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302,1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 45.32 Cubic metre @ Rs. 170/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	906.30	Per Cubic Meter		
Total:-					

Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- Talai to Dhani Road km 0/0 to 7/0 (SH:- C/o Cement Concrete Paver block at RD 4/0745 to 4/191).


Sr. No.	Description of items	Quantity	Estimated cost:- ₹ 491434.00		Only
			Earnest Money:- ₹ 9800.00		Only
			Time allowed:- Two Month	Unit	Amount
		Figures	Rate words		
1	Scarifying metalled (water-bound) road surface including disposal of rubbish, lead upto 50 m and consolidation of the aggregate received from scarifying with power road roller of 8 to 10 tonne capacity, including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi, and other tax	371.20		Per Cubic Meter	
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi.	37.12		Per Cubic Meter	
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge 80 mm thick C. C. paver block of M-30 grade with approved color design and pattern. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	371.20		Per cubic metre	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level within all leads & lifts carriage of material and other incidentals as per direction of Engineer-in-Charge including carriage of materials, 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octroi. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	11.79		Per cubic metre	
Total:-					


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

SCHEDULE OF QUANTITY

Name of Work :- Talai to Dhani Road km 0/0 to 7/0 (SH:- C/o Cement Concrete Paver block at RD 3/960 to 4/075) .

Name of Work :- Talai to Dhani Road km 0/0 to 7/0 (SH:- C/o Cement Concrete Paver block at RD 3/960 to 4/075).		Estimated cost:- ₹ 487208.00		Only	
		Earnest Money:- ₹ 9700.00		Only	
		Time allowed:- Two Month			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
			Figures	words	
1	Scarifying metalled (water-bound) road surface including disposal of rubbish, lead upto 50 m and consolidation of the aggregate received from scarifying with power road roller of 8 to 10 tonne capacity, including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. and other tax	368.00			Per Cubic Meter
2	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octri.	36.80			Per Cubic Meter
3	Providing and laying factory made chamfered edgeCement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by tablevibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engine including carriage of materials ,within all leads and lifts as per direction of Engineer-in-Charge.80 mm thick C.C. paver block of M-30 grade with approved color design and pattern. The rate including of Goods Service Tax, labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	368.00			Per cubic metre
4	Providing and laying in position cement concrete ofspecified grade excluding the cost of centering and shuttering - All work up to plinth leve within all leads & lifts carriage of material and other incidentials as per direction of Engineer-in-Chargeincluding carriage of materials. . 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax , labour cess, other levies / taxes, duties, royalties, sale tax, octri. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	11.69			Per cubic metre
Total:-					


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta