



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD. Nirmand  
Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), Email: [ee-nir-hp@nic.in](mailto:ee-nir-hp@nic.in)

Phone No.-01904-255140

Fax No. 01904-255740

Dated 29.04.2022

No.-PW/OSDN/ Tender-NIT/2021-22 11/29-35  
To


The Executive Engineer (IT Cell),  
Nigam Bihar, H.P. Shimla-2.

**Subject:- Publication of Tender Notice.**

*Jai Hind*


Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16<sup>th</sup> July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity

  
Executive Engineer,  
Outer Seraj Division,  
HP.PWD, Nirmand.

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

  
Executive Engineer,  
Outer Seraj Division,  
HP.PWD, Nirmand.



**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division,

HP.PWD. Nirmand

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), Email: [ee-nir-hp@nic.in](mailto:ee-nir-hp@nic.in)



Phone No.-01904-255140

Fax No. 01904-255740

**NOTICE INVITING TENDER**

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on 10.05.2022 up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on 09.05.2022 between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on 09.05.2022 between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money	Time	Cost of tender form Rs.
1	A/R & M/O link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435. (SH:- P/L paver Block in km. 1/240 to 1/300)	4,90,306/-	10,000/-	Three months	350/-
2	Periodic maintenance of Nore to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-III for surface correction at various RDs between 9/00 to 11/00)	4,97,305/-	10,000/-	One month	350/-
3	Periodic maintenance of Nore to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-III for surface correction at various RDs in km. 14/00 to 14/500)	3,79,961/-	8,000/-	One month	350/-



4	Periodic maintenance of Nore to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-III for surface correction at various RDs in km. 15/00 to 15/500)	3,79,961/-	8,000/-	One month	350/-
5	Periodic maintenance of Nore to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-III for surface correction at various RDs in km. 16/00 to 16/500)	3,79,961/-	8,000/-	One month	350/-
6	Periodic maintenance of Nore to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-III for surface correction at various RDs in km. 17/00 to 17/500)	3,79,961/-	8,000/-	One month	350/-
7	Construction of Link road From Kandagai to sour km 0/00 to 4/810.. (SH:- Construction of wire crate R/wall at RD 3/150 to 3/170 and B/wall at RD. 3/345 to 3/375)	2,84,278/-	5700/-	One month	350/-
8	C/O link road from Bakhnouw to Chitterkoot km. 0/00 to 2/300. (SH:-P/L Kharanja stone soling in km. 0/00 to 2/300)	2,92,599/-	6,000/-	One month	350/-
9	M/T works on Behna Dalash road km. 0/00 to 17/345. under self deposit (SH:- C/O wire crate B/ wall at RD. 8/870 to 8/884.40).	2,83,692/-	5,700/-	One month	350/-
10	A/R & M/O Bakhnouw to Dughashagan road km. 0/00 to 7/210. (SH:- C/O PCC R/Wall at RD 5/665 to 5/680)	3,35,897/-	7000/-	Two months	350/-

It is certified that the above tenders i.e Sr. No 1 to 10 are very urgent nature, So may be uploaded on department website in public interest

Executive Engineer  
Outer Seraj Division  
H.P PWD Nirmand  
on behalf of Governor of Himachal Pradesh

①

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O link road from Nirmand to Johad via Ambika Mata Temple at Nirmand km. 0/00 to 4/435. (SH:- P/L Paver Block at RD 1/240 to 1/300) under deposit of Telecom department)

Estimated Cost:- 490306.00


Earnest money:- 10000.00

Time:- Three months

Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	33.18	Per Cubic Meter			
2	Providing and laying 80mm (eighty millimetre) factory made chamfered edge Cement Concrete paver blocks of NTC or equivalent in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, complete all as per direction of Engineer-in-Charge and including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	221.25	Per Square Meter			
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. grade M 20 Nominal mix (1:2:4) (one cement : two sand: four graded stone aggregates twenty millimetre nominal size) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	2.25	Per Cubic Meter			
<b>Total:-</b>						

Executive Engineer,  
Outer Setai Division,  
HP PWD Nirmand.


Schedule of Quantity						
Name of work:- Periodic maintenance of Nore to Neether road km. 0/00 to 44 765 (Sub Head:- Providing and laying						
WBM G-III for surface correction at various RDs between 9/00 to 11/00)						
				Estimated cost:- Rs. 497305.00		
				Earnest Money:- Rs. 10000.00		
				Time:- One month		
Sr. No.	Description of work	Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	164.90	Per Cubic Metre			
Total in Figures						

  
 Executive Engineer,  
 Outer Seti Division,  
 HP.PWD, Shimla.




(3)

Schedule of Quantity						
Name of work:- Periodic maintenance of Nore to Neether road km. 0/00 to 14/765 (Sub Head:- Providing and laying WBM G-III for surface correction at various RDs between ) <i>114/00 to 14/500</i>						
				Estimated cost:- Rs. 379961.00		
				Latest Money :- Rs. 8000.00		
				Time:- One month		
Sr. No.	Description of work	Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	11.44	Per Cubic Metre			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer - in - Charge complete.	114.38	Per Cubic Metre			
<b>Total in Figures</b>						

  
 Executive Engineer,  
 Outer Serai Division,  
 HP.PWD. Shimla.

4

Schedule of Quantity						
Name of work:-Periodic maintenance of Nore to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-II for surface correction at various RDs between )						
115/100 to 15/500						
Sr. No.	Description of work	Qty.	Unit	Estimated cost:- Rs. 379961.00		
				Earnest Money:- Rs. 8000.00		
				Time:- One month		
				Figures	Rate Words	AMOUNT
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	11.44	Per Cubic Metre			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	114.38	Per Cubic Metre			
Total in Figures						

  
 Executive Engineer,  
 Outer Serai Division,  
 HP.P.W.D. Mirmand.

5

Schedule of Quantity

Name of work:- Periodic maintenance of Noire to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-IIH for surface correction at various RDs between ) 16/00 to 15/500

Estimated cost:- Rs. 379961.00  
 Earnest Money:- Rs. 8000.00  
 Time:- One month

Sr. No.	Description of work	Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	11.44	Per Cubic Metre			
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	114.38	Per Cubic Metre			
Total in Figures						

Executive Engineer.  
 Outer Setai Division,  
 HP.P.W.D. Nirmand.



6

Name of work:- Periodic maintenance of Nore to Neether road km. 0/00 to 44/765 (Sub Head:- Providing and laying WBM G-II for surface correction at various RDs between )		Schedule of Quantity		Estimated cost:- Rs. 379961.00	
Sr. No.		Description of work		Earnest Money:- Rs. 8000.00	
1		Qty.		Time:- One month	
2		Unit		Rate	
1		Figures		Words	
2		AMOUNT			
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 2 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	11.44	Per Cubic Metre		
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405 By Mechanical Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	114.38	Per Cubic Metre		
Total in Figures					

Executive Engineer,  
Outer Sanj Division,  
HP PWD, Nirmal.

Name of Work: Construction of link road from Kandagan to sour in km 0.00 to 4.810 (SH- Construction of wire crate works at various Rd's)

Schedule of Quantity

SL. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hill/ Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	77.60	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	24.80	Cubic Metre			
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS 280 and IS 4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer in - Charge complete. (Wire crate will be supplied by the department free of cost)	165.89	Cubic Metre			
Total in Figures						

Estimated cost - 284278.00  
Earnest Money 5700.00  
Time one month

2

Name of Work: Construction of link road from Bakhnow to Chitrakoot road km 0/00 to 2/300 (SI)- Providing and laying Kharanja stone soling in km 0/00 to 2/300

Schedule of Quantity

S. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Earning Money	Time	One month
				Figures	RATE	AMOUNT
					Words	
1	Preparation of sub grade by dressing to camber (earth work for cutting involved for the sub grade to be paid for separately depending upon the classification of soil) completed as per HPPWD specification.	1105.50	Square Metre			
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and retrolling the subgrade completed as per HPPWD specifications.	1105.50	Square Metre			
3	Stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per H.P.W.D. specification. 150mm spread thickness finished work including carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	165.83	Cubic Metre			
Total in Figures						

Executive Engineer  
Outer Setai Division  
HPPWD, Yamana



(9)

**Schedule of Quantity**

Name of Work: M/T works on Behma to Dalash road km 0/00 to 17/345 under self deposits (SH:- Construction of wire crate B/wall at RD 8/870 TO 8/884.40)

Schedule of Quantity						
Name of Work: M/T works on Behna to Dalash road km 0/00 to 17/345 under self deposits (SH:- Construction of wire crate B/wall at RD 8/870 TO 8/884.40)						
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	83.38	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	20.74	Cubic Metre			
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh ( woven diagonally ) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Wire crate will be supplied by the department free of cost)	165.89	Cubic Metre			
Total in Figures						

20  
Executive Engineer  
Outer Seral Division  
HPV  
Splimand

# **Schedule of Quantity**

Name of Work: A/R & M/O Bakhow to Dughasigan road km 0/00 to 7/210 (S/H:- Construction of PCC R/wall at RD 5/665 to 5/680)

Schedule of Quantity						
Name of Work: A/R & M/O Bakhow to Dughasigan road km 0/00 to 7/210 (SI)- Construction of PCC R/wall at RD 5/665 to 5/680						
						Estimated cost:-
						7000
						Two months
						Earnest Money
						Time
S. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	12.00	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	30.60	Cubic Metre			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.80	Cubic Metre			
4	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	62.80	Cubic Metre			
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	31.00	Each			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	9.00	Cubic Metre			
Total in Figures						

  
 Executive Engineer  
 Outer Setai Division  
 HPPWD, Himachal Pradesh