

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23- 853-55

Dated:- 29/4/22

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **06.05.2022 up to 12:00 Noon** and the same shall be opened on the same day **at 12:30 P.M.** in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on **05.05.2022 upto 01:00 P.M.**

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km 0/00 to 17/810. (SH:- Providing and laying soling, wearing, prime and tack coat in Km 0/0 to 1/680) (Deposit work).	4,31,655/-	8,600/-	350/-	One month
2	Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km 0/00 to 17/810. (SH:- Providing and laying soling, wearing, prime and tack coat in Km 1/680 to 3/340) (Deposit work).	4,26,528/-	8,500/-	350/-	One month
3	Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km 0/00 to 17/810. (SH:- Providing and laying soling, wearing, prime and tack coat in Km 3/340 to 5/000) (Deposit work).	4,26,528/-	8,500/-	350/-	One month
4	Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Kamand Neri road Km 0/00 to 6/000. (SH:- Providing and laying soling, wearing, prime and tack coat in Km 0/0 to 1/500) (Deposit work).	3,75,743/-	7,500/-	350/-	One month
5	Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Kamand Neri road Km 0/00 to 6/000. (SH:- Providing and laying soling, wearing, prime and tack coat in Km 1/500 to 3/000) (Deposit work).	3,75,743/-	7,500/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD, at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh

Schedule of Quantity

Estimated Cost:- Rs. 431655.00
 Earnest Money:- Rs. 8600.00
 Time:- One month

Name of work:- Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on NerDuhki Behindhar Gharan road Km. 0/0 to 17/810.

Sub Head:- Providing and laying soling, wearing, prime and tack coat in damaged portion at R.D. 0/0 to 1/680.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Removal of unsuitable soil including excavation, loading and disposal upto any lead but excluding compaction ground supporting embankment subgrade replacement by suitable soil, which shall be paid separately as per Clause 303.5.2 as per Technical Specification Clause 302.3.11 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	132.30 Cum.			Per cubic metre	
2	Consolidation of sub grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	756.00 Sqm.			Per Square metre	
3	Providing, laying, spreading and compacting stone aggregates by mechanical means of 90mm to 45mm (Ninety millimetre to forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-one hundred kilo newton) static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 (one) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	75.60 Cum.			Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	56.70 Cum.			Per cubic metre	
5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 to 1.00 kg/sqm (Zero point seven zero to one kilogramme per square metre) using mechanical means as per Technical specification Clause 502 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	756.00 Sqm.			Per Square metre	

①

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30kg/sqm (zero point two five to zero point three zero kilogramme per square metre) on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per technical specification clause 503 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	756.00 Sqm.	.		Per Square metre	
					Total:-	


Executive Engineer,
Mandi Division No.I
H.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 426528.00
 Earnest Money:- Rs. 8500.00
 Time:- One month

Name of work:- Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on New Duhki Behindhar Gharan road Km. 0/0 to 17/810.

Sub Head:- Providing and laying soling, wearing, prime and tack coat in damaged portion at R.D. 1/680 to 3/340.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Removal of unsuitable soil including excavation, loading and disposal upto any lead but excluding compaction ground supporting embankment subgrade replacement by suitable soil, which shall be paid separately as per Clause 303.5.2 as per Technical Specification Clause 302.3.11 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	130.73 Cum.			Per cubic metre	
2	Consolidation of sub grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	747.00 Sqm.			Per Square metre	
3	Providing, laying, spreading and compacting stone aggregates by mechanical means of 90mm to 45mm (Ninety millimetre to forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-one hundred kilo newton) static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 (one) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	74.70 Cum.			Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	56.03 Cum.			Per cubic metre	
5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 to 1.00 kg/sqm (Zero point seven zero to one kilogramme per square metre) using mechanical means as per Technical specification Clause 502 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	747.00 Sqm.			Per Square metre	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30kg/sqm (zero point two five to zero point three zero kilogramme per square metre) on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per technical specification clause 503 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	747.00 Sqm.	.		Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.I
 P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 426528.00
 Earnest Money:- Rs. 8500.00
 Time:- One month


Name of work:- Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km. 0/0 to 17/810.

Sub Head:- Providing and laying soling, wearing, prime and tack coat in damaged portion at R.D. 3/340 to 5/000.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Removal of unsuitable soil including excavation, loading and disposal upto any lead but excluding compaction ground supporting embankment subgrade replacement by suitable soil, which shall be paid separately as per Clause 303.5.2 as per Technical Specification Clause 302.3.11 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	130.73 Cum.			Per cubic metre	
2	Consolidation of sub grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	747.00 Sqm.			Per Square metre	
3	Providing, laying, spreading and compacting stone aggregates by mechanical means of 90mm to 45mm (Ninety millimetre to forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-one hundred kilo newton) static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 (one) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	74.70 Cum.			Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	56.03 Cum.			Per cubic metre	
5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 to 1.00 kg/sqm (Zero point seven zero to one kilogramme per square metre) using mechanical means as per Technical specification Cluase 502 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	747.00 Sqm.			Per Square metre	

3

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30kg/sqm (zero point two five to zero point three zero kilogramme per square metre) on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per technical specification clause 503 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	747.00 Sqm.			Per Square metre	
					Total:-	


Executive Engineer,
Mandi Division No.1
H.P. PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 375743.00
 Earnest Money:- Rs. 7500.00
 Time:- One month

Name of work:- Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Kamand Neri road Km. 0/0 to 6/0.
 Sub Head:- Providing and laying soling, wearing, prime and tack coat in damaged portion at R.D. 0/0 to 1/500.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Removal of unsuitable soil including excavation, loading and disposal upto any lead but excluding compaction ground supporting embankment subgrade replacement by suitable soil, which shall be paid separately as per Clause 303.5.2 as per Technical Specification Clause 302.3.11 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	118.13 Cum.			Per cubic metre	
2	Consolidation of sub grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	675.00 Sqm.			Per Square metre	
3	Providing, laying, spreading and compacting stone aggregates by mechanical means of 90mm to 45mm (Ninety millimetre to forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-one hundred kilo newton) static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 (one) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	67.50 Cum.			Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	50.63 Cum.			Per cubic metre	
5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 to 1.00 kg/sqm (Zero point seven zero to one kilogramme per square metre) using mechanical means as per Technical specification Clause 502 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	675.00 Sqm.			Per Square metre	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30kg/sqm (zero point two five to zero point three zero kilogramme per square metre) on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per technical specification clause 503 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	675.00 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.I
 H.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 375743.00
 Earnest Money:- Rs. 7500.00
 Time:- One month

Name of work:- Restoration of damages caused due to laying of OFC by Signal Regiment, Indian Army NFS Project, Northern Command Composite on Kamand Neri road Km. 0/0 to 6/0.
Sub Head:- Providing and laying soling, wearing, prime and tack coat in damaged portion at R.D. 1/500 to 3/000.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Removal of unsuitable soil including excavation, loading and disposal upto any lead but excluding compaction ground supporting embankment subgrade replacement by suitable soil, which shall be paid separately as per Clause 303.5.2 as per Technical Specification Clause 302.3.11 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	118.13 Cum.			Per cubic metre	
2	Consolidation of sub grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	675.00 Sqm.			Per Square metre	
3	Providing, laying, spreading and compacting stone aggregates by mechanical means of 90mm to 45mm (Ninety millimetre to forty five millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-one hundred kilo newton) static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 (one) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	67.50 Cum.			Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-one hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	50.63 Cum.			Per cubic metre	
5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70 to 1.00 kg/sqm (Zero point seven zero to one kilogramme per square metre) using mechanical means as per Technical specification Clause 502 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	675.00 Sqm.			Per Square metre	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
6	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30kg/sqm (zero point two five to zero point three zero kilogramme per square metre) on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per technical specification clause 503 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	675.00 Sqm.		.	Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.I
 H.P.PWD. at Padhar