

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.SD-III-CB-Tender/2021-22-
To

2136

Dated:- 29-4-22

The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2.

Subject: - Tender Notice

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on department website as per notification of Principal Secretary (PW) to the Govt. of HP vide letter No.PBW (B) A (3)1/2020 dated 16th July, 2021 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl: - as above.

Executive Engineer,
Shimla Division No-III,
HP.PWD, Shimla-3

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed item rate tenders on form No. 6&8 are hereby invited by the Executive Engineer, Shimla Division No. III, HP.PWD, Shimla-3 on behalf of the Governor of H.P. for the following works from the eligible Contractors/Firms enlisted in HP.PWD, so as to reach in his office on or before **06-05-2022** up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending Contractors/Firms or their authorized representatives. The tender form can be had from his office against cash payment (non-refundable) on any working day up to 4.00 P.M. on **05-05-2022** and the application for issue of tender form shall be received up to 4.00 P.M. on **04-05-2022**.

The earnest money in the shape of National saving Certificate/Time deposit account/saving account in any of the post office in HP, duly pledged in favour of Executive Engineer, Shimla Division No-III must accompany with the application form for the tender offer. Conditional tender and the tender received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tender without assigning any reason there to. Other conditions are applicable as perform No. 6&8. The offer shall remain open for 30 days.

Sr. No	Name of work	Estimated Cost	Earnest money	Time	Form No	Cost of form
1	Restoration of rain damages to various Road under Shimla Division No.III Shimla (SH:- Providing renewal coat of 30mm thick bituminous concrete on Navbahar to Holy Lodge Road Km. 0/00 to 0/320).	Rs.4,99,685/-	Rs.10000/-	15 th days	6&8	350/-
2	Restoration of rain damages to various road under Shimla division No.III Shimla (SH:-Providing renewal coat of 30mm thick Bituminous concrete on H.P. Sectt. To Majitha House road Km. 0/00 to 0/230).	Rs.3,81,873/-	Rs.7640/-	15 th days	6&8	350/-
3	Restoration of rain damages to various road under Shimla Division No.III Shimla (SH:- Providing renewal coat of 30mm thick bituminous concrete on cart road to Mahamaya Cottage Road Km.1/00 to 1/270).	Rs.4,98,873/-	Rs.9980/-	15 th days	6&8	350/-

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

Terms & Conditions:-

- 1 The contractor/firm shall have his GST No. and attested copy of the same be attached with the application for issue of tender form.
- 2 The contractor/firm should attach attested copy of registration/renewal.
- 3 Copy of PAN card be attached with the application form

NO.SD-III-CB-Tender/2021-22-

2137-2156

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla-2.
2. The Deputy Commissioner Distt. Shimla-1.
3. The Superintending Engineer 4th Circle in H.P, PWD Shimla with the request to issue necessary certificate regarding display of above tender notice in the notice board of circle office in view of the Principal Secretary (PW) to the H.P notification No.PBW (B) A (3)1/2020.Dated:-Shimla-2 the 07January, 2021 and even file No.PBW(B)A(3)1/2020 Dated 16 July,2021 Please.
4. The Executive Engineer, IT wing to the Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla- 2 along with schedule of Quantity through (e-mail) for taking necessary action in view of principal Secretary(PW) to the Government of Himachal Pradesh notification No.PBW (B)A(3)1/2020 dated 16th July,2021.
5. The Municipal Commissioner M.C. Shimla.
6. All the Assistant Engineers working under this Division.
7. The president contractor/association Shimla.
8. Notice board

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3
Dated:-

29-4-22

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 499685.00
 Earnest Money Rs. :- 10000.00
 Time:- 15 Days

Name of work: -Restoration of Rain Damages to Various Road under Shimla Division No.III Shimla(SH):-Providing renewal Coat of 30mm Thick Bituminous Concrete on Navbahar to Holy Lodge Road Km. 0/00 to 0/320)

Sl. No.	Items of work	Quantity	Rate		Unit.	Amount.
			In figures	In words		
1	Providing & applying tack coat with bitumen emulsion (RS-1) using distributor at the rate of 0.25 to 0.30 Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	1230.00	Sqm		Per square meter	
2	Providing & laying bituminous concrete 30mm (thirty millimetre) thick with 100-120 (one hundred one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hours using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 (five point four to five point six) per cent of mix and filler, transportation the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five hundred nine) complete in all respects including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The work should be executed as per job mix Formula approved by Department. The rates should be Quoted accordingly nothing extra should be applicable on this account.	36.90	Cum		Per cubic meter	
					Total	

Executive Engineer
 Shimla Division No.III
 H.P.W.D. Shimla

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 381873.00
 Earnest Money Rs. :- 7640.00
 Time:- 15 Days

Name of work: - Restoration of Rain Damages to Various Road under Shimla Division No.III Shimla(SH):-Providing renewal Coat of 30mm Thick Bituminous Concrete on HP. Sectt. To Majitha House Road Km. 0/00 to 0/230)					
Sl. No.	Items of work	Quantity	Rate		Unit.
			In figures	In words	
1	Providing & applying tack coat with bitumen emulsion (RS-1) using distributor at the rate of 0.25 to 0.30 Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom lifts as per direction of Engineer-in-Charge.	940.00 Sqm			Per square meter
2	Providing & laying bituminous concrete 30mm (thirty millimetre) thick with 100-120 (one hundred one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hours using crushed aggregates of specified grading, premixed with bituminous binder 5.4 to 5.6 (five point four to five point six) per cent of mix and filler, transportation the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five hundred nine) complete in all respects including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The work should be executed as per job mix Formula approved by Department. The rates should be Quoted accordingly nothing extra should be applicable on this account.	28.20 Cum			Per cubic meter
					Total

Executive Engineer
 Shimla Division No.III
 HP PWD, Shimla

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 498873.00

Earnest Money Rs. :- 9980.00

Time:- 15 Days

Name of work: -Restoration of Rain Damages to Various Road under Shimla Division No.III Shimla(SH:-Providing renewal Coat of 30mm Thick Bituminous Concrete on Cart Road to Mahamaya Cottage Road Km. 1/00 to 1/270)

Sl. No.	Items of work	Quantity	Rate		Unit.	Amount.
			In figures	In words		
1	Providing & applying tack coat with bitumen emulsion (RS-1) using distributor at the rate of 0.25 to 0.30 Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	1228.00	Sqm		Per square meter	
2	Providing & laying bituminous concrete 30mm (thirty millimetre) thick with 100-120 (one hundred one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hours using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 (five point four to five point six) per cent of mix and filler, transportation the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five hundred nine) complete in all respects including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The work should be executed as per job mix Formula approved by Department. The rates should be Quoted accordingly nothing extra should be applicable on this account.	36.84	Cum		Per cubic meter	
					Total	

Executive Engineer
Shimla Division No.III
HP (PWD. Shimla)