## HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer, Division HPPWD Solan. Email: **ee-sol-hp@nic.in** Land line NO:-Fax NO:-01792-223811

No.PW-SD/CB-Tender/-22-23-

2374-78

Dated:-

To

The Executive Engineer (IT Cell), Nigam Vihar, Nirman Bhawan, HPPWD, Shimla-2 Email ID:-cc-pwd-hp@nic.in

Subject: -

Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19<sup>th</sup> June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

Executive Engineer, Solan B & R Division, H.P.P.W.D, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

- 1. The Chief Engineer (S.Z), H.P.P.W.D., Nirman Bhawan, Nigam Vihar, Shimla.
- 2. The Superintending Engineer, 3<sup>rd Circle,</sup> HP.PWD, Solan.
- 3. The Drawing Branch & Accounts Branch of this office.
- Notice Board.

Executive Engineer, Solan B & R Division, H.P.P.W.D, Solan.

#### HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT NOTICE INVITING TENDER

(Exigency)

Sealed item rate tenders are hereby invited on Form No.6 &8 by the Executive Engineer, Solan B&R Division, H.P. PWD. Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule		
1	The last date for receipt of application for tender form.	25.05.2022	Upto 4.00 P.M.
2	The last date sale of tender forms.	26.05.2022	Upto 4.00 P.M.
3	The date for receipt of tender forms.	27.05.2022	Upto 10.30 A.M.
4	The date of opening of tender	27.05.2022	At 11.00 A.M.

The tender shall be received upto **10.30 A.M.** on **27.05.2022** and will be opened on the same day at **11.00 AM** in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr.	shall be kept open for 120 days. The Executive Engineer resolvent Name of work	Estimated Cost.	Earnest Money	Time	Cost of
No	Name of work	(Rs.)	(Rs)	Time	Form
1.	"Construction of Solan Rajgarh Bye Pass road	4,96,945/-	9,950/-	One	Rs.350/-
	Km.0/0 to 5/410 under MNP(SH:-Providing and			Months.	
	fixing sign boards".				
2.	"Construction of Solan Rajgarh Bye Pass road	4,99,463/-	10,000/-	One	Rs.350/-
	Km.0/0 to 5/410 under MNP(SH:-Providing and			Months.	
	fixing cat eyes & Delineators".				
3.	"Construction of link road to Seri Salana Km.0/0 to	4,99,62/-	10,000/-	One	Rs.350/-
	1/500 under MNP(SH:-Construction 5/7mtrs wide			Months.	
	road i/c essential CD & soling in Km.0/0 to				
	1/500(SW:-Removal of formation deficiency				
4	Km.0/685 to 0/825".	4.01.7664	0.6504	15.1	D 250/
4.	"Construction of Solan Rajgarh Bye pass road	4,81,566/-	9,650/-	15 days.	Rs.350/-
	Km.0/0 to 5/410 under MNP(SH:-Providing and				
	laying hot applied thermoplastic compound in				
5.	Km.2/0 to 4/0".	4,32,927/-	8,700/-	15 days.	Rs.350/-
٥.	"A/R & M/O Kandaghat to Mahi Karol road Km.0/0 to 4/450(SH:-Breakage of boulder & hard rock	4,32,9211-	8,700/-	15 days.	K8.550/-
	carriage of breakage material upto dumping site at				
	R.D.3/225 to 3/330".				
6.	"A/R & M/O Kandaghat to Mahi Karol road Km.0/0	4,32,927/-	8,700/-	15 days.	Rs.350/-
	to 4/450(SH:-Breakage of boulder & hard rock	,, · ·	-,,.	2 22.5	
	carriage of breakage material upto dumping site at				
	R.D.3/630 to 3/735".				

### **TERMS & CONDITIONS:-**

- 1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
- 2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms. Application without earnest money will not be
- 3. Application without earnest money will not be entertained.
- 4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons

SI.	Description of work	Qty.	Unit		RATE In	AMOUNT
No.	Description of work			Figures		Rs.
NO.	Job No.:- I (Rigery)				Estimated Cost: -	496945.00
	200 (10: - Totaland)				Earnest Money: -	9950.00
					Time limit : -	One Month
	Name of Work :-Construction of Solan Rajgarh Bye Pass road km 0/0	to 5/410 under	MNP (SI	H:- Providi	ng and fixing Sign	boards)
1	Providing and fixing retro - reflective hazard marker confirming to IRC 79:1981 of size 900x300 mm with back support of MS angle 25x25x3mm and leg ost of 80 mm dia having 1.6 mm thickness duly painted, 1500 mm high embedded into 0.3x0.3x0.45 m M20 grade concrete as per site requirement ussing non - metallic micro prismatic retro - reflective sheet confirming to IRC 67-2012 type IV specification fixed on 3 mm thick aluminum composite material sheet as base having 0.5 mm thick aluminum on both sides.	50.000 No	Each			
2	Providing and installing Mandatory/ Regulatory sign boards of 600 mm circular. Prohibited sign, No Parking and No stopping sign, speed limit, and vehicle control sign, restricton ends sign, and compulsoty diredtion control and other signs etc.	10.000 No	Each			
3		74.000 No	Each			

	Otv.	Unit	RATE In	AMOUNT
Description of work	80.		Figures Words	Rs.
Providing and installing of informatory sign board advance direction sign , reassurance sign of route condirmatory sign , place / city indentification, truck lay by, toil booth ahead etc.upto 0.9 sqm sizeshoulder mounted directional signages of various size using matlic micro prismatic retro reflectiove sheet conforming to IRC:67-2012 type IV, HIP specification fixed on 3 mm thick aluminum composite panel having 0.5 mm thick aluminum on both sides supported on single or two Nos. Mild steel pipe post 80 mm NB meduim 1.6mm thick duly painte in altenative color of black and white embedment in M20 grade concrete foundation of size 450x450x600mm complete as per drawings , technical specifications and as directed by Engineer in Charge.				
900x 600mm (nine hondred into six hundred milimeter )size	5.00 No	Each		
1200x600 mm (one thousan two hondred into six hundred milimeter bsize	4.00 No	Each		
	indentification, truck lay by, toil booth ahead etc.upto 0.9 sqm sizeshoulder mounted directional signages of various size using matlic micro prismatic retro reflectiove sheet conforming to IRC:67-2012 type IV. HIP specification fixed on 3 mm thick aluminum composite panel having 0.5 mm thick aluminum on both sides supported on single or two Nos. Mild steel pipe post 80 mm NB meduim 1.6mm thick duly painte in altenative color of black and white embedment in M20 grade concrete foundation of size 450x450x600mm complete as per drawings, technical specifications and as directed by Engineer in Charge.  900x 600mm (nine hondred into six hundred millimeter )size  1200x600 mm (one thousan two hondred into six hundred millimeter	Providing and installing of informatory sign board advance direction sign , reassurance sign of route condirmatory sign , place / city indentification, truck lay by, toil booth ahead etc.upto 0.9 sqm sizeshoulder mounted directional signages of various size using mattle micro prismatic retro reflectiove sheet conforming to IRC:67-2012 type IV , HIP specification fixed on 3 mm thick aluminum composite panel having 0.5 mm thick aluminum on both sides supported on single or two Nos. Mild steel pipe post 80 mm NB meduim 1.6mm thick duly painte in altenative color of black and white embedment in M20 grade concrete foundation of size 450x450x600mm complete as per drawings , technical specifications and as directed by Engineer in Charge.  900x 600mm (nine hondred into six hundred milimeter )size  5.00 No	Providing and installing of informatory sign board advance direction sign , reassurance sign of route condirmatory sign , place / city indentification, truck lay by, toil booth ahead etc.upto 0.9 sqm sizeshoulder mounted directional signages of various size using mattic micro prismatic retro reflectiove sheet conforming to IRC:67-2012 type IV , HIP specification fixed on 3 mm thick aluminum composite panel having 0.5 mm thick aluminum composite panel having 0.5 mm thick aluminum composite panel pairing in alternative color of black and white embedment in M20 grade concrete foundation of size 450x450x600mm complete as per drawings , technical specifications and as directed by Engineer in Charge.  900x 600mm (nine hondred into six hundred milimeter ) 5.00 No Each 1200x600 mm (one thousan two hondred into six hundred milimeter 4.00 No	Providing and installing of informatory sign board advance direction sign , reassurance sign of route condirmatory sign , place / city indentification, truck lay by, toil booth ahead etc.upto 0.9 sqm sizeshoulder mounted directional signages of various size using mattic micro prismatic retro reflectiove sheet conforming to IRC:67-2012 type IV, HIP specification fixed on 3 mm thick aluminum composite panel having 0.5 mm thi

Total :-Total in Words

T/S No. 46 for the 2021-22. Sr. No. 65 for the year 2021-22.

01	In the found	Qty.	Unit	RATE In		AMOUNT
	Description of work	20.	2.000	Figures Words		Rs.
No.	0.00			Estimate	ed Cost: -	499463.0
	Job No. : 2 (Ragery)			Earnest	Money: -	10000.0
				Time lin	nit:-	One Mont
	Name of Work :-Construction of Solan Rajgarh Bye Pass road km 0/0	to 5/410 under	MNP (SI	I:- Providing and f	ixing Cat E	yes and
	Delineators)	200.000 No.	Each			
1	Providing and fixing road side delineator of ht. 1200 mm made old M.S. tube sixe 100x80 mm having thickness 1.2mm of ht.900 mm and, balance 300 mm of MS angle 25x25x3mm. Having Micro primatic retor, reflective panel confirming to IRC 67-2012 type IV HIP and size 80 mm x 150mm on both sides as per clause No.800 of MORTH & H. Complete Deleneator processed by heat treatment process to makes it resistant to all weather effects fixed in CC. 1:2:4 block size of 300 x300x450 mm as clause No.800 of MORTH & H specification 5th, revision 2013.	200.000 No.	Lavi			
2	Providing and fixing cat eyes at edge line, center line marking / speed breaker / in front of madian in triangular shape etd. Pavement marker (cat Eyes) Milded shank raised pavement markers made of polycarbonate and ABS mioded body and reflative panels with micro prismatic lens capable of providing total internal reflection of the light entering he lens face and shall support a load of 16000 kg tested in accordance to ASTMC 4280 Type H and complying to specifications of Category A of MORTH Circular No W/NIJ/3023/10-97-DO III dt. 11.06.1997. The height , width and length shall not exceed 50 mm , 100 mm and with ninimum reflective area of 13 Sqm. on each side and the slope to the base shall be 35+/5degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19+/2mm and height not less than 19+/2mm ) from the body is to be a minimum value of 500 kg. Fixing will be by drilling holes on the road for the shanks to to inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer (of reputed make such as A very Dennison /3m	1175.000 m4	Per Cubic Meter			
	etc). Total:-					

Total in Words

T/S No. 45 for the 2021-22. Sr. No. 64 for the year 2021-22.

DRAFT SCHEDULE OF QUANTITY RATE In AMOUNT in Description of work Quantity Rs. Job No. 3 ( Raigery) 499562.00 Earnest Money: -10000.00 One month. Time: -Name of work: - - Construction of link road to Seri Salana km 0/0 to 1/500 under MNP (SH:- C/O 5/7 mtrs wi;de road i/c essential CD and Soling in km 0/0 to 1/500)(SW:- ROFD in between km 0/685 to 0/825) 0/0 to 1/500)(SW:- ROFD in between km 0/685 to 0/825)

Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site, according to the HP-PWD. specification and sorting out useful and urn-useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling line dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.

Total in Words

T/S No. 325 for the 2021-22. Sr. No. 417 for the year 2021-22.

B&R Division, HP.PWD. Solan.

SCHEDULE O					
	Oty.	Unit		RATE In	AMOUNT
L Description of work			Figures	Words	Rs.
0.				Estimated Cost: -	481566.00
Job No. : 4 ( Brigging)				Earnest Money: -	9650.00
0 4				Time limit : -	Fifteen days
Name of Work: Construction of Solan Rajgarh Bye Pass road km 0.  Thermo plastic compound in km 2/0 to 4/0)  Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five milimeters) thick and 0.10 (Zero point one zero ) meter wide strip in Edge line including reflectorising glass beads @ 250 gms ( two fifty grammes) per square meter area, thickness of 2.5 mm (two point five milimeters) is exclusive of surface applied glass beads as per IRC:35 (thirty five) in accordance with Ministory of Road Transport Specification (Latest revision) and IRC Code. The finished surface to be level, uniform and free from streaks and holes including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.  Total:	782.000 m2	Per Square Meter	- Providi	g and Laying not	approx

Total in Words

T/S No. 42 for the 2022-23. Sr. No. 67 for the year 2022-23.

		Qty.	Unit		KALEIII	Zalia Colina
SI.	Description of work	×		Figures	Words	Rs.
No.	= (0				Estimated Cost: -	432927.00
	Job No. :- 5 (Brigary)				Earnest Money: -	8700.00
	0 4				Time limit : -	Fifteen days.
1	Name of Work:-A/R & M/O Kandaghat to Mahi Karol road Km 0/0 breakage material upto dumping site at RD 3/225 to 3/330)  Excavation for roadway in hard rock (blasting prohibited) with rock breakers including breaking rock, leading in tippers and disposal with all! lift and lead, trimming bottom and side slopes in accordance with requirements of lines, grades and cross-sections as per Technical Specification Clause 302.3.5 as per direction of engineer in charge.	<b>1841.850</b> m3	Per Cubic Meter			
	Total :-					

Total in Words

T/S No. 49 for the 2022-23. Sr. No. 68 for the year 2022-23

Total :-Total in Words

T/S No. 50 for the 2022-23 Sr. No. 69 for the year 2022-23

# "Exigency Certificate"

It is certified that the tenders which were invited vide this Office Niq NO.PW.SD.CB.Tender/2022-23- 2374-78 dated: 18<sup>th</sup> May, 2022 are of emergent nature of work & in public interest.

Dated:18<sup>th</sup> May, 2022 Place:-Solan.

Executive Engineer, Solan B & R Division, H.P.P.W.D, Solan.