



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

Dated 20-05-22

No.-PW/OSDN/ Tender-NIT/2022-23 2787-93
To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.


Subject:-

Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division,
H.P.PWD. Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140
Fax No. 01904-255740


NOTICE INVITING TENDER

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on **07.06.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on **06.06.2022** between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **06.06.2022** between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money	Time	Cost of tender form Rs.
1	C/O of link road from Shani to Ghulat Km 0/00 to 5/210 under MNP (SH:- C/O B/wall on RD 3/540 to 3/570 for protection of house of Sh. Mohan Lal.	351833.00	7000.00	Three Month	350/-
2	A/r & M/O road from Jn. Of LDCK to Jn. Of NAS road km. 0/0 to 32/00 (SH:- improvement of curve in Km.22/096 to 22/104	196637.00	4000.00	One Month	350/-
3	R/R Damages on Chauradhar to Paneo road Km 0/00 to 8/015 (SH:- C/O B/Wall at RD 1/845 to 1/865).	264655.00	6000.00	Three Month	350/-
4	A/R & M/O Ranabag Karshigad road km. 0/00 to 14/510 (Sub Head:- Providing and laying WBM G-III at various RD's between 11/435 to 13/510 for surface correction)	439510.00	9000.00	One Month	350/-

5	Improvement of indentified black spots by providing corrective measures on Amarbag Tandi Road Km.0/000 to 6/00.(SH:- C/O Retaining walls at RD 5/830 to 5/845	203391.00	4000.00	One Month	350/-
6	Improvement of identified black spots by providing corrective measures on Nagan Chheora Chhatttri road km. 0/00 to 12/240. (SH:- Widening of narrow curve at RD 4/735 to 4/780)	438800.00	9000.00	One month	350/-
7	Improvement of identified black spots by providing corrective measures on Nagan Chheora Chhatttri road km. 0/00 to 12/240. (SH:- Widening of narrow curve at RD 5/660 to 5/700)	483661.00	10000.00	One month	350/-
8	Construction of link road from Shigar to Tarala km. 0/00 to 1/350 under SCSP (Sub Head:- Improvement of narrow curve at RD 1/320 to 1/350 and 1/365 to 1/395)	260787.00	6000.00	One month	350/-
9	Construction of road from Guhatan to Balerh km. 0/00 to 2/400 (SH:- Hiring of JCB for dressing of road surface and constructino of road side kutch drain in km. 0/00 to 1/200.) under BASP	97500.00	2000.00	One month	350/-
10	Construction of road from Guhatan to Balerh km. 0/00 to 2/400 (SH:- Hiring of JCB for dressing of road surface and constructino of road side kutch drain in km. 1/200 to 2/400.) under BASP	98750.00	2000.00	One month	350/-
11	A/R & M/O Kandugad Patarna road km. 0/00 to 11/195. (SH:- C/O retaining walls at RD 6/060 to 6/067 and 6/300 to 6/311.50)	385164.00	8000.00	Two months	350/-
12	Construction of road from Ranabag to Kandibag up to Balerh km. 0/00 to 12/800 (SH:- Hiring of JCB for dressing of road surface and constructino of road side kutch drain in km. 0/00 to 12/800.) under BASP	156250.00	4000.00	One month	350/-

It is certified that the above tenders i.e Sr. No 1 to 12 are very urgent nature, So may be uploaded on department website in public interest


 Executive Engineer
 Outer Seraj Division
 H.P PWD, Nirmand
 on behalf of Governor of Himachal Pradesh

Page No.

Schedule of quantity

Name of Work :- C/O Link Road from Chuhar km 0/00 to 5/210 under MNP (Sh:- C/O Breast wall on RD 3/540 to 3/570 for protection of house of Sh.Mohan Lal

Sl. No.	Description of work	Qty.	Unit	Figures	Estimated cost:-	
					Earnest Money	Three Month
					Time	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	60.90	Cum			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	44.1	Cum			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	14.10	Cum			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.30	Cum			
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	70.89	Cum			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	67.71	Cum			
Total in Figures						


Executive Engineer
Outer S&D Division
HPPWD, Mirmand

Schedule of quantity

Name of Work: A/R & M/O road from Jn. of LDCK to Jn. of NAS road km. 0/0 to 32/00 (SH:- Improvement of curve in km. 22/096 to 22/104)

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-	
				Earnest Money	One month
				Time	4000
			Figures	RATE	AMOUNT
				Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract of achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 154.72 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	464.15	Cubic Metre		
Total in Figures					

Signature of Tenderer with seal


 Executive Engineer
 Outer San. Division
 P.W.D. Nimband

Schedule of quantity

Name of work :- R/R Damages on chauradhar to Paneo road Km 0/00 to 8/015 (SH:- C/O B/wall at RD 1/845 to 1/865).

Estimated cost:-	264655.00
Earnest Money	5000.00
Time	Three Month

Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	9.60	Cum			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	11.12	Cum			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.20	Cum			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	36.88	Cum			
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	34.11	Cum			
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.60	Cum			
Total in Figures						

Executive Engineer
Outer Seral Division
HPWD, Yamund

(4)

Schedule of Quantity


Name of work:-A/R & M/O Ranabag Karshaigad road km. 0/00 to 14/510 . (Sub Head:- Providing and laying WBM G-III at various RDS between 11/435 to 13/510 for surface correction)

Estimated cost:- Rs. 439510.00

Earnest Money:- Rs. 9000.00

Time:- One month

Sr. No.	Description of work	Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Providing and laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 KN static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical Specification Clause 405, Grade-III A. By manual Means including carriage of materials, plants/equipments by all modes of transportation with in all leads and lifts and as per directions of The Engineer – in – Charge complete.	172.77	Per Cubic Metre			
Total in Figures						


Executive Engineer,
Outer Setai Division,
HP.PWD. Shimla.

(5)

Schedule of quantity

Name Work:- Improvement of identified black spots by providing corrective measures on Ambarbag Tandi road Km. 0/000 to 6/00.
(SH:- C/O Retaining walls at RD 5.8.30 to 5.8.45)

Name Work:- Improvement of identified black spots by providing corrective measures on Amarbag Tandri road Km. 0/000 to 6/00.							Estimated cost:-		203391.00
(SH:- C/O Retaining walls at RD 5.830 to 5.845							Earnest Money		4000.00
							Time		One months
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT			
				Figures	Words				
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	5.70	Cubic Metre						
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	35.70	Cubic Metre						
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.05	Cubic Metre						
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.64	Cubic Metre						
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	29.18	Cubic Metre						
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	6.00	Cubic Metre						
Total in Figures						0.00			

Executive Engineer
Outer Saijal Division
HPV/D, Nimarnad

2

Draft Schedule of quantity

Name of Work: Improvement of identified black spots by providing corrective measures on Nagan Chheora Chhattari road km. 0/00 to 12/240. (Sub -Head:- Improvement of curve at RD. 4/735 to 4/7800)						
Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Figures	RATE Time Words	AMOUNT One month
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract or achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone,whether useful or not, for 110.15 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prota basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1414.8	Cubic Metre			
Total in Figures						

(7)

Schedule of quantity

Name of Work: Improvement of identified black spots by providing corrective measures on Nagan Chheora Chhattari road km. 0/00 to 12/240. (Sub -Head:- Improvement of curve at RD. 5/660 to 5/700)					
				Estimated cost:-	
				Earnest Money	483661.00
				Time	10000
Sl. No.	Description of work	Qty.	Unit	RATE	AMOUNT
				Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract of achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone,whether useful or not, for 169.41 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on prorta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1198.1	Cubic Metre		
Total in Figures					

8

Schedule of quantity

Name of Work: Construction of link road from Shigar to Tarala km. 0/00 to 1/350 under SCSP (Sub Head:- Improvement of narrow curve at RD 1/320 to 1/350 and 1/365 to 1/395)						
				Estimated cost:-		260787.00
				Earnest Money	6000	
				Time	One month	
Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Excavation in earth work in hilly areas in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, widths, camber, super elevation and level as shown in the drawings or as directed by the Engineer-In-Charge, in conformity with the requirement of technical specifications for Rural Road, August 2004 and clause 16.2 of general conditions for contract or achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites and safe disposal dumping to be arranged by the contractor of un-suitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimentions including disposal of surplus materials with all leads and lifts at the locations specified in the tender documents or as directed by the Engineer-In-Charge for smooth riding. The recovery of the stone, whether useful or not, for 149.57 cum. In all cases, @ Rs. 170/-only per Cum. Shall be effected on porta basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	897.41	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Seral Division
 HPPWD, Miranpur

SCHEDULE OF QUANTITY

Name of work :- Construction of road from Guhatan to Balerh km. 0/00 to ..2/457..... (SH:- Hiring of JCB for dressing of road surface and constructino of road side kutch drain in km. 0/00 to ...1/2000...) under B&A

Estimated Cost Rs. 97500.00
Earnest Money Rs. 2000.00

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for dressing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	78.00			Per Hour	
					Total	

B
Executive Engineer
Outer Sesa Division
HPPWD, Himmatnagar

SCHEDULE OF QUANTITY

Name of work :- Construction of road from Guhatan to Balerh km. 0/00 to ..2/4.59... (SH:- Hiring of JCB for dressing of road surface and construction of road side kutch drain in km. 0/00 to ..1/2.00...) 41464 B.A.S

Estimated Cost Rs. 97500.00
Earnest Money Rs. 2000.00

Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for dressing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	78.00			Per Hour	
	Total					


(Signature)
Executive Engineer
Outer Sesa Division
HPPWD, Himmatnagar

SCHEDULE OF QUANTITY

Name of work :- Construction of road from Guhatan to Balerh km. 0/00 to 2.14 km. (SH:- Hiring of JCB for dressing of road surface and construction of road side kutch drain in km. 0/00 to 2.14 km.) under B&B

Estimated Cost Rs. 97500.00
Earnest Money Rs. 2000.00
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for dressing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissible taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	78.00			Per Hour	
	Total					


Executive Engineer,
Outer Sanei Division
HPPWD, Bhandar

⑪

Schedule of quantity

Name of work:- A.R. & M.C. Kandugad Patana road km. 0/00 to 11/195, (S.H):- C/O retaining walls at R/D 6/060 to 6/067 and 6/300 to 6/311.50)

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-	
				Earned Money	365164.00
				Time	2400.00
			Figures	RATE	AMOUNT
				Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	22.02	Cubic Metre		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	26.30	Cubic Metre		
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	9.07	Cubic Metre		
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications (clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	36.34	Cubic Metre		
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structures and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	57.40	Cubic Metre		
Total in Figures					

Executive Engineer
Outer Sarai Division
HPPWD, Noida


SCHEDULE OF QUANTITY

Name of work :- Construction of road from Ranabag to Kandibag up to Balerh km. 0/00 to 12/800
(SH:- Hiring of JCB for dressing of road surface and constructino of road side kutch drain in km. 0/00 to 12/800.) under BASP

Estimated Cost Rs. 156250.
 Earnest Money Rs. 4000.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB machine for dresssing of road surface, construction of road side kutch drain and removal of slips from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB and all admissile taxes also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	125.00			Per Hour	
	Total					

Time :- One mon


Executive Engineer
Outer Saraj Division
HPVMD Shimana