



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041
Fax No. 01972-288041

No:- PW-BSR-E-105/2022-23-
To

5622-30

Dated:- 28/5/22


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Barsar Division
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Barsar Division
HPPWD Barsar.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar
Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in


Phone No:- 01972-288041
Fax No. 01972-288041.

NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **10.06.2022 up to 10.30 A.M.** and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **08.06-2022 upto 4.00 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **09.06.2022** during office hours till **1.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	C/O Link Road from Village Mangnoti to Harizan Basti Sohari and Pandiri Km. 0/00 to 1/700. (SH:- C/O B/Wall at RD. 0/325 to 0/375 and P/L Solid Cause Way at RD. 0/435 to 0/487) (Under SCSP Head).	Rs. 4,70,313.00	Rs. 9,50000	Two Months
2	Restoration of Rain Damages on Various road Under Barsar Sub Division (Section Chakmoh). (SH:- Removal of Land Slide Slips, Maintenance of Berms and Maintenance of drain at Various RDs).	Rs. 2,81,595.00	Rs. 5,700.00	One Month
3	A.M.P. on Various Road Under Barsar Sub Division (Section Bijhari). (SH:- P/F Road Infrastructures of Various Road at Various RDs).	4,73,948.00	Rs. 9,500.00	One Month
4.	A/R & M/O Tikkar Kanoh Road and Badaran Galri Road Via Gahlilian Jole. (SH:- P/L Road Infrastructure Features at Various RDs).	Rs. 4,43,800.00	Rs. 8,900.00	One Month
5.	A.M.P. on Jaure Amb Karsai Road Km. 0/00 to 4/00. (SH:- P/L Road Infrastructure Features in Between Km. 0/00 to 4/00).	Rs. 4,43,800.00	Rs. 8,900.00	One Month
6	A/R & M/O Various Bridges Under Barsar Sub Division (Section Galri and Barsar-II) (SH:- Painting of Bridges).	Rs. 1,84,389.00	Rs. 3,700.00	One Month

HIM SUCHANA AYAM JAN SAMPARK.


Executive Engineer

Barsar Division

HPPWD Barsar.


On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BSR-E-105/2022-23-

5022-20 dated 28/5/2022


Executive Engineer
Barsar Division
HPPWD Barsar.

Schedule of quantity

Name of work:-C/O link road from village Mangnoti to Harizan Basti Sohari & Pandiri km 0/0 to 1/700
(SH:-C/O B/wall at RD 0/325 to 0/375 & P/Lsolid cause way at RD 0/435 to 0/487)
(Under SCSP Head)

Job No:-1

Estimated Cost Rs:-470313.00


Earnest Money Rs:-9500.00

Time Limit :- Two Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling wedging out of rock(where blasting in prohibited)and their intermediate classification of soil setting out true to the required line , grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D technical specification clause 302,1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and other necessary to complete the work by mechanical means and/ or labour if required . Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	112.50	cubic metre		Per Cubic Metre	
2	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	40.50	Cubic metre		Per Cubic Metre	

3	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	157.50	Cubic metre		Per Cubic Metre	
4	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	18.20	Cubic metre		Per Cubic Metre	
5	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can presibe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	13.65	Cubic metre		Per Cubic Metre	
6	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401. for grading –I material including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	18.20	Cubic metre		per cubic metre	

7	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	30.00	Numbers			Each	
						Total	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Job No:- 2

Name of work:- Restoration of rain damages on various roads under HPPWD Sub Division Barsar (Chakmoh Section)


Estimated Cost Rs:-281595.00

Earnest Money Rs:- 5700.00

(SH):- Removal of land slideslips, Maintenance of berms & drain at various RDs)

Time Limit :- One Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Maintenance of earthen shoulder (filling with fresh slected soil making up less of material / irregutations on shoulder in design level by adding fresh approved selected soil and compacting it with approprait equipment OMC upto a lead of 1000mtrs as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government .	3500.00	Square metre			Per square Metre	
2	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slops and disposal all marital upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	500.00	cubic metre			Per Cubic Metre	
3	Surface drain in soil construction of unlined surface drains of average cross section area 0.40sqm (zero point four zero sqare metre) in soil to specified lines, grades, levels and dimensions . Excavated material to be used in embankment with a lift upto 3m(three metre) and lead of 50 m(fifty metre) average lead 25m) as per technical specification Clause No 307 (mechanical means) including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	5800.00	Running metre			Per running Metre	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Name of Work:- AMP on various road under Barsar Sub Division (Section Bijhari)

(SH:- P/F road infrasturcture features of various road and various Rds)

Job No -3

Estimated Cost Rs:- 473948.00

Earnest Money Rs:-9500.00

Time Limit :- One month

Sr.No	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Providing and laying of hot applied Thermoplastic compound 2.5mm (two point five millimeter) thick including reflectorising glass beads @250gms(two point five zero gram) ¹ per sqm area, with road marking materials with 20%(twenty percent) glass beads having reflective index of 1.5(one point five millimeter) and 75%(seventy five percent) spherical and indigenous or foreign plant having sufficient strength to withstand heavy load without deformation and having softening point 25 to 30 degree(twenty five to thirty degree) more than the climate temperature of the area in a width of 0.10 (zero point ten metre) strips in specified colour . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	690.00 square metre			Per square metre	
2	Providing and fixing road studs dual directional retro reflective cat eyes studs made for high quality colour less retro reflective mini board embedded to 6mm high (six millimeter) impact plastic eyes of dia 16mm (sixteen millimeter) containing 7(seven) beads to each thus making a total of 42(forty two) beads housed on both side in a strong aluminum castes stud size 10x10cm(ten into ten centimeter) provided with a mild steel zinc plated nail of dia 12mm (twelve millimeter) for fixing of roads by hammering made green/ lite only as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	450.00 Numbers			Each	
				Total		


 Executive Engineer
 Barsar Division
 HPPWD-Barsar

Schedule of quantity

Name of Work:- A/R & M/O on Tikkar Kanoh road & Badaran Garli road Gallian via Jole
(SH:- P/L road infrasturcture features at various Rds)

Job No -4

Estimated Cost Rs:- 443800.00

Earnest Money Rs:-8900.00

Time Limit :- One month

Sr.No	Description of Item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Providing and laying of hot applied Thermoplastic compound 2.5mm (two point five millimeter) thick including reflectorising glass beads @250gms(two point five zero gram) per sqm area, with road marking materials with 20%(twenty percent) glass beads having reflective index of 1.5(one point five millimeter) and 75%(seventy five percent) spherical and indigenous or foreign plant having sufficient strength to withstand heavy load without deformation and having softening point 25 to 30 degree(twenty five to thirty degree) more than the climate temperature of the area in a width of 0.10 (zero point ten metre) strips in specified colour . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	800.00	square metre			Per square metre	
					Total		



Executive Engineer

Barsar Division

HPPWD Barsar



Schedule of quantity

Name of Work:- AMP on Jaure Amb Karsai road Km 0/00 tp 4/00

(SH:- P/L road infrastrucrture features in between Km 0/00 to 4/00)

Job No -5

Estimated Cost Rs:- 443800.00

Earnest Money Rs:-8900.00

Time Limit :- One month

Sr.No	Description of Item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Providing and laying of hot applied Thermoplastic compound 2.5mm (two point five millimeter) thick including reflectorising glass beads @250gms(two point five zero gram) per sqm area, with road marking materials with 20%(twenty percent) glass beads having reflective index of 1.5(one point five millimeter) and 75%(seventy five percent) spherical and indigenous or foreign plant having sufficient strength to withstand heavy load without deformation and having softening point 25 to 30 degree(twenty five to thirty degree) more than the climate temperature of the area in a width of 0.10 (zero point ten metre) strips in specified colour . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	800.00	square metre			Per square metre	
					Total		

Executive Engineer

Barsar Division

HPPWD Barsar

Schedule of quantity

Job No - 6

Name of work:-A/R & M/O various bridges under Barsar Sub Division Barsar HPPWD Barsar (Section Garli & Barsar-II)

Estimated cost Rs:- 184389.00

Earnest money Rs:- 3700 .00

Time Limit :- One Month

(SH:- Painting of various bridges etc.)

Sr.No	Discription of item	Quantity	Rate inclusive all taxes i/c G.S.T	Unit	Amount
		Figures	words		
1	Finishing wall with APEX exterior grade made of Nerolac , Berger, Asian paint of approved quality or its equalized on undecorated wall surface (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt dust and other foreign matter etc. including sand paper smooth complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax , GST or other taxes imposed by the Government	1808.86	square metre	per square metre	
2	Applying one coat of Acrylic primer (Spectrum) or equivalent of superior quality on new plastered surface and including preparing the surface by thoroughly brushing the surface free from motar dropping and other foreign mater and sand papering the surface smooth complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	1808.86	square metre	per square metre	
3	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar dropping dust loose material and other foreign matter sand papered smooth to give final finish t the surface complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	1266.20	square metre	per square metre	
4	Removing old paint from steel and other metal surface and making the surface even with frame cleaning . including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	70.57	square metre	per square metre	
5	Painting two coats (excluding priming coat)on previously painted steel and other metal surfaces with readymixed bituminous paint anticorrosive paint,brushing,black to give an even shade including cleaning of all dirt,dust and other foreign matter.including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	70.57	Square metre	Per square Metre	
				Total:-	

Executive Engineer
Barsar Division
HPPWD Barsar