

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO.SD-III-CB-Tender/2022-23-
To

4781

Dated:- 18-5-22

*The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2.*

Subject:- Tender Notice

Enclosed kindly find herewith the tender notice for the work as given in the notice inviting tender for uploading on department website as per notification of Principal Secretary (PW) to the Govt. of HP vide letter No.PBW (B)A(3)1/2020 dated 16th July,2021 as the works mentioned in the notice inviting tender are urgent/emergent nature of works in public interest.

Encl:- as above

*Executive Engineer,
Shimla Division No-III,
HP.PWD Shimla-32*

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Sealed item rate tenders on form No. 6&8 are hereby invited by the Executive Engineer, Shimla Division No. III, HP.PWD. Shimla-3 on behalf of the Governor of H.P. for the following works from the eligible Contractors/Firms enlisted in HP.PWD, so as to reach in his office on or before **24-05-2022** up to 10.30 A.M. and will be opened on the same day at 11.00 A.M. in the presence of the intending Contractors/Firms or their authorized representatives. The tender form can be had from against cash payment (non-refundable) on any working day up to 5.00 P.M. on **23-05-2022** and the application for issue of tender form shall be received on the same day i.e. **23-05-2022** up to 12.00 P.M.

The earnest money in the shape of National saving Certificate/Time deposit account/saving account in any of the post office in HP, duly pledged in favour of Executive Engineer, Shimla Division No-III must accompany with the application form for the tender offer. Conditional tender and the tender received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tender without assigning any reason there to. Other conditions are applicable as perform No. 6&8. The offer shall remain open for 30 days.

Sr. No	Name of work	Estimated Cost	Earnest money	Time	Cost form	of Form No
1	Special repair to residential building under Shimla Division No.III (SH:- Providing water tank and plateform for Set No. 1,4 and 5 at Harvington Estate Lakkar Bazar Shimla).	Rs.3,60,927/-	Rs.7220/-	One Month	350/-	6&8
2	S/R to residential buildings under division No.III Shimla (SH:- Providing and fixing PVC water tank and tank stand for new type-V at Richmond Shimla).	Rs.3,31,924/-	Rs.6640/-	One Month	350/-	6&8
3	Special repair to Type-II of Block-IV Y Lodge at Lakkar Bazar Shimla and Type-II of Kitchen Block at Correstophen Estate at IGMC Shimla (SH:- Half Brick Masonary, M.S. Grils, Partition & distempering, water supplying and sanitary fittings in set No. 48 of Kitchen Block & Set No. 3 & 4 of IVY Lodge).	Rs.3,18,008/-	Rs.6370/-	One Month	350/-	6&8
4	A/R & M/O to Approach road to High Court Building Shimla. (SH:- Providing and laying metaling & taring to approach road to High Court building at RD 0/00 to RD 0/119.00)	Rs.3,63,516/-	Rs.7270/-	One Month	350/-	6&8
5	Special repair to Doctors residence type-IV of Block B at Correstophen Estate Lakkar Bazar Shimla (SH: - Providing wood work, Eaves board, Gutter, painting and distempering etc.).	Rs.2,06,640/-	Rs.4140/-	One Month	350/-	6&8
6	A/R & M/O to Approach road to High Court Building Shimla.(SH.-Providing and laying metaling taring of approach road RD 0/00 to RD 0/104.60)	Rs.1,94,885/-	Rs.3900/-	One Month	350/-	6&8

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

Terms & Conditions:-

- 1 The contractor/firm shall have his GST No. and attested copy of the same be attached with the application for issue of tender form.
- 2 The contractor/firm should attach attested copy of registration/renewal.
- 3 Copy of PAN card be attached with the application form

NO.SD-III-CB-Tender/2022-23-

Copy forwarded for the following for information and necessary action to-

1. The Engineer-in -Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla-2.
2. The Deputy Commissioner Distt. Shimla-1.
3. The Superintending Engineer 4th Circle in H.P, PWD Shimla with the request to issue necessary certificate regarding display of above tender notice in the notice board of circle office in view of the Principal Secretary (PW) to the H.P notification No.PBW (B) A (3)1 2020.Dated:-Shimla-2 the 07January, 2021 and even file No.PBW (B)A(3)1/2020 Dated 16 July,2021 Please.
4. The Executive Engineer, IT wing to the Engineer-in -Chief, HPPWD Nirman Bhawan, Nigam Vihar Shimla- 2 along with schedule of Quantity through (e-mail) for taking necessary action in view of principal Secretary(PW) to the Government of Himachal Pradesh notification No.PBW (B)A(3)1/2020 dated 16th July,2021.
5. The Municipal Commissioner M.C. Shimla.
6. All the Assistant Engineers working under this Division.
7. The president contractor/association Shimla.
8. Notice board

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3

Dated:-

18-5-22

Executive Engineer,
Shimla Division No-III,
HP.PWD.Shimla-3

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 0-00 360 927/-
Earnest Money Rs. :- 0-00 72 20 00

Time:- One Month.

Name of work: - Special Repair to Residential Building Under Shimla Division No.III(SH:- Providing Water Tank and Plateform for Set No. 1, 4 and 5 at Harvington Estate Lakkar Bazar Shimla)

Sl. No.	Items of work	Quantity	Rate		Unit.	Amount.
			In figures	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	5.06 cum.			Per Cubic Metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. (i) 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size)	5.06 cum.			Per Cubic Metre	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. (i) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	3107.26 Kg			Per Kilogram me	
	Conditions:-					
	Total					

- i Rates should be quoted for all heights including all leads and lifts for internal and external works.
- ii Useful materials will be handed over to the Assistant Engineer, Medical College Sub Division HPPWD, Shimla-1 otherwise credit for useful materials will be charged.
- iii Sample of all Materials to be used on work. Shall be got approved from the Engineer-in-charge in advance before actual use on work, and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer
Shimla Division No.III
HP PWD, Shimla-8.

2

SCHEDULE OF QUANTITY

Estimated cost:- 331924.00
Earnest Money:- 6640.00
Time :- One Month.

Name of work: - S/R to Various residential buildings under division no III Shimla. (SH:- Providing and fixing PVC water tank and tank stand for new type V at Richmond Shimla.)

SR. NO.	Sub-Head/Item of work.	Qty.	Rate		Unit.	Amount.
			In Figures.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	3.24	Cum		6	
2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level: 1:1.5:3 (1 cement : 1.5 coarse sand); 3 graded stone aggregate 20 mm nominal size)	3.24	Cum		Per cubic metre	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in girders, frames, guard bar, ladder, railings, brackets, gates and similar works.	1169.24	Sqm		Per square metre	
4	Providing and fixing welded mesh 25mm x 25mm X 3mm thick as per approved design by welding with electrical plant complete including applying priming coat of red lead paint as per HP.PWD. Specification 1990 Volume-I including carriage of materials upto all leads and lifts.	63.80	Sqm		Per square metre	
5	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	16000.00	Ltr		Per litre	
					Total	
	CONDITION					

- 1 Rates should be quoted for all heights including all leads and lifts for internal and external works.
- 2 Sample of all the material to be used on work shall be got approved from the Engineer-in-charge in advance before actual use on work, and any or all of the material which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer
Shimla Division NO.III.
HP&PWD, Shimla-171003

3

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 318008.00
Earnest Money Rs. :- 6370.00

Time:- One Month.

Name of work : - Special Repair to Type-II of Block-IVY lodge at Lakkar Bazar Shimla and Type-II of Kitchen Block at Correstophen Estate at IGM.C. Shimla(SH:- Half Brick Masonary , MS. Grils , Partition & distempering, Water Supplying and Sanitary Fittings in Set No. 48 of Kitchen Block & Set No. 3&4 of IVY Lodge .)

Sl. No.	Items of work	Quantity	Rate		Unit.	Amount.
			In figures	In words		
1	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level:- Cement mortar 1:4 (1 cement :4 coarse sand) complete including carriage of materials within all leads and lifts as per direction of Engineer - in - charge.	24.34 Sqm			Per Square metre	
2	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. Including priming coat with approved steel primer all complete. (i) Fixed to openings Wooden frames with rawl plugs screws etc.	437.80 KG.			Per Kilogram me	
3	Providing and fixing insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately) .(i) Natural colour insulating board (a) 12 mm thick	25.22 Sqm			Per Square metre	
4	Providing and fixing 50x12mm hard wood moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete .(i) Kiln seasoned and chemically treated hollock wood (a) 50x12mm Thick	77.70 Rmt.			Per Running metre	
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete.	35.24 Sqm			Per Square metre	
6	Dismantling of Drajji Walling including Stacking of serviceable Materials and Disposal of Unserviceable materials with in all leads and lifts	24.34 Sqm			Per Square metre	
7	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, in skirting, riser of steps, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete. Including carriage of material within all leads and lifts as per direction of Engineer-in-charge.	12.51 Sqm			Per Square metre	
8	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) and a top layer 6 mm thick cement plaster 1:3 (1 cement : 3 coarse sand) finished rough with sponge.	139.69 Sqm			Per Square metre	

	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :One or more coats on old work	139.69	Sqm			Per Square Metre	
10	Distemping with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade :(i) Old work (one or more coats)	651.46	Sqm			Per Square Metre	
11	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	260.58	Sqm.			Per Square Metre	
12	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials and as per the direction of the Engineer-In-Charge.	400.27	Sqm			Per Square Metre	
13	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work on wood surface complete including carriage of materials within all leads and lifts.	477.86	Sqm			Per Square Metre	
14	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content (i)With ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 50 grams/ litre	25.22	Sqm.			Per Square Metre	
15	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade complete including carriage of materials within all leads and lifts.:- Two or more coats on new wood work.	25.22	Sqm.			Per Square Metre	
16	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat of approved brand and manufacture within all leads and lifts of materials and other incidentals.	26.35	Sqm.			Per Square Metre	
17	Dismantling old plaster or skirting taking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	95.67	Sqm			Per Square Metre	
18	Disposal of surplus excavated earth by Mechanical with in all leads on approved dumping site of M.C. Shnila or otherwise including payment of prescribed charges of dumping to the owner of dumping site through all mode of transportation including head load animal load or mechanical means alongwith its leveling and to complete the work of mechanized means and labour (if any required).The dumping site to be arranged by the contractor entirely at his own risk and cost. All useful materials such as stones, aggregate and slates shall be sorted out and stacked along roads side any loss of the public/private property during the course of disposal shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respect as per direction of Engineer-in-Charge.	5.43	Cum			Per Cubic Metre	
19	Renewing glass panes, with wooden fillets wherever necessary;including carriage of materials within all leads and lifts (i)Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	2.45	Sqm			Per Square Metre	

20	Providing and fixing wash basin with single hole C.I. brackets, 15 mm C.P. brass pillar tap, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:(i) White Vitreous China Wash basin size 630x450 mm including carriage of materials within all leads and lifts.	2.00	No.			Each	
21	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work:-15mm dia nominal bore complete in all respects as directed by the Engineer-in-charge including carriage of materials in all leads and lifts.	34.70	Rmt.			Per Running metre	
22	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials upto all leads and lifts and as directed by the Engineer in Charge.	1000.00	Ltrs.			Per Litre	
Conditions:-							
i Rates should be quoted for all heights including all leads and lifts for internal and external works.						Total	

- ii Useful materials will be handed over to the Assistant Engineer, Medical College Sub Division HPPWD, Shimla-1 otherwise credit for useful materials will be charged.
- iii Sample of all Materials to be used on work Shall be got approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer
Shimla Division No.III
HP PWD, Shimla-8

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 363516.00
Earnest Money/ Rs. :- 7270.00

Time:- One Month.

Name of work:- A/R and M/O to Approach road to High Court Building Shimla. (SH:- Providing and Laying metaling & taring to approach road to high court building at RD 0/00 to RD 0/119.00)

Sl. No.	Items of work	Quantity	Rate		Unit	Amount
			In figures	In words		
1	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kilogram per square metre on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per technical specification Clause 503 (Five hundred three) including carriage of material with in all leads, lifts and as per the direction of Engineer-in- Charge.	853.63			Per square metre	
2	Providing and laying 30mm (twenty five millimetre) thick bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour crushed aggregates of specified grading, premixed with bituminous binder @ 5.40 to 5.60 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.508 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	25.61			Per cubic metre	
		Cum				
					Total	

- i Rates should be quoted for all heights including all leads and lifts for internal and external works.
- ii Useful materials will be handed over to the Assistant Engineer, Vidhan Sabha Sub Division HPPWD, Shimla-4 otherwise credit for useful materials will be charged.
- iii Sample of all the materials to be used on work shall be got approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of indian standards.


Executive Engineer,
Shimla Division No. III,
HP. PWD. Shimla-3.

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 206640.00
Earnest Money Rs. :- 4140.00

Time:- One Month.

Name of work: -Special Repair to Doctors Residence type-IV of Block B at Correstophen Estate lakker Bazar Shimla. (SH: - Providing wood work, Eaves board, Gutter, painting and Distempering etc.)

Sl. No.	Items of work	Quantity	Rate		Unit.	Amount.
			In figures	In words		
1	Dismantling roofing including ridges, hips, valleys, gutters etc. stacking the serviceable materials and disposal of un-serviceable materials within all leads and lifts:- G.I. Sheet roofing.	29.93 Sqm.			Per square metre	
2	Providing wood work in trusses, purlins, rafters, posts, post plates, wall plates and the like within all leads and lifts in 2nd class deodar wood.	0.211 Cum			Per Cubic metre	
3	Providing eaves board 200mm X 25mm thick including fixing in position including carriage of materials within all leads and lifts in 2nd class deodar wood.	15.50 Rmt.			Per running metre.	
4	Providing weather board 100mm X 25mm thick including fixing in position including carriage of materials within all leads and lifts in 2nd class deodar wood.	15.50 Rmt.			Per running metre.	
5	Providing and fixing 25mm thick wooden plank ceiling/ flooring with tongued and grooved pointing and wood screws (frame work and cover fillets to be measured and paid for separately) in 1st class deodar wood complete including carriage of materials within all leads and lifts.	9.30 Sqm			Per square metre	
6	Providing and fixing 50mm X12mm section plain square edged cover fillets (beading) with wood screws in ceiling and lining including mitring at junctions in deodar wood including carriage of materials within all leads and lifts as per direction of Engineer-in-charge.	55.80 Rmt.			Per Running metre	
7	Providing and fixing 15cm wide 45cm overall semicircular plain G. I. sheet gutter with iron brackets 40mm X 3mm size bolts and nuts and washers etc. including making necessary connections with rain water pipe complete as per design including carriage of materials within all leads and lifts :- 0.63mm thick sheet.	69.50 Rmt.			Per Running metre	
8	Providing and fixing 110mm dia pipes on wall face PVC Finolex type "A" rain water pipes including filling the joints with approved adhesive and including require No. of collar and clamps etc complete including carriage of materials within all leads and lifts.	12.00 Rmt.			Per running metre	
9	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of material in all leads and lifts.	127.98 Sqm.			Per square metre.	

10	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and knotting including carriage of materials within all leads and lifts in Ready/mixed paint brushing with white lead for priming.	12.40	Sqm			Per square metre	
11	Painting two coat (excluding priming coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt, dust and other foreign matter, sand papering and stopping including carriage of materials within all leads and lifts in With white enamel paint.	12.40	Sqm.			Per square metre	
12	Painting one coat(excluding priming coat) on previously painted wood and wood based surfaces with enamel paint to given and even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping including carriage of materials in all leads and lifts:-With Enamel paint other than white.	55.36	Sqm.			Per square metre.	
13	Applying one or more coat of paint based putty made of whitening and POP etc. mixed in required quantity of white enamel paint for application on wood based products after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials within all leads and lifts.	12.40	Sqm.			Per square metre.	
14	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surfaces (one coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc. including sand paper smooth complete in all leads and lifts including carriage of materials and as per the direction of the Engineer-in-Charge.	319.96	Sqm			Per square metre	
15	Painting one or more coats on G.I Sheets with ready/mix paint of approved brand and manufacture on old work to give an even shade including carriage of materials within all leads and lifts :- White /grey/green shade.	313.34	Sqm.			Per square metre	
16	Providing scaffolding for all kind of works in multistorey buildings up to all height with Bamboo complete tied with rope on joints and pedestal of CGI Sheet etc. in all respect (Face area of scaffolding up to top pedestal height shall be measured and paid for) including carriage of materials within all leads and lifts as per direction of the Engineer - in - charge.	77.64	Sqm			Per square metre	
	Conditions:-					Total	

i Rates should be quoted for all heights including all leads and lifts for internal and external works.

- ii Useful materials will be handed over to the Assistant Engineer, Medical College Sub Division HPPWD, Shimla-1 otherwise credit for useful materials will be charged.
- iii Sample of all Materials to be used on work Shall be got approved from the Engineer-in-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer
Shimla Division No. III
HPPWD, Shimla-1

SCHEDULE OF QUANTITY

Estimated Cost Rs. :- 194885.00
Earnest Money Rs. :- 3900.00

Time:- One Month.

Name of work:- A/R and M/O to Approach road to High Court Building Shimla. (SH- Providing and Laying metaling taring of approach road RD 0/00 to RD 0/104.60)

Sl. No.	Items of work	Quantity	Rate		Unit	Amount
			In figures	In words		
1	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kilogram per square metre on the prepared granular surfaces Treated with primer and cleaned with hydraulic broom as per technical specification Clause 503 (Five hundred three) including carriage of material with in all leads, lifts and as per the direction of Engineer-In- Charge.	457.53	Sqm		Per square metre	
2	Providing and laying 30mm (twenty five millimetre) thick bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour crushed aggregates of specified grading, premixed with bituminous binder @ 5.40 to 5.60 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.508 including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge.	13.73	Cum		Per cubic metre	

i Rates should be quoted for all heights including all leads and lifts for internal and external works.

ii Useful materials will be handed over to the Assistant Engineer, Vidhan Sabha Sub Division HP PWD, Shimla-4 otherwise credit for useful materials will be charged.

iii Sample of all the materials to be used on work shall be got approved from the Engineer-In-charge in advance before actual use on work and any or all of the materials which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer,
Shimla Division No. III,
HP. PWD. Shimla-3.