



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW-BSR-E-105/2022-23-

To

-3038-47

Dated:- 10/05

2022


The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,


Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

**DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.**


Executive Engineer
Barsar Division
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.


Executive Engineer
Barsar Division
HPPWD Barsar.



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041.


NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **23-05-2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **20-05-2022** upto 4.00 P.M. The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on or before **21.05.2022** during office hours till 1.00 P.M. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	A.M.P on Old Una Aghar Mandi Road Km. 0/0 to 2/0. (SH:- P/F Road Studs in Between Km. 0/0 to 2/0).	Rs. 3,52,421.00	Rs. 7,100.00	One Month
2	A/R & M/O on Various Road Under HPPWD Sub Division Barsar. (SH:- Removal of Slips, Maintenance of Drain & Maintenance of Berms at Various RDs).	Rs. 1,97,679.00	Rs. 4,000.00	One Month.
3	A/R & M/O P.W.D. Rest House at Bhota. (SH:- Removal of Sludge of Septic Tank).	Rs. 56,753.00	Rs. 1,200.00	One Month
4.	C/O Link Road Pansai Beha to Hathol Road Km. 0/0 to 4/0. (SH:- C/O Solid Cause Way alongwith Hume Pipe Both Side at RD. 3/200) (Under O.T.M.N.P. Head).	Rs. 4,88,302.00	Rs. 9,800.00	Two Months
5.	C/O Link Road Kothera Chowk to Ropa Km. 0/0 to 1/165. (SH- C/O Solid Cause Way alongwith Hume Pipe Both Side at RD. 0/600) (Under O.T.M.N.P. Head).	Rs. 4,87,354.00	Rs. 9,800.00	Two Months
6.	A/R & M/O Bridge Over Man Khad on Manpul Gauna Karour Basaral Jasoh Road at RD. 5/190. (SH:- P/L 25mm Thick Mastic Asphalt Wearing Course).	Rs. 4,60,219.00	Rs. 9,300.00	One Month
7.	A/R & M/O Various Road Under Barsar HPPWD Sub Division. (SH:- Supply and Stacking Grit and Sand for Patch Work). <i>(Selection Chakraborty)</i>	Rs. 2,49,461.00	Rs. 5,000.00	One Month

8.	A/R & M/O Various Road Under HPPWD Sub Division Barsar. (SH:- Supply and Stacking Fuel Wood for Patch Work).	Rs. 1,71,000.00	Rs. 3,500.00	One Month
9.	SDF/2021/21. Repair of Link Road Chakdad to Sasan Bali (G.P. Makkar) SDF/2021/22 Repair of Link Road Charcheri (G.P. Dandroo) SDF/2021/23 Repair of Link Road Ghunani (G.P. Tipper) SDF/2021/24 Repair of Link Road Bumbloo to Kaloun (G.P. Kaloun) SDF/2021/25 Repair of Link Road Balh to Bumbloo (G.P. Bal Bihal). (SH:- Removal of Slips and Maintenance of Drain and Maintenance of Earthen Shoulder at Various RDs) (Deposit Work).	Rs. 1,79,165.00	Rs. 3,600.00	One Month
10.	Preparation of DPRs i/c Plan L-Section, X- Section and Survey of Work for the Up-Gradation/ Improvement of Jalari Salauni Bijhari Deotsidh Road Km. 27/0 to 52/500).	Rs. 4,59,000.00	Rs. 9,200.00	Two Months

HIM SUCHANA AVAM JAN SAMPARK.



Executive Engineer
Barsar Division
HPPWD Barsar.

On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BSR-E-105/2022-23- **3038-47** dated **10-05-2022.**



Executive Engineer
Barsar Division
HPPWD Barsar.

Schedule of quantity

Name of Work:- AMP on Old UAM road Km 0/00 to 2/00
(SH:- P/F road stud in between Km 0/00 to 2/00)

Job No :- 1
Estimated Cost Rs:- 352421.00
Earnest Money Rs:-7100.00
Time Limit :- One month

Sr. No	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Providing and fixing road studs dual directional retro reflective cat eyes studs made for high quality colour less retro reflective mini board embedded to 6mm high (six millimeter) impact plastic eyes of dia 16mm (sixteen millimeter) containing 7(seven) beads to each thus making a total of 42(forty two) beads housed on both side in a strong aluminum castes stud size 10x10cm(ten into ten centimeter) provided with a mild steel zinc plated nail of dia 12mm (twelve millimeter) for fixing of roads by hammering made green/ lite only as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, or other taxes imposed by the Government .	850.00	square metre		Per square metre	
2	Providing and Solar road stud 3.00 metre (three metre) 100x100 mm (one hundred into one hundred millimetre) dia light distance upto 1000 metre (one thousand metre) solar power yellow sides market light with for speed bumps side walk etc., installed in concrete or asphaltic surface by drilling holes 30mm (thirty millimetre) upto a depth of 600mm (six hundred millimetre) and bedded in a suitable bituminous gout or epoxy mortoe all as per BS: 873 (part 4) 1973 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	64.00	cubic metre		Per cubic metre	
					Total	


Executive Engineer
Barsar Division
HPPWD Barsar

Job No:- 2

Estimated Cost Rs:-197679.00

Earnest Money Rs:- 4000.00


Time Limit :- One Month

Schedule of quantity

Name of work:-A/R & M/O on various roads under HPPWD Sub Division Barsar (Section Barsar-1)

(SH):- Removal of slips , Maintenance of earthen shoulder & maintenance of drain at various RDs)

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Maintenance of earthen shoulder (filling with fresh selected soil making up less of material / irregularities on shoulder in design level by adding fresh approved selected soil and compacting it with appropriate equipment OMC upto a lead of 1000mtrs as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government .	7800.00 Square metre			Per square Metre	
2	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slops and disposal all material upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	220.00 cubic metre			Per Cubic Metre	
3	Maintenance of Drain :- Maintenance of drain including erosion, repair clearing , cleaning reshaping regarding deeding of side drain as well as catch water drain as per technical specification clause No 1907 including carriage of material and equipments in all leads and lifts with all mode of transport and as per the direction of Engineer-in- Charge. including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	3500.00 Running metre			Per running Metre	



Executive Engineer

Barsar Division

HPPWD Barsar

Schedule of quantity

Name of work:- A/R &M/O P.W.D Rest House Bhotia
(SH:- Removal of sludge of septic tank)

Job No -3
Estimated cost Rs:- 56753.00
Earnest money Rs:- 1200 .00
Time Limit :- One Month

Sr.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Extraction of sludge manure and other foul material from existing septic tank and clearance of pipes including dewatering and than disposing of all surplus extracted sludge manure and other foul material including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	32430.00			Per liter	
				Total:-		


Executive Engineer
Barsar Division
HPPWD Barsar

Name of work:-C/O link road Pansai Beha to Hathol km 0/0 to 4/00
(SH:- C/O Solid casue way along with Hume pipe both side at Rd 3/200)
(under 0.5 MNH Head)

Schedule of quantity

Job No:-4

Estimated Cost Rs:-488302.00

Earnest Money Rs:-9800.00

Time Limit :- Two Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	43.81	Cubic metre		Per Cubic Metre	
2	Stone soling properly hand packed filling intersties with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax, GST or any other taxes imposed by the Government	7.00	Cubic metre		Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	75.91	Cubic metre		Per Cubic Metre	

4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can presbe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	3.50	Cubic metre			Per Cubic Metre
5	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	100.80	Cubic metre			Per Cubic Metre
6	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	20.00	Numbers			Each
7	Providing and Laying reinforced cement concrete pipe NP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government .	15.00	Running metre			Per running Metre
						Total-

Executive Engineer

Barsar Division

HPPWD Barsar


Schedule of quantity
Name of work:-C/O link road Kathera Chowk to Ropa km 0/0 to 1/165 (G.P Sareri)
(SH:- C/O Solid casue way along with Hume pipe both side at Rd 0/600)

Job No:-5
Estimated Cost Rs:-487354.00
Earnest Money Rs:-9800.00
Time Limit :- Two Month

(under 0.7 m NF Head)

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words	Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	36.41	Cubic metre			Per Cubic Metre	
2	Stone soling properly hand packed filling intersties with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax, GST or any other taxes imposed by the Government	7.00	Cubic metre			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	75.91	Cubic metre			Per Cubic Metre	

4	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can prescribe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	3.50	Cubic metre		Per Cubic Metre
5	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	100.80	Cubic metre		Per Cubic Metre
6	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	20.00	Numbers		Each
7	Providing and Laying reinforced cement concrete pipe NP ² 900mm(nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government .	15.00	Running metre		Per running Metre
					Total:-


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Name of work:-A/R M/O on bridge over Man Khad on Manipul Gauna Karour Basaral Jasoh at RD 5/190
(SH:- Providing and laying 25mm thick mastic asphalt wearing course)


Job No:-6

Estimated Cost Rs:-460219.00

Earnest Money Rs:-9300.00

Time Limit :- One Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		607.75	Square metre	Figure	words		
1	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.275 kg(zero point two seven five kilogram) per square metre on the prepared granular surface treated with primer and cleaned with hydraulic broom as per Technical Specification Clause 503 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	607.75	Square metre			Per square Metre	
2	Providing and laying 25mm (fifty millimetre thick mastic asphalt wearing course with paving grade bitumen meeting the requirements given in table 500- 29 prepared by using mastic cooker and laid to required level and slope after cleaning the surface including providing antiskid surface with bitumen precoated fine grained hard stone chipping of 13.2 mm nominal size at the rate 0.005 cubic metre per 10% square metre and at an approximate apacing of 10 centimetre center to center in both direction s pressed into surface when the temperature of surfaces is not less than 1000.C protruding 1mm to 4mm over mastic surface alll complete as per Clause 515 including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi royalty Malkana toll tax GST or other taxes	607.75	Square metre			Per square Metre	
						Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Name of work:- A/R&M/O on various road under HPPWD Barsar Sub Division
(SH:- Supply & stacking Grit & sand for patch work)

Job No:- 7

Estimated cost Rs:- 249464.00

Earnest money Rs:- 5000 .00

Time Limit :- One Month

Section Chakmoh

Sr.No	Discription of item	Quantity	Unit	Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figures	words		
1	Supplying and stacking at site hard crushed stone aggregate 10mm to 12mm (ten millimetre into twelve millimetre) nominal size broken/ crushed stone aggregate including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, G.S.T or other taxes imposed by the Government .	175.00	cubic metre			per cubic metre	
2	Supplying and stacking at site hard crushed stone aggregate 50mm to 25mm (fifty millimeter into twenty five millimeter)nominal size broken / crushed aggregate including carriage of material within all leads and lifts and other incidentalsThe rates are inclusive octroi , royalty , Malkana, toll tax, G.S.T or other taxes imposed by the Government .	175.00	cubic metre			per cubic metre	
3	Supplying and stacking river bed course sand at site work free from foreign material including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, G.S.T or other taxes imposed by the Government .	10.00	cubic metre			per cubic metre	
						Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Job No:- 8
 Estimated cost Rs:- 171000.00
 Earnest money Rs:- 3500 .00
 Time Limit :- One Month

Schedule of quantity
 Name of work:- A/R&M/O on various road under HPPWD Barsar Sub Division
 (SH:- Supply & stacking ~~fuel~~ hard fuel wood for patch work on various roads)

Sr.No	Discription of item	Quantity	Unit	Rate inclusive all taxes i/c G.S.T		Amount	
				Figures	words	Per Quintal	Total:-
1	Supplying and stacking dry bansu hard fuel wood in logs not less than 25cm (twenty five centimeter) in girth and stacking in proper stacks including loading unloading including sand paper smooth complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	450.00	Quintal				


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Job No:- 9

Name of work:-SDF/ 2021/21 Repair of link road Chakdad to Sasan Bali (G.P Makkar) , SDF/ 2021/22 Repair of link road Charcheri (G.P Dandroo)

Estimated Cost Rs:- 179165.00

Earnest Money Rs:-3600.00

Time Limit :- One Month

SDF/ 2021/23 Repair of link road Ghunani (G.P Tipper) , SDF/ 2021/24 Repair of link road Bumbloo to Kaloun (G.P Kaloun) ,

SDF/2021/25 Repair of link road Balh to Bumbloo (G.P Bal Bihal)

(SH:- Removal of slips & maintenance of drain and maintenance of earthen shoulder at various RDs) (Deposit Work)

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Maintenance of earthen shoulder (filling with fresh slected soil making up less of material / irrigations on shoulder in design level by adding fresh approved selected soil and compacting it with approprait equipment OMC upto a lead of 1000mtrs as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government .	3905.00 Square metre			Per square Metre	
2	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slops and disposal all marital upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	246.00 cubic metre			Per Cubic Metre	
3	Surface drain in soil_ construction of unlined surface drains of average cross section area 0.40sqm (zero point four zero sqare metre) in soil to specified lines, grades, levels and dimensions . Excavated material to be used in embankment with a lift upto 3m(three metre) and lead of 50 m(fifty metre) average lead 25m) as per technical specification Clause No 307 (mechanical means) including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	2520.00 Running metre			Per running Metre	

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:- Preparation of DPRs i/c Plan, L-section X-section and Survey of work for the Up-Gradation/ improvement of
Jalari Salouni Bijhari Deotsidh road Km 27/00 to 52/500 (under MLA priority 2014-15)

Job No :- 10

Estimated Cost Rs:- 459000.00

Earnest Money Rs:- 9200.00

Time Limit :- Two Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Preparation of detailed project report and drawings complete in all respect in manuscript form and submission of the same to Higher office for approval . If any correction / amendment has desired by the Head office. The same may be corrected as desired and directed by the Engineer-in- Charge complete in all respect. After approval the same should be submitted dully computerized spiral bending in pen triplicate . The payment shall be made as per actual length of road . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	25.500 kilometre			Per kilometre	
					Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar