



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on **13-05-2022 up to 11:30 A.M.** and will be opened on the same day at **(12:00 noon)** in the presence of intending contractors. The tender application will be received in this office against cash payment on **11-05-2022 up to 10.00 A.M. to 12:30 P.M.** and tender form can be had from this office on **12-05-2022 from 2.00 P.M. to 5.00 Pm.** The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST, work done certificate, proof of machinery etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

Sr. No.	Name of work	Amount put to tender/ Est. cost	Earnest money	Cost of Tender Form	Eligible Class of Contractor	Time
1	Periodical Maintenance of Sandhapattan Lad Bharol Basahi Banwar Kotli road (MDR-057) Major District road under Annual Maintenance Plan 2022-23. (Sub Head:- Providing and laying built-up spray grout, bituminous concrete in Km. 4/210 to 4/387)	₹ 3,49,239/-	₹ 7,000/-	₹ 350/-	"All classes deal with bitumen's works"	Two months
2	A/R & M/O Sandhapattan Lad Bharol Basahi Banwar Kotli road (MDR-057) Km. 0/0 to 85/0 (Sub Head:- Providing and laying built-up spray grout, bituminous concrete in Km. 4/0 to 4/195).	₹ 4,36,542/-	₹ 8,700/-	₹ 350/-	"All classes deal with bitumen's works"	Two months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No. the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

District Mandi (HP) on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2022-23-

3832-56

Dated:- 30-4-2022

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. Drawing Branch in this office.
7. Notice Board.
8. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD,
Joginder Nagar.

SCHEDULE OF QUANTITY

Name of Work : Periodical Maintenance Sandapattan Lad Bharol Bashai Banwar Kotli Road (MDR-57) Km 0/00 to 85/00

(Sub-Head:- Providing and laying built-up spray grout, bituminous concrete in Km. 4/210 to 4/387)

Sr. No. Description of work

No. or Qty. Unit

Figures Rate Words

AMOUNT Rs.

1 Providing, laying, spreading and rolling of built-up spray grout layer using bitumen VG-10 over prepared base by manual means consisting of a Double layer composite construction of crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder after each layer, and with key aggregates placed on top of the second layer to serve as a base, conforming to the line, grades and cross-section specified, the compacted layer thickness being 75mm (Seventy five millimetre) as per Technical Specification, complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge.

2 Providing and applying tack coat with bitumen emulsion conforming to IS-8887 (RS-1) using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom on the prepared dry and hungry bituminous surface @ 0.275 kg/sqm (at the rate of zero point two seven five kilogramme per square metre) as per technical specification, complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge.

3 Providing and Laying bituminous concrete 30mm (thirty millimetre) compacted thickness with bitumen of grade VG-10 (ten) @ 5.0% (at the rate of five point zero per cent) (percentage by weight of total mix) and lime/cement filler @ 2% (three percentage) (percentage by weight of aggregate) prepared in Batch Type Hot Mix Plant of 100-120 (Hundred - one hundred twenty) TPH capacity by using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge.

Total

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar


SCHEDULE OF QUANTITY

Name of Work : Annual Repair and Maintenance of Sandapattan Lad Bharol Bashai Banwar Koti Road (MDR-57)
Km 0/00 to 85/00

Estimate Cost: 4,36,542
Earnest Money: 8,700
Time Limit : 100 Mon

(Sub-Head:- Providing and laying built-up spray grout, bituminous concrete in Km. 4/00 to 4/195)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
2	Providing, laying, spreading and rolling of built-up spray grout layer using bitumen VG-10 over prepared base by manual means consisting of a Double layer composite construction of crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder after each layer, and with key aggregates placed on top of the second layer to serve as a base, conforming to the line, grades and cross-section specified, the compacted layer thickness being 75mm (Seventy five millimetre) as per Technical Specification, complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge.	293.42	Per square metre			
3	Providing and applying tack coat with bitumen emulsion confirming to IS:8887 (RS-1) using emulsion pressure distributor including preparing the surface and cleaning with mechanical broom on the prepared dry and hungry bituminous surface @ 0.275 kg/sqm (at the rate of zero point two seven five kilogramme per square metre) as per technical specification, complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge.	652.05	Per square metre			
4	Providing and Laying bituminous concrete 30mm (thirty millimetre) compacted thickness with bitumen of grade VG-10 (ten) @ 5.0% (at the rate of five point zero per cent) (percentage by weight of total mix) and lime/cement filler @ 2% (three percentage) (percentage by weight of aggregate) prepared in Batch Type Hot Mix Plant of 100-120 (Hundred - one hundred twenty) TPH capacity by using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equiped with electronic sensor to the required garde, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete in all respect including haulage of material in all leads and lifts by all modes of transportation and as per the entire satisfaction and direction of Engineer-in-Charge.	19.56	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar