

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-MDI(Padhar)E-Tender-NIT/2022-23-

1263-65

Dated:- 6/5/22

To

✓ The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: -

Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **20.05.2022 up to 12:00 Noon** and the same shall be opened on the same day **at 12:30 P.M.** in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on **19.05.2022 upto 01:00 P.M.**

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Annual repair and maintenance of Drang Basahi road Km 0/0 to 22/0 (SH:- Repair of pot holes in Km 0/0 to 2/500) (Under SCSP)	4,02,589/-	8,100/-	350/-	One month
2	Annual repair and maintenance of Drang Basahi road Km 0/0 to 22/0 (SH:- Repair of pot holes in Km 2/500 to 5/0) (Under SCSP)	3,82,264/-	7,600/-	350/-	One month
3	Annual repair and maintenance of Drang Basahi road Km 0/0 to 22/0 (SH:- Repair of pot holes in Km 5/0 to 8/0) (Under SCSP)	3,83,936/-	7,700/-	350/-	One month
4	Annual repair and maintenance of Drang Basahi road Km 0/0 to 22/0 (SH:- Repair of pot holes in Km 14/0 to 15/0 & WBM G-III in Km 20/700 to 22/0) (Under SCSP)	4,98,636/-	10,000/-	350/-	One month
5	Annual repair and maintenance of Drang Basahi road Km 0/0 to 22/0 (SH:- Repair of pot holes in Km 20/700 to 22/0) (Under SCSP)	3,05,646/-	6,100/-	350/-	One month
6	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of pot holes by providing BUSG in Km 5/0 to 8/0)	4,70,043/-	9,400/-	350/-	One month
7	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of pot holes by providing BUSG in Km 8/0 to 8/420)	4,78,748/-	9,600/-	350/-	One month
8	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of pot holes in Km 3/500 to 5/0 & balance work in Km 9/0 to 9/500)	4,93,608/-	9,900/-	350/-	One month
9	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of pot balance holes in Km 9/500 to 10/500)	4,95,538/-	9,900/-	350/-	One month
10	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of balance pot holes in Km 10/500 to 11/500)	4,77,322/-	9,500/-	350/-	One month
11	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of pot holes in Km 11/500 to 12/500)	4,78,891/-	9,600/-	350/-	One month

12	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of pot holes in Km 12/500 to 14/0)	4,99,069/-	10,000/-	350/-	One month
13	Annual repair and maintenance of Padhar Balh road Km 0/0 to 18/500 (SH:- Repair of pot holes in Km 14/0 to 14/500)	3,55,133/-	7,100/-	350/-	One month

1. **Certified that tender of above works are being called of emergent nature in exigency of public interest.**

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.
5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh


(1)

Schedule of Quantity

Estimated Cost:- Rs. 402589.00
 Earnest Money:- Rs. 8100.00
 Time:- One month

Name of work:- Annual repair and maintenance of Drang Basahi road Km. 0/0 to 22/0.
 Sub Head:- Repair of pot holes in Km. 0/0 to 2/500 under SCSP.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	12.58 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1740.51 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.I
 H.P. PWD. at Padhar

2

Schedule of Quantity

Estimated Cost:- Rs. 382264.00
 Earnest Money:- Rs. 7600.00
 Time:- One month

Name of work:- Annual repair and maintenance of Drang Basahi road Km. 0/0 to 22/0.

Sub Head:- Repair of pot holes in Km. 2/500 to 5/0 under SCSF.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer-in-Charge.	7.44 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1725.49 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P. PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 383936.00
 Earnest Money:- Rs. 7700.00
 Time:- One month

Name of work:- Annual repair and maintenance of Drang Basahi road Km. 0/0 to 22/0.
 Sub Head:- Repair of pot holes in Km. 5/0 to 8/0 under SCSP.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	7.58 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1731.30 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P.W.D. at Padhar

(4)

Schedule of Quantity

Estimated Cost:- Rs. 498636.00
 Earnest Money:- Rs. 10000.00
 Time:- One month

Name of work:- Annual repair and maintenance of Drang Basahi road Km. 0/0 to 22/0.

Sub Head:- Repair of pot holes in Km. 14/0 to 15/0 & WBM G-III in Km. 14/0 to 15/0 & 20/700 to 22/0 under SCSP.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	50.67 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1556.08 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 305646.00
 Earnest Money:- Rs. 6100.00
 Time:- One month

Name of work:- Annual repair and maintenance of Drang Basahi road Km. 0/0 to 22/0.
 Sub Head:- Repair of pot holes in Km. 20/700 to 22/0 under SCSP.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1463.47 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P. PWD. at Padhar

6

Schedule of Quantity

Estimated Cost:- Rs. 470043.00
Earnest Money:- Rs. 9400.00
Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.
Sub Head:- Repair of pot holes by providing BUSG in Km. 5/0 to 8/0.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and rolling of built-up spray grout layer over prepared base consisting of a two layer composite construction of crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder (S-90/ VG-10) after each layer, and with key aggregates placed on top of the second layer to serve as a base, conforming to the line, grades and cross-section specified, the compacted layer thickness being 75mm (Seventy five millimetre) as per Technical Specification Clause 505 of MORD by manual means including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	810.00 Sqm.			Per square metre	
					Total:-	


Executive Engineer,
Mandi Division No.1
HP.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 478748.00
 Earnest Money:- Rs. 9600.00
 Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.

Sub Head:- Repair of pot holes by providing BUSG in Km. 8/0 to 8/420.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and rolling of built-up spray grout layer over prepared base consisting of a two layer composite construction of crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder (S-90/ VG-10) after each layer, and with key aggregates placed on top of the second layer to serve as a base, conforming to the line, grades and cross-section specified, the compacted layer thickness being 75mm (Seventy five millimetre) as per Technical Specification Clause 505 of MORD by manual means including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	825.00 Sqm.			Per square metre	
					Total:-	

Executive Engineer,
 Road Division No.1
 H.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 493608.00
 Earnest Money:- Rs. 9900.00
 Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.

Sub Head:- Repair of pot holes in Km. 3/500 to 5/0 & balance work in Km. 9/0 to 9/500.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	2201.64 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 495538.00
 Earnest Money:- Rs. 9900.00
 Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.

Sub Head:- Repair of pot balance holes in Km. 9/500 to 10/500.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	2210.25 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 J.D.PWD. at Padhar

10

Schedule of Quantity

Estimated Cost:- Rs. 477322.00
 Earnest Money:- Rs. 9500.00
 Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.

Sub Head:- Repair of balance pot holes in Km. 10/500 to 11/500.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	2129.00 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P.W.D. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 477322.00
 Earnest Money:- Rs. 9500.00
 Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.

Sub Head:- Repair of pot holes in Km. 11/500 to 12/500.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	2129.00 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 J.P.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 499069.00
 Earnest Money:- Rs. 10000.00
 Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.

Sub Head:- Repair of pot holes in Km. 12/500 to 14/0.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	2226.00 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 355133.00
 Earnest Money:- Rs. 10000.00
 Time:- One month

Name of work:- Annual repair and maintenance of Padhar Balh road Km. 0/0 to 18/500.

Sub Head:- Repair of balance pot holes in Km. 14/0 to 14/500.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1584.00 Sqm.			Per Square metre	
					Total:-	

Executive Engineer,
 Mandi Division No.1
 H.P.W.D. at Padhar