

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT
NOTICE INVITING TENDER

Sealed items rates tender on form No. 6 and 8 are hereby invited on behalf of Governor of HP for the following works from approved and eligible contractor enlisted in HPPWD so as to reach in this office 30.05.2022 upto 10:30 AM and shall be opened on the same day at 11:00 AM in the presence of intending contractors or their authorised representative who may link to be present. The tender form be had from his office against cash payment (non refundable) during working hours.

The earnest money in the shape of FDR/TDR in HP duly pledged in favour of Executive Engineer Rajgarh Division HPPWD Rajgarh must be accompanied with the each tender. Conditional tender and tender received without earnest money will be rejected. The undersigned reserves the right to reject any or all tenders without assigning the reason. The offer of the tender will be kept opened for 75 days.

Sr. No.	Tender Sechedule	
1	Last date for tender receipt of application for tender form	27.05.2022 upto 4:00 PM
2.	Last date of sale of tender forms.	28.05.2022 upto 4:00 PM
3.	Date of receipt of tender forms	30.05.2022 upto 10:30AM
4.	Date of opening of tenders	30.05.2022 at 11:00AM

Sr. No	Name of Work	Estimated cost	Earnest Money	Time Limit	Cost of form
1.	A/R & M/O to Gain Kot Matal Bakhog road km 0/0 to 5/300 (SH: Providing and laying of stone aggregate 53 mm to 22.4 mm size G-III aggregate for repair of damaged depressed and sunken portion and pot holes etc in km 0/0 to 3/500.	4,98,750/-	10,000/-	One Month	350/-
2.	Preparation of Detail Project Report for C/O link road Palu to Bharan via Kathli km 0/0 to 6/500 (SH:- C/O 5/7 mtr wide road in Km 0/0 to 2/0 & C/O 5/7 mtr road in Km. 2/0 to 6/500, CD & Soling in Km. 0/0 to 6/500). Under NABARD	97,500/-	2,000/-	One Month	350/-
3.	A/R & M/O of HPPWD Rest House at Rajgarh, District Sirmour (HP) (Sh:- Providing and Laying Paint and Distemper in Building)	2,27,934/-	4,600/-	One Month	350/-
4.	A/R & M/O to Habban Dhamoon road Km. 0/0 to 21/465 (SH:- Maintenance of unlined drain and earthen shoulder in Km 5/0 to 9/0)	2,29,240/-	4,600/-	One Month	350/-
5.	A/R & M/O to Habban Dhamoon road Km. 0/0 to 21/465 (SH:- Maintenance of unlined drain and earthen shoulder in Km 13/0 to 18/0)	2,64,158/-	5,300/-	One Month	350/-
6.	C/O Link road Plau to Bharan to via Kathli Km 0/0 to 6/500 (SH:- C/O Removal of formation defeiciency in Km 0/0 to 0/495)	4,91,475/-	9,900/-	One Month	350/-
7.	C/O Link road Plau to Bharan to via Kathli Km 0/0 to 6/500 (SH:- C/O Removal of formation defeiciency in Km 0/495 to 1/00)	4,96,501/-	10,000/-	One Month	350/-
8.	A/R & M/O to Solan Meenus road km 24/345 to 61/0 (SH:- Providing and laying BM repair of damages portion in Km 30/0 to 33/0)	3,01,604/-	6,100/-	One Month	350/-
9.	C/O link road from Mattal Bakhog to Nag Timba road Km. 0/0 to 3/300 (SH:- C/o 5/7 Mtr wide motorable road in Km 0/640 to 1/405). Under MNP	4,95,873/-	10,000/-	One Month	350/-
10.	C/O link road from Mattal Bakhog to Nag Timba road Km. 0/0 to 3/300 (SH:- C/o 5/7 Mtr wide motorable road in Km 1/405 to 2/105). Under SCSP	4,95,177/-	9,900/-	One Month	350/-
11.	Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road km 48/0 to 87/0 (SH:- C/O Brest Wall between Km 82/315 to 82/330)	287305/-	5800/-	One Month	350/-

Certificate :-It is certified that the tender of above work are exigency/emergent nature and in public interest.

Terms & conditions:-

1. The contractors/Bidders must submit their Permanent Income Tax Account Number/GST number on the tender along with copy of the same be attached with the application.
2. The contractor/Firms should attached copy of the Registration/Renewal with the application
3. The contractor/bidder should quoted his rates both in Figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be governed.
4. The contractors/bidders must inspect the site to ascertain/familiar the site conditions, accessibility etc. Before quoting the bid/tender.

5. Conditional and telegraphic tender shall be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/firm should have to produce the detail of work in hand in HPPWD and its position therefore along with application.
7. The tender document shall be issued to only those contractors who do not have more than two works in hand in any HPPWD Circle/ Division worth Rs. 1.00 crore each.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid upto 75 days.
10. The above Job is on present market rates and tender will be processed as per instruction issued by the Add. Chief Secretary (PW) to the Govt. of H.P notification No. PBW(B)A(3)1/2020 dt. 22.07.2020. Regarding adoption of CPWD works manual 2019 & other publication of CWP in HPPWD shall also be applicable.
11. The Executive Engineer reserve the right any or all the tenders without assigning any reason.


Executive Engineer
HPPWD Division Rajgarh
Distt Sirmour HP

on behalf of Governor of Himachal Pradesh

Tel. No. 01799-221023

Mail. ee-raj-hp@nic.in

Dated:-


19-05-2022

No.PW/RGH/Estt-Tender/2022-23-

2436-85

Copy forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP.PWD.Shimla-1.
2. The Chief Engineer (South) HP.PWD.Shimla-1.
3. The Superintending Engineer, 12th Circle HPPWD Nahan.
4. The Executive Engineer (IT Cell), Nigam Vihar, HPPWD Shimla-2 for uploaded of Notice Inviting Tenders on Departmental website please.
5. All the Assistant Engineers working under this Division.
6. All Head of Branches of this office.
7. All Intending Bidders/Contractors.
8. Notice Board.


Executive Engineer,
Rajgarh Division,
HP.PWD Rajgarh.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to Gain Kot Matal Bakhog road km 0/0 to 5/300 (SH: Providing and laying of stone aggregate 53 mm to 22.4 mm size G-III aggregate for repair of damaged depressed and sunken portion and pot holes etc in km 0/0 to 3/500.

Job No. 2

Estimated cost:-Rs. 4,98,750/-

Earnest money:- Rs. 10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing and laying at site of work stone aggregate-Grading- 3, 53 mm to 22.4 mm(size as per HP.PWD. Specification 1990 Volume-1 including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads lifts and during the course of supply of material shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect including all incidental charges.	250.00	Per Cubic Metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work :- Preparation of Detail Project Report for C/O link road Palu to Bharan via Kathli km 0/0 to 6/500 (SH:- C/O 5/7 mtr wide road in Km 0/0 to 2/0 & C/O 5/7 mtr road in Km. 2/0 to 6/500, CD & Soling in Km. 0/0 to 6/500). Under NABARD

Job No. 3

Estimated cost:-Rs. 97,500/-
Earnest money:- Rs. 2,000/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Preparation of detail project report and drawing (Plan, L-section & X-section etc) complete in all respect including all required test in manuscript form and submission of the same to higher office for approval. If any correction/ ammendment will be desired by the head office the same may be corrected as desired and directed by the Engineer-In-Charge and complete in all respect. After approval the same from the head office should be submitted in five fair copies, working estimate, DNIT and soft copy of all as per the requirement of this office.	6.500	Per Kilometre	15000.00	Rs. Fifteen thousand and paise nil only.	97500.00
					Total:	97500.00


 Executive Engineer
 Rajgarh Division
 HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work: A/R & M/O of HPPWD Rest House at Rajgarh, District Sirmour (HP) (Sh:- Providing and Laying Paint and Distemper in Building)

Job No.

Estimated cost:-Rs. 2,27,934/-

Earnest money: - Rs. 4,600/-

Time Limit: - One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Distemping with oil bond washable distemper of approved brand and manufacture (two coats) and of required shade on undecorated wall surface to give an even shade over and including a priming coat of with distemper primer approved brand and manufacture thoroughly brushing the surface free from mortar droppings and other foreign matter including preparing the surface even and sand papered smooth complete as per HP.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of	1128.78	Per Square metre.			
2	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade. New work two or more coats applied 21.43ltr/10sqm over and including priming coat of exterior primer applied 0.90 ltr/10sqm as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	567.09	Per Square metre.			
3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	315.59	Per Square metre.			
4	French spirit polishing Two or more coats on new works including a coat of wood filler as per HP.PWD specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	126.80	Per Square metre.			


 Executive Engineer
 Rajgarh Division
 HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work : A/R & M/O to Habban Dhamoon road Km. 0/0 to 21/465 (SH:- Maintenance of unlined drain and earthen shoulder in Km 5/0 to 9/0)

Job No.

Estimated cost:-Rs.2,29,240/-
Earnest money:- Rs. 4,600/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903.	4200.00	Per Square Metre			
2	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site. by mechanical means as per H.P.PWD. specification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	2500.00	Per Running Metre.			


Executive Engineer
Rajgarh Division
HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work: A/R & M/O to Habban Dhamoon road Km. 0/0 to 21/465 (SH:- Maintenance of unlined drain and earthen shoulder in Km 13/0 to 18/0)

Job No.
Estimated cost:-Rs.2,64,158/-
Earnest money:- Rs. 5,300/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 .	4725.00	Per Square Metre			
2	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site. by mechanical means as per H.P.PWD. specification, including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts including all incidental charges.	3000.00	Per Running Metre.			


Executive Engineer
Rajgarh Division
HPPWD Rajgarh

Job No.
Estimated cost:-Rs. 4,91,475/-
Earnest money:- Rs.9,900/-
Time Limit:- One Month.

SCHEDULE OF QUANTITY

Name of work : C/O Link road Plau to Bharan to via Kathli Km 0/0 to 6/500 (SH:- C/O Removal of formation defeiciency in Km 0/0 to 0/495)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones,whether useful or not, for 178.11 cum (One hundred seventy eight point eleven cubic metre) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3636.65	Per cubic metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work : C/O Link road Plau to Bharan to via Kathli Km 0/0 to 6/500 (SH:- C/O Removal of formation defeiciency in Km 0/495 to 1/00)

Job No.

Estimated cost:-Rs. 4,96,501/-

Earnest money:- Rs.10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangements of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones,whether useful or not, for 190.00 cum (One hundred ninety point zero zero cubic metre) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3900.24	Per cubic metre.			


 Executive Engineer
 Rajgarh Division
 HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work: A/R & M/O of Solan Meenus road Km 9/345 to 46/0 (SH :- Providing & Laying BM, for repair of damage portion in Km. 30/0 to 33/0)

Job No.
Estimated cost:-Rs. 3,01,604/-
Earnest money:- Rs. 6,100/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Providing and laying bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder, transported to site upto a lead of 1000 m laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504.(Four hundred Five) upto entire satisfaction & direction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	29.442	Per Cubic Meter			
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (zero point two five to zero point three kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	588.84	Per Square Meter			


Executive Engineer
Rajgarh Division
HPPWD Rajgarh

SCHEDULE OF QUANTITY

Name of work : C/O link road from Mattal Bakhog to Nag Timba road Km. 0/0 to 3/300 (SH:- C/o 5/7 Mtr wide motorable road in Km 0/640 to 1/405). Under MNP

Job No. 4

Estimated cost:-Rs. 4,95,873/-

Earnest money:- Rs. 10,000/-

Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones,whether useful or not, for 230.10 cum (Two hundred thirty point ten cubic metre) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3539.93	Per cubic metre.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work : C/O link road from Mattal Bakhog to Nag Timba road Km. 0/0 to 3/300 (SH:- C/o 5/7 Mtr wide motorable road in Km 1/405 to 2/105). Under SCSF

Job No. 8
Estimated cost:-Rs. 4,95,177/-
Earnest money:- Rs.9,900/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindness and finishing of the road to specified dimensions or as directed by the Engineer -in -Charge for smooth riding. The recovery for stones,whether useful or not, for 236.32 cum (Two hundred thirty six point thirty two cubic metre) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro- rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3489.25	Per cubic metre.			



Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Banethi Bagthan Rajgarh Chandol road Km 48/0 to 87/0 (SH:- C/O Breast wall between Km 82/315 to 82/330).

Estimated cost:-Rs.2,87,305/-
Earnest money:- Rs. 5,800/-
Time Limit:- One Month.

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earthwork in excavation for all type of roads, structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) and 1606.1(One six zero six point one) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts including dressing of sides and bottom and backfilling in trenches with excavated suitable material. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side & any structure near about, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site(to be arranged by the contractor), trimming, filling of unevenness blindages and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	42.08	Per Cubic Metre.			
2	Providing and laying concrete for plain Cement concrete in 1-4:8 (one cement: four sand: eight graded crushed hard stone aggregate 40 (forty) millimeter nominal size) mechanical mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	60.72	Per Cubic Meter.			
3	Providing weep holes in brick masonry/Plain/Reinforced concrete abutment, wing wall/ return wall with 100 mm (one hundred millimeter) dia AC pipe, extending through the full width of the structure with slope of 1: 20 1(V): 20 (H) towards drawing face. Complete as per drawing and technical specifications clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	14.00	Each			
4	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	2.70	Per cubic meter.			


Executive Engineer
Rajgarh Division
HP, PWD, Rajgarh