

HIMACHAL PRADESH

PUBLIC WORKS DEPARTMENT

NO:-PW/SD/CB/TA/NIT /2022- 23-

657

Dated- 30-4-2022

To

The Executive Engineer (IT Cell)
Nigam Vihar, Shimla-2,

Subject:-


Tender Notice.

Dear Sir,

Enclosed Please find herewith the notice work as given in the notice inviting tender for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP. Letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency are urgent nature and in public interest.

DA:- Notice inviting tender and sechedule of quantity.


Executive Engineer
B&R Division Shillai
HP PWD Shillai


CERTIFICATE

Certified that the tenders of works, as called vide this office letter

No.PW-SD-CB-TA 2022-23- 658-707

dated 30/04/2022

are of urgent nature.


Executive Engineer
B&R Division Shillai
HP PWD Shillai

Himachal Pradesh
Public Works Department
Notice inviting Tender


Sealed item rate tender on form PWD 6 & 8 are invited by the Executive Engineer Shillai, Division HP, PWD on behalf of governor of himachal Pradesh for the following works from approved and eligible contractors enlisted in HP PWD. So as to reach in this office as per time schedule given below.

1. Date of receipt of application of tenders forms:- 07-05-2022 at 10:00 AM, Up To 12:00 PM
2. Date of issue/ sale of tender Forms:- 07-05-2022 at 1:00 PM, Up To 3:00 PM
3. Date of receipt of tender 07-05-2022 at 3:30 PM,
4. Date of opening of tender:- 07-05-2022 at 4:00 PM,

Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender Form	Eligible of class of Contractor
Construction of link road from Kafenu Via Kukrech Bogra Konla Thana to Manal G.P Loza Km 0/0 to 3/345 (SH-Balance work of formation cutting 5/7 Mtrs wide road in Km 0/840 to 1/045 (0/930)	4,17,815/-	8360/-	Two Months	350/-	C & D Class

Terms and conditions :- The tender documents shall be issued only to these contractors firms who fulfill the following criteria and submit the following documents with the application.

1. The Earnest money for the above works should be submitted with applications for the purchase of the tender documents.
2. The contractors should quote the rates of all the items in the tenders both in figures and words.
3. Income Tax and GST No. latest clearance certificate.
4. The contractors/firms shall accompany his enlistment /renewal and EPF submit before the award of tender.
5. The contractor should apply for two works only at a time for tenders.
6. The Executive Engineer reserves the right to accept / rejected any tender/applications or all tenders without assigning any reason.


Executive Engineer
B&R Division Shillai
HP PWD Shillai


dated- 30-4-2022

PW-SD-CB-TA-2022-23

658-707

Copy forwarded for information and wide publicity to:-

1. The Superintending Engineer in 12th HP PWD in Nahan.
2. All the Assistant Engineer working under this Division.
3. A/B and D/B in this office.
4. Notice Board.


Executive Engineer
B&R Division Shillai
HP PWD Shillai

DRAFT SCHEDULE OF QUANTITY

Name of work:-Construction of link road from Kafenu Via Kukrech Bogra Konla Thana to Manal G P. Lojja Km 0/0 to 3/345 (SH - Balance work				Job-		Estimated Cost 417815/- only
of formation Cutting 5/7 Mtrs wide road in Km 0/840 to 1/045(0/930))						Earnest Money 8060/- only
						Time Allowed - Two Months
S.No	Sub-Heads and Items of Work	Quantity	Unit	Rate in		Amount
1	2	3	4	In Figures	In Words	7
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soils including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting , blasting workshall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side rock shall be excavated with chiseling and wedgingout rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification of rural roads, and clause 16.2(Sixteen point two) of General conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposalal dumping to be arranged by the contractor of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery for stones, whether useful or not, for 408 96 cubic metre (Four hundred eight point nine six cubic metre) in all cases @ Rupees 170/- (Rupees one hundred seventy only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1892.620	Per Cubic meter	220.76	Rupees Two hundred twenty and seventy six Paise only	417815.00
Total:-						417815.00

The contractor shall procure all the materials conforming to specification. MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.

Draft of Schedule of quantity approved for Rs. 417825/- only

[Signature]
Executive Eng

Shillai Division
HP BWD, Shillai

SCHEDULE OF QUANTITY

Name of work: -Construction of link road from Kafenu Via Kukrech Bogra Konla Thana to Manal G.P. Lojia Km 0/0 to 3/345 (SH - Balance work of formation Cutting 5/7 Mtrs wide road in Km 0/840 to 1/045(0/930))


Job-

Estimated Cost - 417815/- only
Earnest Money - 8360/- only
Time Allowed - Two Months.

S.No	Sub-Heads and Items of Work	Quantity	Unit	Rate in		Amount
				In Figures	In Words	
1	2	3	4	5	6	7
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soils including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting, blasting work shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation, including rock excavation shall be carried out true to lines, grades, side slopes, width, camber, super-elevation and level as shown on the drawings or as directed by the Engineer-in-charge, in conformity with the requirement of technical specification of rural roads, and clause 16.2(Sixteen point two) of General conditions for Contract to achieve designed formation width including hauling and stacking of material useful for construction at suitable sites and safe disposal and dumping to be arranged by the contractor of unsuitable cut materials in specified manner, trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in charge for smooth riding. The recovery for stones, whether useful or not, for 408.96 cubic metre (Four hundred eight point nine six cubic metre) in all cases @ Rupees 170/- (Rupees one hundred seventy only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1892.620	Per Cubic meter			
Total:-						

The contractor shall procure all the materials conforming to specification MORT&H at his own risk and cost. All the rates including octroi, royalty, malkhana, toll tax, GST or other taxes imposed by the Government.

Name, Signature and full address with Mob.No. of the contractor:-


Executive Engineer
Shillai Division
HP PWD, Shillai