

**HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Division HPPWD Solan.

Email: [ee-sol-hp@nic.in](mailto:ee-sol-hp@nic.in) Land line NO:-Fax NO:-01792-223811

No.PW-SD/CB-Tender/-22-23-

1703-08

Dated:- 09/05/22

To


The Executive Engineer (IT Cell),  
Nigam Vihar, Nirman Bhawan,  
HPPWD, Shimla-2  
Email ID:-[cc-pwd-hp@nic.in](mailto:cc-pwd-hp@nic.in)

Subject: -

Publication of e-Tender Notice.


Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19<sup>th</sup> June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

  
Executive Engineer,  
Solan B & R Division,  
H.P.P.W.D, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), H.P.P.W.D., Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3<sup>rd</sup> Circle, HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

  
Executive Engineer,  
Solan B & R Division,  
H.P.P.W.D, Solan.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER  
(Exigency)**

Sealed item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD. Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	18.05.2022	*
1	The last date for receipt of application for tender form.		Upto 4.00 P.M.
2	The last date sale of tender forms.	19.05.2022	Upto 4.00 P.M.
3	The date for receipt of tender forms.	20.05.2022	Upto 10.30 A.M.
4	The date of opening of tender	20.05.2022	At 11.00 A.M.

The tender shall be received upto **10.30 A.M. 20.05.2022** and will be opened on the same day at **11.00 AM** in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs)	Time	Cost of Form
1.	"Construction of District Treasury Officer residence at Solan, District Solan(H.P)(SH:-C/o building portion, Providing WS & SI, Rain harvesting tank & site development)(SW:-Providing and laying reinforced cement concrete in roof beams".	1,76,303/-	3,550/-	One Months.	Rs.350/-
2.	"Construction of District Treasury Officer residence at Solan, District Solan(H.P)(SH:-C/o building portion, Providing WS & SI, Rain harvesting tank & site development)(SW:-Providing and laying reinforced cement concrete in slab of building".	2,94,691/-	5,900/-	One Months.	Rs.350/-
3.	"Construction of District Treasury Officer residence at Solan, District Solan(H.P)(SH:-C/o building portion, Providing WS & SI, Rain harvesting tank & site development)(SW:-Providing and laying reinforced cement concrete in plinth beam and stair case".	3,03,528/-	6,100/-	One Months.	Rs.350/-
4.	"Construction of District Treasury Officer residence at Solan, District Solan(H.P)(SH:-C/o building portion, Providing WS & SI, Rain harvesting tank & site development)(SW:-Providing and laying reinforced cement concrete in columns, beams and roof slab in building".	3,42,708/-	6,900/-	Two Months.	Rs.350/-

5.	"Construction of Sadhupul Tharola Dhar Ki Ser Via Nihara road Km.0/0 to 0/250 in Solan Constituency under SCSP(SH:-C/o jeepable 2.75/5.00mtrs wide road, CD work, soling in Km.0/0 to 0/250 & C/o 18.00mtrs span single Bridge at R.D.0/250(SW:- Removal of deficiency of road in Km.0/0 to 0/180".	4,90,359/-	9,850/-	Two Months.	Rs.350/-
6.	"Construction of Sadhupul Tharola Dhar Ki Ser Via Nihara road Km.0/0 to 0/250 in Solan Constituency under SCSP(SH:-C/o jeepable 2.75/5.00mtrs wide road, CD work, soling in Km.0/0 to 0/250 & C/o 18.00mtrs span single Bridge at R.D.0/250(SW:- Removal of deficiency of road in Km.0/0 to 0/090".	4,81,946/-	8,400/-	Two Months.	Rs.350/-

**TERMS & CONDITIONS:-**

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms. Application without earnest money will not be
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.

**SCHEDULE OF QUANTITY**

SL. No.		Description of work	Qty.	Unit	RATE In		AMOUNT
					Figures	Words	Rs.
Job No. :- 1							
					Estimated Cost: -		176303.00
					Earnest Money: -		3550.00
					Time limit: -		One Month
Name of work :- Construction of District Treasury officer residence at Solan District Solan (HP) (SH:- C/O Building portion , Providing WS & SI , Rain harvesting tank & site development) (SW:- P/Lreinforced cement concrete in roof beams)							
1		Providing and laying cement concrete 1:1.5:3 (one cement isto one point five Sand isto three graded stone aggregate 20 mm (twenty milimeters) nominal size in foundation and plinth and curing complete excluding cost of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	8.950 m <sup>2</sup>	Per Cubic metre			
2		Providing tor Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per structural drawing in all floors up to all heights and levels, direction of Engineer-in-Charge and as per HP.PWD. Specification 1990 volume-I, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1405.150 *	Per kilopgra mme			
Total :-							
Total in Words							

T/S No. 33 for the 2022-23.

Sr. No. 52 for the year 2022-23.



Executive Engineer  
B&R Division, HP.PWD, Solan.




**SCHEDULE OF QUANTITY**

SL. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	Rs.
Job No. :- 2				Estimated Cost: -		294691.00
				Earnest Money: -		5900.00
				Time limit : -		One month.
<u>Name of work</u> : - Construction of District Treasury officer residence at Solan District Solan (HP) (SH:- C/O Building portion , Providing WS & SI . Rain harvesting tank & site development) (SW:- P/L reinforced cement concrete in slab of building)						
1	Providing and laying cement concrete 1:1.5:3 (one cement isto one point five Sand isto three graded stone aggregate 20 mm (twenty milimeters) nominal size in foundation and plinth and curing complete excluding cost of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	14.960 m2	Per Cubic metre			
2	Providing tor Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per structural drawing in all floors up to all heights and levels, direction of Engineer-in-Charge and as per HP.PWD. Specification 1990 volume-I, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2348.700	Per kilopgrame			
Total :-						
Total in Words						

T/S No. 28 for the 2022-23.

Sr. No. 49 for the year 2022-23.

  
 Executive Engineer  
 B&R Division, HP.PWD. Solan.

**SCHEDULE OF QUANTITY**

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	
Job No. :-3				Estimated Cost: -		303528.00
				Earnest Money: -		6100.00
				Time limit : -		One month.
<u>Name of work</u> : - Construction of District Treasury officer residence at Solan District Solan (HP) (SH:- C/O Building portion , Providing WS & SI . Rain harvesting tank & site development) (SW:- P/L reinforced cement concrete in plinth beam and stair case)						
1	Providing and laying cement concrete 1:1.5:3 (one cement isto one point five Sand isto three graded stone aggregate 20 mm (twenty millimeters) nominal size in foundation and plinth and curing complete excluding cost of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	15.410 m2	Per Cubic metre			
2	Providing tor Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per structural drawing in all floors up to all heights and levels, direction of Engineer-in-Charge and as per HP.PWD. Specification 1990 volume-I, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	2419.000 -	Per kilopgrame			
Total :-						
Total in Words						

Total in Words

T/S No. 29 for the 2022-23.

Sr. No. 50 for the year 2022-23.

  
 Executive Engineer  
 B&R Division, HP.PWD, Solan.

**SCHEDULE OF QUANTITY**

SL. No.		Description of work	Qty.	Unit	RATE In		AMOUNT
		Job No. :-			Figures	Words	Rs.
						Estimated Cost: -	342708.00
						Earnest Money: -	6900.00
						Time limit: -	Two months.
Name of work :- Construction of District Treasury officer residence at Solan District Solan (HP) (SH:- C/O Building portion , Providing WS & SI. Rain harvesting tank & site development) (SW:- P/L reinforced cement concrete in columns, beams and roof slab in building)							
1	Providing form work with steel plates 3.15 (Three point One Five ) millimetres thick welded with angle iron in frame 30*30*5 (Thirty into Thirty into Five ) millimetres, so as to give a fair finish including centering, shuttering, strutting and propping etc. with wooden/steel battens and ballies in all heights of propping and centering below supporting floor to ceiling and removal of the same in-situ-reinforced concrete as per HP.PWD specification including carriage of all labour equipments and materials to various location of site through all modes of transportation in all leads and lifts, including all incidental charges in :-						
1.1	Foundation, footings and bases of columns etc. and mass concrete.		18.00 m2	Per Square Meter			
1.2	Columns, Pillars, Posts and struts. Square, rectangular or polygonal in plan.		79.36 m2	Per Square Meter			
1.3	Lintels, beams, plinth beams, girders, bressumers and cantilevers.		88.510 m2	Per square meter.			
1.4	Suspended floors, roofs, landings, balconies and access platform.		141.300 m2	Per square meter.			
2	Providing and laying cement concrete 1:1.5:3 (one cement isto one point five Sand isto three graded stone aggregate 20 mm (twenty milimeters) nominal size in foundation and plinth and curing complete excluding cost of form work as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.		10.030 m2	Per Cubic metre			

# SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
3	Providing for Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per structural drawing in all floors up to all heights and levels, direction of Engineer-in-Charge and as per HP.PWD. Specification 1990 volume-I, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1574.000	Per kilopgrame			
Total :-						
Total in Words						

T/S No. 30 for the 2022-23.

Sr. No. 51 for the year 2022-23.

  
Executive Engineer  
B&R Division, HP.PWD. Solan.



**SCHEDULE OF QUANTITY**

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	Rs.
Job No. :- 5				Estimated Cost: -		490359.00
				Earnest Money: -		9850.00
				Time: -		Two Month
Name of work: - Construction of Sadhupul Tharola Dhar Ki Ser via Nihara road km 0/0 to 0/250 in Solan Constituency under SCSP (SH:- C/O jeepable 2.75/5.00 mtrs wide road, CD work, Soling in km 0/0 to 0/250 & C/O 18.00 mtrs.span single lane Bridge at RD.0/250 ) (SW:- Reoval of deficiency of road in Km 0/0 to 0/180)						
1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer -in-Charge at site, according to the HP.PWD, specification and sorting out useful and un- useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site ( to be arranged by the contractor) as per satisfaction of Engineer-in -Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2064.150 m3	Per Cubic Meter			
Total :-						
Total in Words						

T/S No.15 for the 2022-23

Sr. No. 44 for the year 2022-23.

  
Executive Engineer

B&R Division, HP.PWD, Solan.

90520

**DRAFT SCHEDULE OF QUANTITY**

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	Rs.
Job No. :-					Estimated Cost: -	418946.00
					Earnest Money: -	8400.00
					Time: -	Two Months
<u>Name of work: -Construction of Sadhupul Tharola Dhar Ki Ser Via Nihara road km 0/0 to 0/250 in Solan Assembly Constituency under SCSP (SH:- C/O Jeepable 2.75/5.00 mtr wide road, CD, Soling, in km 0/0 to 0/250 &amp; C/O 18.00 mtr span single lane Bridge at RD 0/0250) (SW:- ROFD in between km. 0/0 to 0/090)</u>						
1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer -in-Charge at site, according to the HP.PWD. specification and sorting out useful and un- useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site ( to be arranged by the contractor) as per satisfaction of Engineer- in -Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required).Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	1608.160 m3	Per Cubic metre	237.56	Rupees Two Hundred & Thirty Seven - Paise Fifty Six Only	382034.00
2	Construction of embankment with approved material deposited at site form roadway cutting and excavation form drain and foundation of other structures graded and compacted to meet requirement of table 300.2.	318.540 m3	Per Cubic metre	115.88	Rupees One Hundred & Fifteen - Paise Eighty Eight	36912.00
Total :-						418946.00

**Total in Words**

**Rupees Four Lakh Eighteen Thousand Nine Hundred & Fourty Six Only**

T/S No. 12 for the 2022-23.

Sr. No. 30 for the year 2022-23.

**Draft Schedule of Quantity approved for Rs. 418946.00 only.**


Executive Engineer  
B&R Division, HP.PWD. Solan.

### **"Exigency Certificate"**

It is certified that the tenders which were invited vide this Office Niq NO.PW.SD.CB.Tender/2022-23- 1703-08 dated: 09<sup>th</sup> May, 2022 are of emergent nature of work & in public interest.

**Dated:09<sup>th</sup> May, 2022**

**Place:-Solan.**

  
**Executive Engineer,  
Solan B & R Division,  
H.P.P.W.D, Solan.**



































