

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender-NIT/2022:- 6679-86

Dated: 21-06-2022

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: - Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of work as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pr. Secy. (PW), to the Govt. of H.P. letter No.PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA: - Notice Inviting Tender.
(10 Nos. Works)

Executive Engineer,
HP.PWD., Division,
Nerchowk.

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD., Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Account Branch and Drawing Branch in this office.
Notice Board.

Executive Engineer,
HP.PWD., Division,
Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed Percentage rate tender on form "6&8" are invited by the Executive Engineer, Nerchowk, H.P.PWD. Nerchowk for the following work from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in his office on or before **30-06-2022 upto 11.30 A.M.** and will be opened on the same day at **3.00 P.M.** in the presence of interested contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:00 A.M. on 28-06-2022** and EMD should be attached during the submission of application for obtaining the tender form, without Earnest Money & Cost of tender form, application will not be accepted.


The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest should be attached with application. The offer of the tender shall be kept open for **90 days**. The Executive Engineer reserves the right to reject the tender without assigning any reason:-

| Sr. No. | Name of work | Estimated Cost (Rs.) | Earnest Money (Rs.) | Cost of Tender From (Rs.) | Time limit | Eligible Class of Contractor |
|---------|--|----------------------|---------------------|---------------------------|------------|------------------------------|
| 1. | RRD on Ratti Kalkhar road 0/0 to 10/0 (SH:-Dressing of berms and cleaning of drain etc. portion in Km. 5/0 to 10/0) Ratti Section. | 428000 | 8600 | 350 | Two Months | "C&D" |
| 2. | RRD on Ner Dhangu road Km. 0/0 to 2/300. (SH:- Diversion of Suketi Khad at RD. 2/040 to 2/176). | 377399 | 7600 | 350 | One Month | "C&D" |
| 3. | RRD on Galma Majhyali road 0/0 to 9/0 (SH:-Dressing of berms and cleaning of drain etc. portion in Km. 4/0 to 9/0 (Ratti Section) | 310880 | 6300 | 350 | Two Months | "C&D" |
| 4. | A/R & M/O Sidyani Balt via Dhanu road Km. 0/0 to 9/00 (SH:-Providing and Laying G-III for correction Layer and repair of pot holes in Km. 3/00 to 9/00). | 199700 | 4000 | 350 | One Month | "C&D" |
| 5. | Annual Repair and Maintenance of in SLBS Govt. Medical College and Hospital at Nerchowk (SH:-Providing and Fixing 15mm calcium silicate false ceiling in various floor). | 132475 | 2700 | 350 | One Month | "C&D" |
| 6. | RRD on Mandi Gagah Chail Chowk Janjahli Chhattari Rana Bag road Km. 0/0 to 16/190 (SH:-Providing and Laying WBM Grade-II in Km. 5/0 to 5/350 & 7/900 to 8/240). | 371898 | 7500 | 350 | Two Months | "C&D" |
| 7. | Balance work on Mandi Gagah Chail Chowk Janjahli Chhattari Rana Bag road Km. 0/0 to 16/190 (SH:-Repair of pot holes in various reaches in Km. 0/0 to 16/190). | 347013 | 7000 | 350 | One Month | "C&D" |
| 8. | A/R & M/O various roads under Chakkar Sub-Division HP.PWD., Nerchowk (Ratti Section) (SH:-Hiring of JCB clearing of debris drains and dressing of berms etc.) | 99750 | 2000 | 350 | One Month | "C&D" |
| 9. | A/R & M/O various roads under Chakkar Sub-Division HP.PWD., Nerchowk (Nerchowk Section) (SH:-Hiring of JCB clearing of debris drains and dressing of berms etc.) | 99750 | 2000 | 350 | One Month | "C&D" |
| 10. | A/R & M/O SLBS Govt. Medical College & Hospital Nerchowk (SH:-Providing and applying wall putty, primer, oil bound distemper and polish in 6 th floor VIP set). | 68481 | 1400 | 350 | Two Months | "C&D" |

It is certified that the above tenders i.e. Sr. No. 1 to 10 are very Urgent Nature, so may be uploaded on department website in public interest.

Note:- The Contractors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and tendered amount below 30% of the estimated cost will be summarily rejected.


Executive Engineer,
HP.PWD. Division,
Nerchowk.

Name of work:- RRD on Ratti Kalkhar road 0/0 to 10/0. (SH:- Dressing of berms and cleaning of drain etc. portion in Km.
5/0 to 10/0) (Ratti Section)

SCHEDULE OF QUANTITY

Estimated Cost:- 428000.00
Earnest Money :- 8600.00
Time :- Two Months

| S.N o | Description of Item | Quantity | Rate | | Unit | Amount |
|------------------------------------|--|----------|-----------|---------|-------------------|--------|
| | | | In figure | In word | | |
| 1 | Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC including carriage of material with in all leads and lifts as per technical specification Clause 1903 and as per the entire satisfaction and direction of Engineer-in-Charge. | 3300.00 | | | Per square Metre | |
| 2 | Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge. | 3300.00 | | | Per square Metre | |
| 3 | Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge. | 3200.00 | | | Per Running Metre | |
| <u>Quoted Percentage in Figure</u> | | | | | Total | |
| <u>Quoted Percentage in Words</u> | | | | | | |

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

2

SCHEDULE OF QUANTITY

Name of work:- RRD on Ner Dhangu road Km. 0/0 to 2/300. (SH:- Diversion of Sukeiti Khad at RD. 2/040 to 2/176)

Estimated Cost:- 377399.00
Earnest Money :- 7600.00

Time :- One Month

| S.N o | Description of item | Quantity | Rate | | Unit | Amount |
|----------|---|------------------------------------|-----------|---------|-----------------|------------------|
| | | | In figure | In word | | |
| 1 | Excavation for roadway soil using mechanically means for carrying of cut earth emankment site with a lift up to 1.5 m and lead up to 50 m as per technical specification clause 302.3 in all respect including all leads and lift of materials or as per direction of Engineer in-Charge. | 2302.62 | | | Per cubic Metre | |
| | | | | | Total | 377399.00 |
| | | <u>Quoted Percentage in Figure</u> | | | | |
| | | <u>Quoted Percentage in Words</u> | | | | |

Chg
Executive Engineer,
HPPWD Division
Nerchowk

3

SCHEDULE OF QUANTITY

Name of work:- RRD on Galma Majhyali road 0/0 to 9/0. (SH:- Dressing of berms and cleaning of drain etc. portion in Km. 4/0 to 9/0) (Ratti Section)

Estimated Cost:- 310880.00
Earnest Money :- 6300.00

Time :- Two Months

| S.N o | Description of Item | Quantity | Rate | | Unit | Amount |
|------------------------------------|--|----------|-----------|---------|-------------------|--------|
| | | | In figure | In word | | |
| 1 | Maintenance of Earthen shoulder (filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC including carriage of material with in all leads and lifts as per technical specification Clause 1903 and as per the entire satisfaction and direction of Engineer-in-Charge. | 3300.00 | | | Per square Metre | |
| 2 | Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge. | 3300.00 | | | Per square Metre | |
| 3 | Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge. | 3200.00 | | | Per Running Metre | |
| <u>Quoted Percentage in Figure</u> | | | | | Total | |
| <u>Quoted Percentage in Words</u> | | | | | | |

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

Dis

586 No (5)

NAME OF WORK :- Annual Repair and maintenance in SLBS Govt. Medical College and Hospital at Nerchowk. (SH:- Providing and Fixing 15mm calcium silicate false ceiling in various floor .)

SCHEDULE OF QUANTITY

Estimated Cost:- 132475.00
Earnest Money :- 2700.00
Time :- One Months

| S.N | Description of item | Quantity | Rate | | Unit | Amount |
|-----|---|----------|-----------|--|------------------|------------------|
| | | | In figure | In word | | |
| 1 | Providing and Fixing 15 mm (Fifteen millimetre) thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm (Five hundred ninety five into five hundred ninety five millimetre) in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising at the rate 120 (One hundred twenty) grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm (twenty four into thirty eight millimetre) made from 0.33 mm (Zero point three millimetre) thick (minimum) sheet, spaced 1200 mm (One thousand two hundred millimetre) centre to centre, and cross 'T' of size 24x28 mm (twenty four into twenty eight millimetre) made out of 0.33 mm (Zero point three millimetre) (Minimum) sheet, 1200 mm (One thousand two hundred millimetre) long spaced between main 'T' at 600 mm (Six hundred millimetre) centre to centre to form a grid of 1200x600 mm (One thousand two hundred into six hundred millimetre) and secondary cross 'T' of length 600 mm (Six hundred millimetre) and size 24 x28 mm (twenty four into twenty eight millimetre) made of 0.33 mm (Zero point three millimetre) thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm (One thousand two hundred into six hundred millimetre) panel to from grid of size 600x600 mm (six hundred into six hundred millimetre) , resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size (24x24x3000 mm (Twenty four into twenty four into three thousand millimetre) made of 0.40 mm (Zero point four zero millimetre) thick (minimum) sheet with the help of rawl plugs at 450 mm (Four hundred fifty millimetre) centre to centre with 25 mm (Twenty five millimetre) long dry wall screws at the rate 230 mm (Two hundred thirty millimetre) interval and laying 15 mm (Fifteen millimetre) thick densified edges calcium silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm (Twenty five into thirty five into one point six millimetre) fixed to ceiling with 12.5 mm (Twelve point five millimetre) dia and 50 mm (Fifty millimetre) long dash fasteners, 4 mm (Four millimetre) G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm (Eighty five into thirty into zero point eight millimetre), spaced at 1200 mm (One thousand two hundred millimetre) centre to centre along main 'T', bottom exposed with 24 mm (Twenty four millimetre) of all T sections shall be pre-painted with polyester baked paint, for all heights, as per specifications, drawings and as directed by Engineer-In-Charge complete with in all leads, lifts and carriage of material and other incidental charges. | 83.50 | 1586.53 | Rupees One Thousand Five Hundred EightySix and Paise FiftyThree Only | Per square metre | 132475.00 |
| | Total | | | | | 132475.00 |

Quoted Percentage in
Figures
Quoted Percentage in
Words

Executive Engineer,
 Nerchowk Division
 HPWD Nerchowk.

| SCHEDULE OF QUANTITY |
|--|
| Name of work:- RRD on Mandi Gagel Chailchowk Janiahli Chhattari Rana Bag road Km. 0/0 to 16/190. (SH:- Providing and laying WBM Grade-ii in Km. 5/0 to 5/350 & 7/900 to 8/240) |

| | |
|------------------|-----------|
| Estimated Cost:- | 371898.00 |
|------------------|-----------|

| | |
|------------------|---------|
| Earnest Money :- | 7500.00 |
|------------------|---------|

Time :-Two Months

Executive Engineer,
HPPWD Division
Nerchowk

| SCHEDULE OF QUANTITY | |
|----------------------|-----|
| 1 | ... |
| 2 | ... |
| 3 | ... |
| 4 | ... |
| 5 | ... |
| 6 | ... |
| 7 | ... |
| 8 | ... |
| 9 | ... |
| 10 | ... |
| 11 | ... |
| 12 | ... |
| 13 | ... |
| 14 | ... |
| 15 | ... |
| 16 | ... |
| 17 | ... |
| 18 | ... |
| 19 | ... |
| 20 | ... |
| 21 | ... |
| 22 | ... |
| 23 | ... |
| 24 | ... |
| 25 | ... |
| 26 | ... |
| 27 | ... |
| 28 | ... |
| 29 | ... |
| 30 | ... |
| 31 | ... |
| 32 | ... |
| 33 | ... |
| 34 | ... |
| 35 | ... |
| 36 | ... |
| 37 | ... |
| 38 | ... |
| 39 | ... |
| 40 | ... |
| 41 | ... |
| 42 | ... |
| 43 | ... |
| 44 | ... |
| 45 | ... |
| 46 | ... |
| 47 | ... |
| 48 | ... |
| 49 | ... |
| 50 | ... |
| 51 | ... |
| 52 | ... |
| 53 | ... |
| 54 | ... |
| 55 | ... |
| 56 | ... |
| 57 | ... |
| 58 | ... |
| 59 | ... |
| 60 | ... |
| 61 | ... |
| 62 | ... |
| 63 | ... |
| 64 | ... |
| 65 | ... |
| 66 | ... |
| 67 | ... |
| 68 | ... |
| 69 | ... |
| 70 | ... |
| 71 | ... |
| 72 | ... |
| 73 | ... |
| 74 | ... |
| 75 | ... |
| 76 | ... |
| 77 | ... |
| 78 | ... |
| 79 | ... |
| 80 | ... |
| 81 | ... |
| 82 | ... |
| 83 | ... |
| 84 | ... |
| 85 | ... |
| 86 | ... |
| 87 | ... |
| 88 | ... |
| 89 | ... |
| 90 | ... |
| 91 | ... |
| 92 | ... |
| 93 | ... |
| 94 | ... |
| 95 | ... |
| 96 | ... |
| 97 | ... |
| 98 | ... |
| 99 | ... |
| 100 | ... |

| | |
|--|--|
| Name of work:- Balance work on Mandi Gagal Chail Chowk Janjehali Chattri Rana Ka Bag Nagan road Km. 0/0 to 16/190. | |
|--|--|

(SH:- Repair of pot holes in various reaches in Km. 0/0 to 16/190),

| SCHEDULE OF QUANTITY | | | | | | |
|--|---|----------|-----------|---|----------------------------|-----------|
| Name of work:- Balance work on Mandi Gagal Chail Chowk Janjehali Chattri Rana Ka Bag Nagan road Km. 0/0 to 16/190. | | | | | Estimated Cost:- 347013.00 | |
| (SH:- Repair of pot holes in various reaches in Km. 0/0 to 16/190). | | | | | Earnest Money :- 7000.00 | |
| | | | | | Time :- One Month | |
| S.N | Description of item | Quantity | Rate | | Unit | Amount |
| | | | In figure | In word | | |
| 1 | Providing, laying, spreading and compacting stone aggregate of sizes 53mm to 22.40mm (fifty three to twenty two point four millimetres) to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty by hundred Kilo Newton) in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading-II by manual means as per technical specification Clause 405 including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge. | 49.45 | 2290.00 | Rs. Two thousand two hundred ninety and paise zero only | Per Cubic Metre | 113241.00 |
| 2 | Repairing of pot holes up to any depth and removal of loose material, trimming of sides, cleaning of surface by providing tack coat bitumen VG-10 at the rate of 0.300Kg./sqm. (Zero point three zero zero kilogrammes per squaremetre) 20mm (Twenty millimetre) thick premix carpet at the rate of 1.46kg./sqm. (One point four six kilogramme per square metre) and seal coat at the rate of 0.68kg./sqm. (Zero point six eight kilogramme per square metre) type B specification clause 1904.2, 503 and 508.1. Including carriage of material within all leads and lifts and any other incidental charges as per direction of Engineer-in-Charge. | 1198.83 | 195.00 | Rs. One hundred ninety five and paise zero only | Per Square Metre | 233772.00 |
| Total | | | | | | 347013.00 |
| Quoted Percentage in Figure | | | | | | |
| Quoted Percentage in Words | | | | | | |
| Executive Engineer, HPPWD Division Nerchowk | | | | | | |

Executive Engineer,
HPPWD Division
Nerchowk

SCHEDULE OF QUANTITY


Executive Engineer
HPPWD Division
Nerchowk.

SCHEDULE OF QUANTITY

Executive Engineer
HPPWD Division
Nerchowk.

1

SCHEDULE OF QUANTITY

NAME OF WORK :- A/R & M/O SLBS Govt. Medical College & Hospital Nerchowk. (SH:- Providing and applying wall putty, primer,oil bound distemper and polish in 6th floor VIP set.)

| | |
|------------------|----------|
| Estimated Cost:- | 68481.00 |
|------------------|----------|

| | |
|------------------|---------|
| Earnest Money :- | 1400.00 |
|------------------|---------|

Time :- Two Months

[illegible]