

email

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-NHD-GA-TENDER/2022-23

1775-77

Dated: 06/06/2022

To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla-2

Subject:-

Publication of Notice Inviting Tenders.

Dear Sir,

Enclosed please find herewith the tender Notice for work as given in the Notice inviting Tender for Uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of HP letter No. PBW(BA9(3)1/2020 dated Shimla-2 16th July 2021 as the work mentioned in the tender notice are urgent in nature and public interest being the visit of Hon'ble President of India and Hon,ble Prime Minister of India on dated 10-06-2022 and 16-06-2022)

Executive Engineer,
National Highway Division,
HP PWD Hamirpur.

Copy to the Superintending Engineer National Highway Circle HPPWD
Shahpur for information please.

Copy to Computer Cell O/O Executive Engineer (IT Cell), Nigam Vihar
Shimla-2 for information and necessary action please.

Executive Engineer,
National Highway Division,
HP, PWD Hamirpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed Tenders on item rate basis are hereby invited on behalf of Governor of H.P. by **Executive Engineer, NH Division, HPPWD, Hamirpur (H.P)** from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on or before **10-06-2022 upto 10.30 A.M** and shall be opened on the same day at **11:00 A.M.** in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received upto **9-06-2022 upto 12.00 Noon** on cash payment (Non-Refundable) and tender document will be issued on the same day from **2.30 P.M. to 5:00 P.M.** If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.

SN	Name of work	Estimated cost	Earnest money	Time allowed	Cost of form	Form No
1	A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH-503 (SH:- Providing and laying Bituminous Concrete in Km. 8/600 to 9/100)	498009.00	10000.00	Five Days	350/-	6&8
2	A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH-503 (SH:- Providing and laying Bituminous Concrete in Km. 9/200 to 9/600)	497068.00	10000.00	Five Days	350/-	6&8
3	A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH-503 (SH:- Providing and laying Bituminous Concrete in Km. 9/900 to 10/300)	498928.00	10000.00	Five Days	350/-	6&8
4	A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH-503 (SH:- Providing and laying Bituminous Concrete in Km. 10/450 to 10/900)	498668.00	10000.00	Five Days	350/-	6&8
5	A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH-503 (SH:- Providing and laying Bituminous Concrete in Km. 10/950 to 11/500)	499226.00	10000.00	Five Days	350/-	6&8
6	A/R & M/O on Una-Basoli Barsar-Bhota-Road Km. 0/0 to 70/0 (NH-503A) (SH:-Repair of Rain Shelter at Salouni)	110000.00	2500.00	One Month	350/-	6&8

Draft notice inviting/ specification special conditions can be seen in this office on any working day between **11:00 AM to 4:00 PM** ambiguous/ Telegraphic conditional tenders by fax shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. All the application must accompanied with the Earnest Money in the shape of call at deposit/ N.S.C. purchased from any post office in H.P/FDR from any nationalized bank duly pledged in favour of Executive Engineer. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS:- The following document are required to be attached with the application:-

- 1 A copy of valid enlistment and renewal certificate.
- 2 A copy of GST

- 2/2
- 3 Any other information as desired by the Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the contractor/ firm, is found false at any stage the tender is liable to be rejected and action taken against contractor/ firm.
 - 4 Copy of Pan Card.

Executive Engineer,
NH Division, HPPWD
Hamirpur.

DATED: -

NO.PW-NHD-HMR-GA-TENDER/2022-23


COPY FORWARDED TO THE FOLOWING:

- 1 The Engineer-in-Chief, HPPWD, Shimla-I
- 2 The Chief Engineer (NH), HPPWD, Shimla-I.
- 3 All the Superintending Engineer, NH /B&R in HP.
- 4 The D.C Hamirpur District Kangra at Dharamshala.
- 5 The D.C Hamirpur District Hamirpur.
- 6 All the Executive Engineer, NH/B&R in HP.
- 7 The Sub-Divisional Officer (Civil) Hamirpur Hamirpur District Hamirpur .
- 8 All the Assistant Engineer, NH/B&R in HP.
- 9 The B.D.O. Hamirpur District Hamirpur.
- 10 The Executive Officer, Muncipal Committee Hamirpur
- 11 Secretary Zila Parishad Hamirpur
- 12 All the Contractors/ Suppliers working under HPPWD Hamirpur.
- 13 All the Head of Branches of this office.
- 14 Notice Board

Executive Engineer,
NH Division, HPPWD
Hamirpur.

Certificate

Certified that the tenders called vide this office letter No. NO.PW-NHD-HMR-GA-TENDER/2022-23 1733-74 DATED: - 06-06-2022 are of emergent nature and public interest being the visit of Hon'ble President of India and Hon,ble Prime Minister of India on dated 10-06-2022 and 16-06-2022 respectively.


Executive Engineer,
NH Division, HPPWD
Hamirpur

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 499226.00
 Earnest Money:- Rs. 10000.00
 Time:- Five Days

Name of work :- A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH- 503 (SH:- Providing and laying Bituminous Concrete in Km. 10/950 to 11/500)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and applying tack coat with Bitumen emulsion (RS-1) grade conforming to IS : 8887 using emulsion distributor at the rate of 0.20 to 0.25 Kg per sqm (zero point twenty five)Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per technical specification clause 503 including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	1438.690			Per square meter	
2	Providing and laying 30mm thick (thirty millimetre) bituminous concrete with 100-120 (Hundred-hundred one twenty) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with bituminous binder VG-30 @ minimum 5.5% (Five point five percent) by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification 507 (5th revision). Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job.including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	43.1607			Per Cubic meter	
G.Total						



Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 498009.00
 Earnest Money:- Rs. 10000.00
 Time: - Five Days

Name of work :-A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH- 503 (SH:- Providing and laying Bituminous Concrete in Km. 8/600 to 9/100)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and applying tack coat with Bitumen emulsion (RS-1) grade conforming to IS : 8887 using emulsion distributor at the rate of 0.20 to 0.25 Kg per sqm (zero point twenty to zero point twenty five)Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per technical specification clause 503 including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	1435.19			Per square meter	
2	Providing and laying 30mm thick (thirty millimetre) bituminous concrete with 100-120 (Hundred-hundred one twenty) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with bituminous binder VG-30 @ minimum 5.5% (Five point five percent) by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification 507 (5th revision). Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job.including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	43.0556			Per Cubic meter	
G.Total						


 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 497068.00
 Earnest Money:- Rs. 10000.00
 Time:- Five Days

Name of work :-A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH- 503 (SH):- Providing and laying Bituminous Concrete in Km. 9/200 to 9/600)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and applying tack coat with Bitumen emulsion (RS-1) grade conforming to IS : 8887 using emulsion distributor at the rate of 0.20 to 0.25 Kg per sqm (zero point twenty to zero point twenty five)Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per technical specification clause 503 including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	1432.474			Per square meter	
2	Providing and laying 30mm thick (thirty millimetre) bituminous concrete with 100-120 (Hundred-hundred one twenty) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with bituminous binder VG-30 @ minimum 5.5% (Five point five percent) by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification 507 (5th revision). Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job.including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	42.9742			Per Cubic meter	
G.Total						

Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 498928.00
 Earnest Money:- Rs. 10000.00
 Time: - Five Days

Name of work :- A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH- 503 (SH:- Providing and laying Bituminous Concrete in Km. 9/900 to 10/300)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and applying tack coat with Bitumen emulsion (RS-1) grade conforming to IS : 8887 using emulsion distributor at the rate of 0.20 to 0.25 Kg per sqm (zero point twenty to zero point twenty five)Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per technical specification clause 503 including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	1437.833			Per square meter	
2	Providing and laying 30mm thick (thirty millimetre) bituminous concrete with 100-120 (Hundred-hundred one twenty) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with bituminous binder VG-30 @ minimum 5.5% (Five point five percent) by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification 507 (5th revision). Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job.including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	43.1350			Per Cubic meter	
G.Total						

Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 498668.00
Earnest Money:- Rs. 10000.00
Time: - Five Days

Name of work :-A/R & M/O on Mubarikpur Dehra Gopipur-Ranital-Kangra-Matour-Dharamshala-Mcleodganj Road NH- 503 (SH:- Providing and laying Bituminous Concrete in Km. 10/450 to 10/900)

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and applying tack coat with Bitumen emulsion (RS-1) grade conforming to IS : 8887 using emulsion distributor at the rate of 0.20 to 0.25 Kg per sqm (zero point twenty five)Kg per sqm on the prepared bituminous surface cleaned with Hydraulic broom as per technical specification clause 503 including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	1437.085		Rupees Seventeen and paise nil only	Per square meter	
2	Providing and laying 30mm thick (thirty millimetre) bituminous concrete with 100-120 (Hundred-hundred one twenty) TPH batch type hot mix plant producing an average output of 75 tonne per hour using crushed stone aggregates of specified grading-II, premixed with bituminous binder VG-30 @ minimum 5.5% (Five point five percent) by weight of total mix material and filler, as per job mix formula transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment , rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification 507 (5th revision). Item to include all materials, labour, machinery/equipments and incidental charges required to complete the job.including carriage of materials upto all leads and lifts as per direction of the Engineer-in-charge.	43.1126		Rupees Eleven thousand and paise nil only	Per Cubic meter	
G.Total						

Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs. 110000.00
Earnest Money:- Rs. 2500.00
Time:- One Month

Name of Work:- A/R & M/O on Una-Basoli Barsar-Bhota-Road Km. 0/0 to 70/0 (NH-503A) (SH:-Repair of Rain Shelter at Salouni)					
Sr. No.	Description of item	Qty.	Rate		Amount
			In Figure	In Words	
1	Providing fixing 150 mm dia M.S pipe in Pillar post including welding, joists, hoisting . complete including entire carriage of materials, taxes within all leads and lifts and as per the direction of Engineer-in-charge.	100.00			Per Kg
2	Steel work welded in built up sections trusses and framed work i/c cutting hoisting fixing in position and applying a priming coat of read lead paint in grating framed guard bars, railings bracket etc and similar work as per the direction of Engineer in charge and carriage of materials within all leads and lifts and other incidentals complete as per the direction of Engineer-in-Charge.	310.00			Per Kg
3	Providing and fixing Eversest fibre cement sheet ceiling fire resistant ,moisture resistant size 610x610x6mm of zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to tack coat of polyester of 5 microns over 5 microns primer coating including fixing with pepainted iron J or L hooks, bolts and nuts 6mm dia and pepainted G.I. limpet and bitumen washers complete with all accessories complete including entire carriage of materials, taxes within all leads and lifts and as per the direction of Engineer-in-charge.	16.357			Per Square meter
4	Providing and fixing Eversest fibre cement sheet ceiling fire resistant ,moisture resistant size 610x610x6mm of approved quality with butt jointing and stainless screws (frame work and cover fillets to be measured and paid for separately)(AR) complete including entire carriage of materials, taxes within all leads and lifts and as per the direction of Engineer-in-charge.	25.00			Per Square meter
5	2 nd class half brick masonry in common burnt clay building bricks in foundation and plinth C.M1:4 (One cement: four sand) up to floor all level including carriage of material complete including entire carriage of materials, taxes within all leads and lifts and as per the direction of Engineer-in-charge.	3.00			Per Cubic meter
6	15mm cement plaster in single coat on the rough side of bricks/conc. Stone walls for interior plastering up to floor level i/c arrises internal rounded angles chamfers and or rounded angles not exceeding 80mm in girth and finished and smooth. Cement mortar 1:5 (one cement: five sand)complete including entire carriage of materials, taxes within all leads and lifts and as per the direction of Engineer-in-charge.	35.00			Per Square meter
7	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushing to give and even shade includes cleaning the surfaces of all dirt, dust and other foreign matter with enamel white paint complete including entire carriage of materials, taxes within all leads and lifts and as per the direction of Engineer-in-charge.	45.00			Per Square meter
8	Distempering with dry distemper of approved brand and manufacture (Two coats) and of required shade on undecorated wall surface to given an even shade over and including priper coat of whitening after thorough complete including entire carriage of materials, taxes within all leads and lifts and as per the direction of Engineer-in-charge.	35.00			Per Square meter
Total					

Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur