

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Short terms tenders on form 6&8 are hereby invited by the Executive Engineer Bangana Division HP.PWD Bangana on behalf of the Governor of H.P. for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

5. Date of receipt of applications for the tender
Form a/w requisite documents: - 04.07.2022 upto 5.00 PM.
6. Date of issue /sale of tender forms against
Cash payment (Non-refundable):- 05.07.2022 upto 4.00 PM.
7. Date of receipt of tenders: - 06.07.2022 upto 10.30 AM.
8. Date of opening of tenders: - 06.07.2022 at 11.00 AM.

Sr.No.	Name of Work	Estimated Cost	EMD	Time Limit	Cost of Tender	Eligible class of Contractor
1	C/o road to village Balh Rehre(SH:- C/o B/wall in km. 0/120 to 0/405 & v-shape drain in km. 0/690 to 0/720 & 900mm dia hume pipe culvert at RD 1/250).	497442	10000	Two months	350/-	Class-A to D
2	A/R & M/O Nari Dadhial Badsala Dahwara road (SH:- P/L edge line with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface & cat eyes in km. 0/0 to 2/00 & Chalola Nangal Salangri Sanjot road in km. 1/0 to 2/0).	446216	9000	Two months	350/-	Class-D
3	A/R & M/O EE office at bangana(SH:- Providing and installation of A.C.,Chairs & Tables).	97500	2000	Two months	350/-	Class-D
4	A/R & M/O Charara Alroo via Baggi road (SH:- P/L edge line with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface & cat eyes in km. 1/0 to 2/00 & 2/0 to 3/0).	316432	6400	Two months	350/-	Class-D


The Earnest money in the shape of National Saving certificate/Time deposit/Saving account of any post office or FDR of Nationalised Bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.

The Copy of valid enlistment, GST Registration No., Income Tax PAN No & EPF No. must be attached with application.

SPECIAL CONDITION:-

1. The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which may be attached with their applications. (The proof of ownership of machinery/legal tie up arrangement).
2. The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.
3. The conditional/ambiguous/telegraphic tenders or tender by fax shall not entertained/considered in any case.


Executive Engineer
Bangana Division
HPPWD, Bangana.


No.PW/BGN/CB/T-1/2022-23-

3286-3305

dated 24/6/2022


Cop forwarded to the following for information and necessary action:-

1. The Engineer-in-Chief HPPWD, Nirman Bhawan Shimla.
2. All the Chief Engineer in HPPWD.
3. The Superintending Engineer, 15th Circle, HPPWD., Una.
4. All the Assistant Engineer, working under this Division.
5. The B.D.O. Bangana
6. Accounts Branch.
7. Drawing Branch.
8. Various Contractors working under this Division
9. Notice Board.


Executive Engineer,
Bangana Division,
HPPWD, Bangana.

Certificate

Certified that the tenders called vide this office letter No. PW/BGN/CB/T-1/2022-23-3286-3305 dated 22.06.2022 is emergent nature and in public interest.



Executive Engineer,
HPPWD Division
Bangana.

Schedule of Quantity
Name of Work:- C/O Link road to Village Balh Rahere (SH:- C/O Breast wall in km. 0/120 to 0/405 & V-Shape
Drain in km. 0/690 to 0/720 & 900 mm dia Hume pipe culvert at RD. 1/250)

Estimated Cost: ` 497442.00
 Earnest Money: ` 10000.00
 Time Limit: Two Month

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge, including carriage of slush materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	166.01	Per cubic metre			
2	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight crushed crushed stone aggregate 40mm nominal size mechanically mixed and curing complete excluding cost of form work in foundation and plinth, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	9.82	Per cubic metre			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth as per drawing and technical specification clause 800, & 1200 for nominal mix 1: 5: 10 (one cement: five sand : Ten graded crushed stone aggregate 40mm (forty millimeters) nominal size and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths and the cost of form work in retaining walls, breast walls etcetra as per the direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	114.60	Per cubic metre			
4	Providing and laying cement concrete work 1:3:6 (one cement: three sand:six graded stone aggregate) 40mm (forty millimetre) nominal size in open foundation mechanically mixed and vibrated including curing complete, including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge, including carriage of material within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	64.13	Per cubic metre			

Sr. No.	Description of work	No. or Qty.	Unit	RATE in Figures and words		AMOUNT Rs. P
				Figures	Words	
5	Providing and laying (to level or slope) 900mm dia (Nine hundred millimeter) diametre reinforced cement concrete heavy duty non pressure pipes IS Class NP-2 for culverts on first class bedding or granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications clause 1106, including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	7.50	Per Running metre			
6	Providing weep holes in stone masonry, plain/ reinforced concrete abutment, wing walls, return walls, retaining walls with 100mm (one hundred millimeter) diameters, PVC pipe extending through the full width of the structures with a slope of 1 (one) vertical : 20 (twenty horizontal) toward drawing face complete as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	38.00	Each			
7	Back filling with granular material behind return wall, abutment, wing wall and retaining walls complete as per drawing and technical specifications clause 1204.3.8 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	8.20	Per cubic metre			
Total in Figures						


 Executive Engineer
 Bangana Divn., H.P.P.W.E
 BANGANA

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O Nari Dadhial Badsala Dathwara road (SH: Providing and Laying hot Applied thermoplastic compound in Km 0/000 to 2/000 & Chalola Nangal Slangri Sanjhot road km 1/000 to 2/000)							Estimated Cost:	446216.00
							Earnest Money:	9000.00
							Time Limit:	Two month
Sr. No.	Description of work	No.or Qty.	Unit	RATE in Figures and words		AMOUN		
				Figures	Words	Rs.		
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimetre)thick including reflectorising glass beads @ 250 gms (at the rate of two hundred fifty gram per square metre)per sqm area, thickness of 2.5 mm(two point five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes.including carriage of material within all leads and lifts The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	716.00	Per Square metre					
2	Providing and fixing Dual Direction Reflective Cat Eye with Double Barrel Sanks of Impact resistant ABS PLASTIC STUD 100X90X16MM Ultea Violet , resistant Yellow/ Red Colour havinf micro persmatic / Cube corner reflectors suitable for fixing with epoxy / Bitumen adseive make M-3 , including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Each					
Total in Figures								


Executive Engineer
 Bangana Division
 P.P.W.D. Bangana

SCHEDULE OF QUANTITY

Name of Work:- A/R & M/O E.E. Office at Bangana Tehsil Bangana Distt. Una (HP) (SH:- Providing and Installation of Air Conditioner, Chairs & Tables)

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Cost: ` 97500.00	
				Earnest Money: ` 2000.00	Time Limit:
1	Providing and installation of 3star inverti cool AC of LG, Blue Star, Voltas or its equerlant , variable Capacity setting , Anti viral Dust Filter Cool Even at 52 C , rapid cooling 18 C in 45 Seconds , smart 4 way swing ,wi Fi ready , Golden condensor , DU0 compressor ,E 55Low gas detection , D, intelligent diagnosis contigtrion complete including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1	Each	RATE in Figures and words	
				Figures	Words
2	Supplying and instalation of Delux modal revolving chair including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1	Each		
3	Supplying and instalation of revolving chair including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2	Each		
4	Supplying and instalation of office table with drawer including carriage of material with in all leads and lifts and other incidentals .The rate includes octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5	Each		
Total in Figures					

Executive Engineer
Bangana Division
P.P.W.D. Bangana

Schedule of Quantity

Name of work: A/R & M/O Charara Arloo via Baggi road (SH: (SH:P/L Edge Line with hot applied thermoplastic compound with reflectorising glass beads on bitumenious surface and Cat Eyes in Km 1/000 to 2/000 & 2/000 to 3/000)

Estimated Cost: ` 316432.00
Earnest Money: ` 6400.00
Time Limit: Two Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No.or Qty.	Unit	RATE in Figures and words		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying of hot applied thermoplastic compound 2.5 mm(two decimal five millimetre) thick including reflectorising glass beads @ 250 gms (two hundred fifty kilogramme) per square metre area, thickness of 2.5 mm (two decimal five millimetre) is exclusive of surface applied glass beads as per IRC:35 .The finished surface to be level, uniform and free from streaks and holes. as per the direction of Engineer-in- Charge including carriage of materials within all leads , lifts and other incidental . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	432.00 Square metre	Per Square metre			
2	Providing and fixing Dual Direction Reflective Cat Eye with Double Barrial Sanks of Impact resistant ABS PLASTIC STUD 100X90X16MM Ultea Voilet , resistant Yellow/ Red Colour havinf micro persnatic / Cube corner reflectors suitable for fixing with epoxy / Bitumen adseive make M-3 , including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	800.00 Each	Each			
Total in Figures						


Executive Engineer
Bangana Divn.H.P.P.W.D
BANGANA