



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand
Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in

Phone No.-01904-255140

Fax No. 01904-255740

Dated 01-06-2022

No.-PW/OSDN/ Tender-NIT/2021-22 2968-58
To

The Executive Engineer (IT Cell),
Nigam Bihar, H.P. Shimla-2.

Subject:-

Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)/A(3) 1/2020 Dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

DA/ Notice inviting tender/Schedule of Quantity


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand

Copy forwarded with its enclosure for information to :-

1. The Superintending Engineer, 11th Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.


Executive Engineer,
Outer Seraj Division,
HP.PWD, Nirmand



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division,
HP.PWD. Nirmand

Web: www.hppwd.gov.in, Email: ee-nir-hp@nic.in



Phone No.-01904-255140

Fax No. 01904-255740


NOTICE INVITING TENDER

Scaled item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on **16.06.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on **15.06.2022** between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **15.06.2022** between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money	Time	Cost of tender form Rs.
1	A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 (SH:- Providing and Supplying of premixed materials for premixed carpet and seal coat at site for patch work between km. 13/00 to 20/00)	374340.00	8000.00	One month	350/-
2	A/R & M/O road from Jn. of Luhri Dalash Chowai Khanag road to Jn. of Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 32/00 (SH:-Providing and Supplying of premixed materials for premixed carpet and seal coat at site for patch work between km. 16/00 to 26/00)	353037.00	8000.00	One month	350/-

3	A/R & M/O various roads under Brow Sub-Division (SH:-Providing and Supplying of premixed materials for premixed carpet and seal coat at site for patch work at various roads)	258156.00	6000.00	One month	350/-
4	Construction of road from Kalog to Tirmidhar km. 0/00 to 1/420 (SH:- Construction of retaining walls at RD. 0/0 to 0/010) under SCSP.	477235.00	10000.00	Three Month	350/-
5	Construction of road from Kalog to Tirmidhar km. 0/00 to 1/420 (SH:- Construction of retaining walls at RD. 0/010 to 0/020) under SCSP.	479578.00	10000.00	Three Month	350/-
6	Improvement of identified black spots by providing corrective measures on road from Jn. Of LDCK road to Jn. Of Nirmand Arsu Sarahan road km. 0/00 to 32/00 (SH:- Supplying and stacking of high intensity engineering grade prismatic sheeting.)	495000.00	10000.00	One month	350/-
7	Construction of link road from Averi to Bayal Km. 0/000 to 8/700 (SH:- Providing and erecting PCC protection for Kuhal portion between 6/197.90 to 6/207.90 and causeway at RD 5/621.) under Deposit work	261521.00	6000.00	Three Month	350/-

It is certified that the above tenders i.e Sr. No 1 to 7 are very urgent nature, So may be uploaded on department website in public interest


 Executive Engineer
 Outer Seraj Division
 H.P PWD, Nirmand
 on behalf of Governor of Himachal Pradesh

①

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Name of work:-A/R & M/O Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 34/00 (SH:-			Estimated cost:- Rs. 374340.00 only			
Providing and Supplying of premixed materials for premixed carpet and seal coat at site for			Earnest Money Rs. 8000.00 only			
patch work between km. 13/00 to 20/00)			Time:- One month			
Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing and supplying of premixed material at site of work for open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm to 5.6 mm aggregates using penetration grade bitumen VG-10 including mixing in a suitable plant, as per Technical Specification Clause 508 including cost of grit and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge. (The bitumen will be supplied by the department free of cost at Plant site).	75.00			Per Cubic Metre	
2	Providing and supplying of premixed material at site of work for seal coat, Type B as per Technical Specification Clause 510 including cost of crushed sand defined as passing 2.36 mm sieve and retained on 180 micron sieve and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge. (The bitumen will be supplied by the department free of cost at plant site).	17.00			Per Cubic Metre	
Total						


 Executive Engineer
 Outer Seraj Division
 HPPWD, Nirmand

2

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O road from Jn. of Luhri Dalash Chowai Khanag road to Jn. of Wazir Bowali Nirmand Arsu Sarahan road km. 0/00 to 32/00 (SH:-Providing and Supplying of premixed materials for premixed carpet and seal coat at site for patch work between km. 16/00 to 26/00)

Estimated cost:- Rs. 353037.00 only
Earnest Money Rs. 8000.00 only
Time:- One month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing and supplying of premixed material at site of work for open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm to 5.6 mm aggregates using penetration grade bitumen VG-10 including mixing in a suitable plant, as per Technical Specification Clause 508 including cost of grit and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge. (The bitumen will be supplied by the department free of cost at Plant site).	70.00			Per Cubic Metre	
2	Providing and supplying of premixed material at site of work for seal coat, Type B as per Technical Specification Clause 510 including cost of crushed sand defined as passing 2.36 mm sieve and retained on 180 micron sieve and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge. (The bitumen will be supplied by the department free of cost at plant site).	17.00			Per Cubic Metre	
Total						


Executive Engineer
Outer Saraj Division
HIPWD Nirmand

3

SCHEDULE OF QUANTITY						
Name of work -A/R & M/O virius roads under Brow Sub-Division (SH:-Providing and Supplying of premixed materials for premixed carpet and seal coat at site for patch work at various roads)				Estimated cost:- Rs. 258156.00 only		
				Earnest Money Rs. 6000.00 only		
				Time:- One month		
Sr. No.	Description of items.	Quantity	Figure	Rates Words	Unit	Amount
1	2	3	4	5	6	7
1	Providing and supplying of premixed material at site of work for open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm to 5.6 mm aggregates using penetration grade bitumen VG-10 including mixing in a suitable plant, as per Technical Specification Clause 508 including cost of grit and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge. (The bitumen will be supplied by the department free of cost at Plant site).	50.00			Per Cubic Metre	
2	Providing and supplying of premixed material at site of work for seal coat, Type B as per Technical Specification Clause 510 including cost of crushed sand defined as passing 2.36 mm sieve and retained on 180 micron sieve and haulage within all leads and lifts of material to site of work with all admissible taxes including GST as per the direction of Engineer-in-charge. (The bitumen will be supplied by the department free of cost at plant site).	14.00			Per Cubic Metre	
Total						


 Executive Engineer
 Outer Sarai Division
 HPPWD, Patna

47

Name of Work: Construction of road from Kalog to Tirmidhar km. 0/00 to 1/420 (SH:- Construction of retaining walls at RD. 0/00 to 0/010) under SCSP.

Schedule of quantity

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-	
				Earnest Money	477235.00
				Time	10000.00
				Figures	Words
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	8.80	Cubic Metre		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	29.00	Cubic Metre		
3	Providing and Laying plain cement concrete 1:6:12 (one cement: six sand: twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.90	Cubic Metre		
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement: six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	94.40	Cubic Metre		
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	17.60	Cubic Metre		
Total in Figures					


 Executive Engineer
 Outer Sargi Division
 HPWD, Tirmidhar


Signature of Tenderer with seal

5

Schedule of quantity

Name of Work: Construction of road from Kalog to Tirmidhar km. 0/00 to 1/420 (SH:- Construction of retaining walls at RD. 0/010 to 0/020) under SCSP.

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				RATE		AMOUNT
				Figures	Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	8.80	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	29.00	Cubic Metre			
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	7.90	Cubic Metre			
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	94.40	Cubic Metre			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	19.80	Cubic Metre			
Total in Figures						


 Executive Engineer
 Outer Sagar Division
 HPPWOD, Tumkur

Schedule of Quantity

Name of work: - Improvement of identified black spots by providing corrective measures on road from Jn. Of LDCK road to Jn. Of Nimmand Arsu
 Sarahan road km. 0/00 to 32/00 (SH:-Supplying and stacking of high intensity engineering grade prismatic sheeting.)

Estimated cost:- 495000.00

Earnest money:- 10000.00

Time:- One Month

Sr. No	Sub-Head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Providing and supplying high intensity engineering grade prismatic sheeting on the front side of existing W-metal beam crash barrier of size 300x450mm (Three hundred into four hundred fifty milimetre) in yellow and white colour at site within all leads and lifts as per direction of Engineer-In Charge complete in all respect.	440.00	Per Running Metre			


 Executive Engineer,
 Outer Seraj Division,
 HP.PWD/Nirmand.

premixed materials for premixed carpet and seal coat at

7

Schedule of quantity

Name of Work: Construction of link road from Averi to Bayal Km. 0/000 to 8/700 (SH:- Providing and erecting PCC protection for Kuhal portion between 6/197.90 to 6/207.90 and causeway at RD 5/621.) under Deposit work

Estimated cost:- 261521.00
Earnest money:-6000.00
Time:- Three months

Sl. No.	Description of work	Qty.	Unit	RATE		AMOUNT
				Figures	Words	
1	Providing and laying concrete Mechanically mixed and vibrated PCC M-15(Fifteen) nominal mix 1:2.5:5 (One cement: Two and half sand :five graded stone 20 mm(Twenty millimeters) nominal size for plain concert in drain or similar work complete as per drawing and technical specification for rural roads August 2004, Clause 802.803,1202 and 1203.and curing complete including the cost of form work including hauling of materials in all leads and lifts and as per entire satisfaction of Engineer-in-	26.73	Cubic Metre			
2	Providing and laying concrete for plain/ reinforced concrete grade M-10 (ten) nominal mix 1:3:6 (One cement: three sand : six graded stone aggregate 20 mm (twenty millimetre) nominal size in open foundation complete as per drawing and technical Specification Clause 802, 803, 1202 and 1203 and as per directions of the Engineer-In-Charge including curing and carriage of materials through all modes of transportation within all leads and lifts and other incidentals.	7.50	Cubic Metre			
3	Providing laying concrete Mechanically mixed and vibrated PCC M-30 nominal mix 1:1½:3 (one cement: one point five sand : three graded stone aggregate 20 mm (Twenty millimeter) nominal size for plain concrete in open foundations and plinths or similar works complete as per drawings and technical specification rural roads August 2004 Clauses 800, 1205.4 and 1205. and curing complete including the cost of form work including hauling of materials in all leads and lifts as per the Engineer-in-Charge.	5.00	Cubic Metre			
Total in Figures						

Signature of Tenderer with seal

Executive Engineer
Outer Section Division
HPFWD, Miranand