

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-MDI(Padhar)E-Tender-NIT/2022-23- 3985-87

Dated:- 13/06/2022

To

The Executive Engineer (IT Cell),
Nirman Bhawan ,Nigam Vihar, Shimla-2.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **23.06.2022 up to 12:00 Noon** and the same shall be opened on the same day **at 12:30 P.M.** in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on **22.06.2022 upto 01:00 P.M.**

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of damages caused due to laying of OFC by Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km 0/0 to 17/810. (SH:- Repair of pot holes in Km 5/0 to 12/0)	3,10,221/-	6,200/-	350/-	One month
2	Restoration of damages caused due to laying of OFC by Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km 0/0 to 17/810. (SH:- Repair of pot holes in Km 12/0 to 17/810)	3,26,930/-	6,500/-	350/-	One month
3	Annual repair and maintenance of Kufri Nihon road Km 0/0 to 5/500. (SH:- Repair of pot holes in Km 0/0 to 1/0)	3,54,434/-	7,100/-	350/-	One month
4	Annual repair and maintenance of Drang Basahi road Km 0/0 to 22/0. (SH:- Repair of pot holes in Km 10/0 to 11/300)	3,61,512/-	7,200/-	350/-	One month
5	Annual repair and maintenance of Kufri Khil Lohara road Km 0/0 to 2/800. (SH:- Repair of pot holes in Km 0/0 to 2/800)	3,57,558/-	7,200/-	350/-	One month
6	Construction of Science Laboratory of Govt. Senior Secondary School at Sudhar District Mandi (H.P.) (SH:- Site development)	1,97,294/-	3,900/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The intending Contractors are requested to see the site of the work before submitting the tender.

5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.



Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh

Schedule of Quantity

Estimated Cost:- Rs. 310221.00
 Earnest Money:- Rs. 6200.00
 Time:- One month

Name of work:- Restoration of damages caused due to laying of OFC by Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km. 0/0 to 17/810.
Sub Head:- Repair of pot holes in Km. 5/0 to 12/0.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	10.70 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1427.04 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.I
 H.P.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 326930.00
 Earnest Money:- Rs. 6500.00
 Time:- One month

Name of work:- Restoration of damages caused due to laying of OFC by Indian Army NFS Project, Northern Command Composite on Neri Duhki Behindhar Gharan road Km. 0/0 to 17/810.
Sub Head:- Repair of pot holes in Km. 12/0 to 17/810.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	11.28 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1503.85 Sqm.			Per Square metre	
					Total:-	

Executive Engineer,
 Mandi Division No.I
 H.P.PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 354434.00
 Earnest Money:- Rs. 7100.00
 Time:- One month

Name of work:- Annual repair and maintenance of Kufri Nihon road Km. 0/0 to 5/500.
Sub Head:- Repair of pot holes in Km. 0/0 to 1/0.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	16.35 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1307.65 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P. PWD. at Padhar

Schedule of Quantity

Estimated Cost:- Rs. 361512.00
 Earnest Money:- Rs. 7200.00
 Time:- One month

Name of work:- Annual repair and maintenance of Drang Basahi road Km. 0/0 to 22/0.
Sub Head:- Repair of pot holes in Km. 10/0 to 11/300.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	41.63 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	976.10 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 HP-PWD. at Padhar


Schedule of Quantity

Estimated Cost:- Rs. 357558.00
 Earnest Money:- Rs. 7200.00
 Time:- One month

Name of work:- Annual repair and maintenance of Kufri Khil Lohara road Km. 0/0 to 2/800

Sub Head:- Repair of pot holes in Km. 0/0 to 2/800.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing, laying, spreading and compacting stone aggregates by mechanical means of 53mm to 22.4mm (fifty three millimetre to twenty two point four millimetre) sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (eighty-hundred kilo newton) in stages to proper grade and camber applying and brooming, stone screening/binding materials to fillup the interstics of coarse aggregate, watering and compacting to the required density Grading-3 (three) as per Technical Specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges complete in all respect as per direction of Engineer in-Charge.	25.26 Cum.			Per cubic metre	
2	Repair of pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20mm (twenty millimetre) thick premix carpet and seal coat type-B specification Clause 1904.2, 503 and 508.1 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge. (Bitumen will be procured by the department)	1182.40 Sqm.			Per Square metre	
					Total:-	


 Executive Engineer,
 Mandi Division No.1
 H.P. PWD. at Padhar

6

Schedule of Quantity

Estimated Cost:- 197294.00
Earnest Money:- 3900.00
Time:- One month.

Name of work:- Construction of Science Laboratory of Govt. Senior Secondary School at Sudhar District Mandi (H.P.)
Sub Head:- Site development.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper and blasting work both in soft and hard rock with chiseling wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out time to the required line, grades, side slopes trimming bottoms and level as shown in the drawing as per the direction of Engineer-In-Charge at site as per technical specification clause 1603.1, 1603.2 and sorting out useful/un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un-useful materials for filling in road ways camber embankments for grades improvements and disposal of all un-useful materials to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling fine dressing and carriage of all labour machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and or labour if required all useful materials such as stones, shingles, aggregates, sand slates shall be sorted out and stacked along road side. Any loss to the public/private property during the course of execution shall be absolute responsibility of the contractor which shall be duly compensated by him in all cases.	1052.28 Cum.			Per cubic metre	
2	Less credit for excavated rock found suitable for use, the recovery of useful rock shall be done on pro-rata basis in each running bill for item No.1	10.52 Cum.	600.00	Rupees six hundred and paise nil only	Per cubic metre	-6312.00
				Total:-		

Executive Engineer,
Mandi Division No.1,
H.P.PWD. at Padhar.