


**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**



Office of the Executive Engineer, Outer Seraj Division, HP.PWD, Nirmand  
Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), Email: [ee-nir-hp@nic.in](mailto:ee-nir-hp@nic.in)

Phone No.-01904-255140  
Fax No. 01904-255740

Dated 30-05-2021

No.-PW/OSDN/ Tender-NIT/2021-22 2923-29  
To

The Executive Engineer (IT Cell),  
Nigam Bihar, H.P. Shimla-2.


**Subject:-**

**Publication of Tender Notice.**

*Jai Hind*


Enclosed please find herewith the Tender Notice of various works as given in the Tender Inviting Tender for uploading on departmental website as per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh Letter No.-PBW(B)A(3) 1/2020 Dated Shimla-2 the 16<sup>th</sup> July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

**DA/ Notice inviting tender/Schedule of Quantity**

  
Executive Engineer,  
Outer Seraj Division,  
HP.PWD, Nirmand

**Copy forwarded with its enclosure for information to :-**

1. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD, Rampur Bushahr.
2. The Assistant Engineer, Sub-Division, HP.PWD, Nirmand/Brow/Neethar/Dalash/Anni.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Suptt. of C Branch.
6. Notice Board.

  
Executive Engineer,  
Outer Seraj Division,  
HP.PWD, Nirmand.






**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer, Outer Seraj Division,  
HP.PWD. Nirmand

Web: [www.hppwd.gov.in](http://www.hppwd.gov.in), Email: [ee-nir-hp@nic.in](mailto:ee-nir-hp@nic.in)



Phone No.-01904-255140  
Fax No. 01904-255740

**NOTICE INVITING TENDER**


Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Outer Seraj Division HP. PWD. Nirmand on behalf of Governor of HP. from the approved eligible contractors enlisted in HP.PWD (B&R) in appropriate class "C and D", for the following works, so as to reach this office on **13.06.2022** up to 10.30 A.M. and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application for obtaining the tender form will be received on **10.06.2022** between 10.00 A.M. to 1.00 P.M. The tender form can be had from this office against cash payment (Non-refundable) on **10.06.2022** between 2.00 AM to 5.00 PM. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Outer Seraj Division HP.PWD. Nirmand cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept open for 90 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment /renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid Copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Sr. No.	Name of work	Estimated cost (in Rupees)	Earnest Money	Time	Cost of tender form Rs.
1	M/T on Bashad to Kanda Katmore road km 0/000 to 7/600 under BASP (SH:-C/o R/Wall at RD 1/420 to 1/437)	436665.84	10000	Three Month	350/-
2	C/o Link Road to Ambika Mata temple Nirmand km 0/00 to 4/200 (SH-C/O Breast wall at RD 0/365 to 0/375)	129440.00	4000	Three Month	350/-
3	Construction of link Road from Junction of N.A.S Road to Junction of LDCK Road km 0/0 to 26/765 under MNP (SH:- C/o R/wall at RD 10/845 to 10/857)	470275.00	10000	Three Month	350/-
4	Construction of link Road from Dhanudhar to Pujarli Km 0/000 to 3/765 under Deposit (SH:- Construction of wire Crate retaining wall at RD 2/240 to 2/255)	232660.00	5000	Three Month	350/-



5	Restroation of Rain damage on Nore to Neether Road km 0/000 to 26/765 (SH:- C/O Retaning wall at RD 17/305 to 17/317 under BASP	189550.18	10000	Three Month	
6	Conastruction of link road from Dhanudhar to Pujarli km. 0/000 to 3/750 undr deposit work ( Sub Head:- Construction of R/Wall at RD. 2/367 to 2/371)	83818.00	2000.00	One month	
7	Repair and Maintenance of Parshuram Mela ground at Nirmand District Kulllu H.P. (SH:- P/L local stone flooring in Parshuram mela ground Nirmand portion stage side) under SDP deposit	417591.00	10000.00	Three months	350/-
8	Repair and Maintenance of Parshuram Mela ground at Nirmand District Kulllu H.P. (SH:- P/L local stone flooring in Parshuram mela ground Nirmand portion Parshuram kothi side) under SDP deposit	417591.00	10000.00	Three months	350/-

It is certified that the above tenders i.e Sr. No 1 to 7 are very urgent nature, So may be uploaded on department website in public interest


  
 Executive Engineer  
 Outer Seraj Division  
 H.P PWD, Nirmand  
 on behalf of Governor of Himachal Pradesh



## Schedule of quantity

Work :- M/T Bashad to Kanda Katmor road Km 0/00 to 7/600 under BASP (SH:- C/O R/wall  
1/420 to 1/437

No	Description of work	Qty.	Unit	Estimated cost:-	
				Earnest Money	10000
				Time	10000
Figures	RATE	Words	AMOUNT		
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	18.36	Cubic Metre		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	27.71	Cubic Metre		
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	84.32	Cubic Metre		
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	34	Each		
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	11.22	Cubic Metre		
Total in Figures					


  
 Executive Engineer  
 Outer Sand Division  
 HPPW&E, Miramand



## Draft Schedule of quantity

Work:- C/O link road from Ambika mata temple km 0/00 to 4/200 (SH-C/O B/Wall at 65 to 0/375)

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Figures	Earning Money	
					Time	More months
					RATE	AMOUNT
					Words	
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	15.5	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	4.1	Cubic Metre			
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 P.C.C nominal mix 1:5:10 (40mm aggregates)	25.1	Cubic Metre			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20	Each			
Total in Figures						

  
 Executive Engineer  
 Outer ~~SSJ~~ Division  
 HPPWD, Nirmam



Work :- C/O Road from Junction of N.A.S Road to Junction of LDCK km 0/0 to 26/765 under MNP  
 At :- C/O Road at RD 10/845 to 10/857

### Schedule of quantity

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Earnest Money	Tender monthly AMOUNT	
				Time	RATE	Words
			Figures			
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	17.04	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	17.04	Cubic Metre			
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	89.16	Cubic Metre			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	40	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	23.04	Cubic Metre			
Total in Figures						

Executive Engineer  
 Outer Sanitation Division  
 PWD, Noida



## Schedule of quantity

Name Of Work :- Construction of Work Link Road From Dhanudhar to Pujarli km 0/0 to 7/05 (SH-c/o create Retaining wall 2/240 to 2/255 ) under department						
Sl. No.	Description of work	Qty.	Unit	Figures	Estimated cost:-	
					Earnest Money	232660.00
					Rate	150000
					Words	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1	10.20	Per Cum			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	18.60	Per Cum			
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh ( woven diagonally ) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specification including carriage of materials in all leads and lifts and as per directions of The Engineer – in – Charge complete. (Wire crate will be supplied by the department free of cost)	81.00	Per Cum			
4	Back filling behind abutment, wing and return well complete as per drawing and technical specifications clause 1204.3.8. granular materials.	6.97	Per Cum			
Total in Figures						



## Schedule of quantity

Work :- R/R Damage Nore to Neether road km 0/00 to 26/765 under BASP (SH:- C/O R/Wall at RD  
No. 17/317

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-		
				Earnest Money		4000
				Time		Two months
				Figures	RATE Words	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	8.10	Cubic Metre			
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	12.84	Cubic Metre			
3	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) curing complete in retaining and breast walls as per drawing and technical specification including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	35.88	Cubic Metre			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	24.00	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	5.04	Cubic Metre			
Total in Figures						

Executive Engineer  
Outer Setai Division  
UPPWID, Himmatnagar




6

**Schedule of quantity**

Name of Work: Construction of link road from Dhanuudhar to Pujarli km. 0/00 to 3/750 undr deposit work ( Sub Head:- Construction of R/Wall at RD. 2/367 to 2/371)

Sl. No.	Description of work	Qty.	Unit	Estimated cost:-	
				Earnest Money	83818.00
				Time	20000.00
				RATE	AMOUNT
1	Excavation in soil in Hilly Area in all kinds of soil by all means including cutting and trimming of side slopes and disposing of excavated earth upto all leads and lifts as per drawing and technical Specification clauses 1603.1 and as per direction of The Engineer-In-Charge complete.	4.20	Cubic Metre		
2	Earthwork in excavation for foundation of structures upto all depth as per drawing and technical specification clauses 305.1 including setting out, construction of shoring and bracing , removal of stumps and other deleterious matter, dressing of sides and bottom and backfilling with approved material as per direction of The Engineer-In-Charge complete.	6.80	Cubic Metre		
3	Providing and Laying plain cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	1.72	Cubic Metre		
4	Stone masonry work in cement mortar in sub-structure complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	18.28	Cubic Metre		
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	3.00	Cubic Metre		
<b>Total in Figures</b>					

  
 Executive Engineer  
 Outer Seral Division  
 HPPWD, Nimmarid

Signature of Tenderer with seal



(7)

SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of Parshuram Mela ground at Nirmand District Kullu H.P. (SH:- P/L)  
 local stone flooring in Parshuram mela ground Nirmand portion stage side) under SDP deposit

Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains in all depths including dressing of sides and ramming of bottoms, up to all leads and lifts including getting out the excavated soil and disposal of surplus excavated soil as directed within all leads in all kinds of soil as per direction of The Engineer-In-Charge complete.	20.40	Per Cubic Meter			
2	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.40	Per Cubic Meter			
3	Providing and laying 40mm (forty millimetre) thick red sand stone slab flooring on 20mm (twenty millimetre) thick base of cement mortar 1:5 (one cement : five sand) with joints 3 mm (three millimetre) thick side buttered with cement mortar 1:2 (one cement : two sand) admixed with pigment to match the shade of stones and pointing with same mortar complete all as per direction of Engineer-in-Charge and including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	204.00	Per Square Meter			
<b>Total:-</b>						

Executive Engineer,  
 Outer Serai Division,  
 HP PWD, Nirmand.



8

SCHEDULE OF QUANTITY

NAME OF WORK :- Repair and Maintenance of Parshuram Mela ground at Nirmand District Kullu H.P. (SH:- P/L)  
 local stone flooring in Parshuram mela ground Nirmand portion Parshuram kothi side) under SDP deposit

Estimated Cost:- 417591.00  
 Earnest money:- 10000.00  
 Time:- Three months

Sr. No.	Sub-head and item of work	Quantity	Unit	Rate in Figures	Rate in words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains in all depths including dressing of sides and ramming of bottoms, up to all leads and lifts including getting out the excavated soil and disposal of surplus excavated soil as directed within all leads in all kinds of soil as per direction of The Engineer-In-Charge complete.	20.40	Per Cubic Meter			
2	Providing and Laying plain cement concrete 1:5:10 (one cement : five sand : ten graded stone aggregate 40 mm (forty millimetre) nominal size) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	20.40	Per Cubic Meter			
3	Providing and laying 40mm (forty millimetre) thick red sand stone slab flooring on 20mm (twenty millimetre) thick base of cement mortar 1:5 (one cement : five sand) with joints 3 mm (three millimetre) thick side buttered with cement mortar 1:2 (one cement : two sand) admixed with pigment to match the shade of stones and pointing with same mortar complete all as per direction of Engineer-in-Charge and including curing and carriage of materials in all leads and lifts as per direction of The Engineer-In-Charge complete.	204.00	Per Square Meter			
<b>Total:-</b>						

Executive Engineer  
 Outer Sanitation Division  
 H.P.W.D. Nirmand