

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
"NOTICE INVITING TENDER"**

Sealed **Percentage rates** tender in **emergent condition** on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under **emergent/inescapable nature** from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **17.06.2022 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interested contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto 1.00PM & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Non refundable) up to 5.00 P.M. on 16.06.2022.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No.II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr.No	Name of work	Estt cost	E/Money	Cost of tender form	Time limit
1	A/R & M/O Chail Gohar Pandoh road km 24/0 to 29/600 (SH:- P/L G-III for correction layer & repair of pot holes between km 24/0 to 29/600)	Rs.497538/-	Rs.10000/-	Rs.350	One month
2	A/R & M/O Dhar Kathyana road km 0/0 to 1/0 (SH:- P/L G-III for correction layer & repair of pot holes in km 0/0 to 1/0)	Rs.357993/-	Rs.7200/-	Rs.350	15 days
3	A/R & M/O MRBU road under Mandi Sub Division No.III HPPWD Mandi (Jail road Section) (SH:- Repair of patch work/pot holes in various RDs)	Rs.483035/-	Rs.9700/-	Rs.350	15 days
4	C/O Link road from Talyahar Maswari Manthala km 0/0 to 3/0 (SH:- F/C 5/7 mtr wide road in km 0/930 to 1/250) under SCSP	Rs.456588/-	Rs.9200/-	Rs.350	One month
5	A/R & M/O Ganpati Kun ka Tar road km 0/0 to 21/500 (SH:- C/O V shape drain in km 0/860 to 0/997)	Rs.64597/-	Rs.1300/-	Rs.350	One month
6	A/R & M/O on Mandi Tili Kehnwal Biar Kathlag Padhiun road 0/0 to 14/400 (SH:- C/O R/wall at RD 14/310 to 14/317)	Rs.155524/-	Rs.3200/-	Rs.350	One month
7	A/R & M/O on Mandi Tili Kehnwal Biar Kathlag Padhiun road 0/0 to 14/400 (SH:- C/O R/wall at RD 14/317 to 14/326)	Rs.203683/-	Rs.4100/-	Rs.350	One month
8	C/O Ratti Pul to Alathu via Sai road km 0/0 to 1/500 under SCSP (SH:- C/O B/wall at RD 0/395 to 0/410)	Rs.193862/-	Rs.3900/-	Rs.350	15 days
9	A/R & M/O NR building under Mandi Sub Division No.III HPPWD Mandi (SH:- Supplying and installation of computer, UPS Printer including all accessories)	Rs.358500/-	Rs.7200/-	Rs.350	15 days
10	A/R & M/O NR building under Mandi Sub Division No.III HPPWD Mandi (SH:- supplying and fixing stainless steel water cooler)	Rs.51330/-	Rs.1100/-	Rs.350	15 days
11	A/R & M/O on Circuit house Mandi Distt.Mandi HP (SH:-C/O B/wall in Old building circuit house parking front side RD 0/0 to 0/021.50)	Rs.476318/-	Rs.9600/-	Rs.350	One month
12	C/O Link road Sanyardi km 0/0 to 1/300 (SH:- C/O PCC R/wall at RD 0/600 to 0/610)	Rs.359457/-	Rs.7200/-	Rs.350	One month

13	A/R & M/O on Talyahr Pairi road km 0/0 to 5/100 (SH:- C/O R/wall at RD 3/060 to 3/075)	Rs.280466/-	Rs.5700/-	Rs.350	One month
14	A/R & M/O Residential building PWD type-II Qtr at Jail road Mandi Distt.Mandi HP (SH:- Providing wood work painting, distempering, kitchen cup board and other minor repair work to type-II Qtr.No.14 block-B)	Rs.125773/-	Rs.2600/-	Rs.350	One month
15	C/O Link road Sambal Nallah (Saatmile) km 0/0 to 5/700 (SH:- F/C 5/7 mtr wide jeepable to motorable road in km 2/958 to 3/285)	Rs.495374/-	Rs.10000/-	Rs.350	One month
16	C/O approach road to Centraol Gramin Himachal Bhandar (Rural huts) near Transit camp Pandoh HP (SH:- C/O parking, edge wall and grating) Deposit work	Rs.499321/-	Rs.10000/-	Rs.350	One month
17	Maintenance of Nerchowk Pandoh i/c Pandoy by pass section of NH-21 km 191/190 to 230/500 under NHDP-IVB on Hybrid Mode in the state of HP (SH:-clearing/removal of slips over drain demolition of blocked PCC existing drain at RD 201/750 to 203/00)	Rs.306909/-	Rs.6200/-	Rs.350	One month
18	A/R & M/O various road of under Mandi Sub Division IV HPPWD Mandi (Bdir Section) (SH:- Hiring of JCB for removal of slips,debries & excavation of katcha drain)	Rs.150000/-	Rs.3000/-	Rs.350	One month

**GENERAL CONDITIONS:-**

- 1 The tender forms will not be issued to those contractors whose performance is not found satisfactory.
- 2 The contractors whose rates are abnormally low may be asked to furnish the full justification of his rate failing which he will be debarred to compete in tendering for four months.
- 3 The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking that he is not having more than two works in hand must be recorded in the application.
- 4 **The rates beyond the limit of -30% and over + 5%, will be rejected, besides this the Additional Performance security will have to borne @ 20% & 30 % for unbalanced bid in case the rates is lower than 10% but upto 20% & lower than 20% upto 30% respectively..**

Executive Engineer  
Mandi Division No.II  
HP.PWD Mandi

No.PW-MDII-CB NIT (off line) /2021-

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt.Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt.Mandi HP
4. The Chief Engineer, (MZ) HPPWD: Mandi.
5. The Superintending Engineer, Ist Circle, HPPWD: Mandi.
6. The Distt.Panchyat officer Mandi Distt.Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt.Mandi HP
8. All A.E.S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies

Executive Engineer  
Mandi Division No.II  
HP.PWD Mandi


4814-28

Dated:-

8<sup>6</sup>/<sub>2022</sub>

## CERTIFICATE

CERTIFIED THAT THE TENDER AS CALLED VIDE THIS OFFICE  
LETTER NO.PW/MDII/CB/NIT/OFF LINE/21-4814-28 DATED 8/6/22 THEREIN  
THE URGENCY OF WORK I.E. C/O R/WALLS, B/WALL & MAINTENANCE OF  
RESIDENTIAL/NON RESIDENTIAL BUILDINGS ETC AS WELL AS REPAIR OF  
ROAD SURFACE BY PROVIDING G-III & POTES HOLES WHICH HAS BEEN  
DAMAGED BADLY DUE TO HEAVY RAINY IN WINTER & RAINY SEASONS AND  
REQUIRED SUCH PROVISION MENTIONED THEREIN TO MAINTAIN THE ROAD  
SURFACE FOR PLYING OF SMOOTH VEHICULAR TRAFFIC.

  
Executive Engineer  
Mandi Division No.II  
HP.PWD,Mandi

Name of work :- A/R & M/O Chail Gohar Pandoh road Km. 24/00 to 29/600.  
(SH:- P/L G-III for correction layer and repair of pot holes between Km. 24/00 to 29/600).

%age Rate of SCHEDULE OF QUANTITY

Estimated Cost Rs. 4,97,538/-  
Earnest Money Rs. 10000/-  
Time :- One Month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (Eighty- hundred Kn) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405 By Manual/Mechanical means including carriage of materials with in all leads, lifts and other incidentals.	13.14	3203.00	Rupees Three Thousand Two Hundred Three Only	Per cubic metre	42,087.00
2	Providing and applying tack coat with Bitumen Emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 Kg. per sqm (zero point two five to zero point three zero kilogram per square metre) on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause 503 including hauling/carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	1352.29	22.05	Rupees Twenty Two and Paise Five Only	Per square metre	29,818.00
3	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm (Thirteen point two millimetre) to 5.6 mm (Five point six millimetre) aggregates using penetration grade bitumen VG-10/ S-90 to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (Eighty - hundred Kn) static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specification Clause 508 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	1352.29	240.80	Rupees Two Hundred Forty and Paise Eighty Only	Per square metre	3,25,631.00
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Bitumen S-90/ VG-10 grade Type B as per Technical Specification clause 510 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	1352.29	73.95	Rupees Seventy Three and Paise Ninety Five Only	Per square metre	1,00,002.00
					Total	4,97,538.00

Executive Engineer,  
Mandi Division No-II,  
H.P. PWD, Mandi.

# %age Rate of SCHEDULE OF QUANTITY

Name of work : A/R & M/O on Dhar Kathyana road Km. 0/00 to 1/00.  
(SI:- P/L G-III for correction and repair of pot holes in Km. 0/00 to 1/00).

Estimated Cost Rs. 3,57,1  
Earnest Money Rs. 7200,  
Time :- Fifteen days.

Sr. No.	Description of items.	Quantity	Rates		Unit	Am
			Figure	Words		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (Eighty- hundred Kn) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading-III as per Technical Specification Clause 405 By Manual/Mechanical means including carriage of materials with in all leads, lifts and other incidentals.	46.53	3203.00	Rupees Three Thousand Two Hundred Three Only	Per cubic metre	1,
2	Providing and applying tack coat with Bitumen Emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm (zero point two five to zero point three zero kilogram per square metre) on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause 503 including hauling/ carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	620.42	22.05	Rupees Twenty Two and Paise Five Only	Per square metre	
3	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm (Thirteen point two millimetre) to 5.6 mm (Five point six millimetre) aggregates using penetration grade bitumen VG-10/ S-90 to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (Eighty - hundred Kn) static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specification Clause 508 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	620.42	240.80	Rupees Two Hundred Forty and Paise Eighty Only	Per square metre	1,4
4	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Bitumen S-90/ VG-10 grade Type B as per Technical Specification clause 510 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	620.42	73.95	Rupees Seventy Three and Paise Ninety Five Only	Per square metre	4
	<b>Total</b>					<b>3,5</b>

Executive Engineer,  
Mandi Division No-II,  
P.W.D., Mandi.

# **%AGE OF SCHEDULE OF QUANTITY**

name of work :- A/R & M/O MRBU<sup>road</sup> under Mandi Sub-Division No. III, HPPWD Mandi. (Jail road Section).  
(SH:- Repair of patch work/pot holes in various RDs.)

Estimated Cost Rs. 4,83,035/-  
Earnest Money Rs. 9,700/-  
Time :- Fifteen days.

Sl. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
		3	4	5	6	7
2	Providing and applying tack coat with Bitumen Emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 Kg. per sqm (zero point two five to zero point three zero kilogram per square metre) on the prepared granular surfaces treated with primer and cleaned with Hydraulic broom as per Technical Specification Clause 503 including hauling/carryage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	1434.19	22.05	Rupees Twenty Two and Paise Five Only	Per square metre	31,624.00
2	Providing, laying and rolling of open-graded premix carpet of 20 mm (Twenty millimetre) thickness composed of 13.2 mm (Thirteen point two millimetre) to 5.6 mm (Five point six millimetre) aggregates using penetration grade bitumen VG-10/ S-90 to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 80-100 kN (Eighty - hundred Kn) static roller capacity, finished to required level and grades to be followed by seal coat of Type B as per technical specification Clause 508 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	1434.19	240.80	Rupees Two Hundred Forty and Paise Eighty Only	Per square metre	3,45,353.00
3	Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Bitumen S-90/ VG-10 grade Type B as per Technical Specification clause 510 By Manual Means including carriage of materials with in all leads, lifts and other incidentals.	1434.19	73.95	Rupees Seventy Three and Paise Ninety Five Only	Per square metre	1,06,058.00
					<b>Total</b>	<b>4,83,035.00</b>


Executive Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi

# %age Rate of SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Talyahar Maswari Manthala Km. 0/00 to 3/00.  
(SH:- F/C 5/7 mtr. wide road in Km. 0/930 to 1/250) under SCSP.

Estimated cost Rs. 4,56,588/-  
Earnest Money Rs. 9200/-  
Time:- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) over all areas in depth and width as well as any sqm in plan including getting out and disposal of excavated earth any leads and lift as directed by the Engineer-in-charge. The work shall be executed in workman like manner and avoids any damages to the private/Govt. property in the vicinity of work site, if damage access any property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	3 1858.28	4 264.10	5 Rupees Two Hundred Sixty Four and Paise Ten Only	6 Per Cubic Metre	7 4,90,764.00
2	Less credit for useful stone the recovery for useful stone shall be deducted from each running bill of the contractor on Pro-rata basis against item No.1.	113.92	300.00	Rupees Three Hundred Only	Per Cubic Metre	4,90,764.00 34,176.00
	<b>Total</b>					<b>4,56,588.00</b>


 Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi.

# %age Rate of SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Ganpati Kun Ka Tar road Km. 0/00 to 21/500  
(SH:- C/O V-shape Drain in Km. 0/860 to 0/997).

Estimated Cost Rs. 64,597/-  
Earnest Money Rs. 1300/-  
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	11.23	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	4,878.00
2	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals.	9.86	6056.65	Rupees Six Thousand Fifty Six and Paise Sixty Five Only	Per Cubic Metre	59,719.00
	<b>Total</b>					<b>64,597.00</b>

  
Executive Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi

**%age Rate of SCHEDULE OF QUANTITY**  
**Name of work :- A/R & M/O on Mandi Tili Kehwal Biar Kathag Padih road 0/00 to 14/400.**  
**(SH:- C/O R/wall at RD 14/310 to 14/317).**

Estimated Cost Rs. 1,55,524/-  
 Earnest Money Rs. 3,200/-  
 Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto any lead, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead including carriage of materials with in all leads, lifts and other incidentals	3 6.30	171.40	Rupees One Hundred Seventy One and Paise Forty Only	6 Per Cubic Metre	7 1,080.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas upto any lead including getting out and disposal of surplus excavated earth work upto any lead in ordinary rock as directed by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	7.14	235.05	Rupees Two Hundred Thirty Five and Paise Five Only	Per Cubic Metre	1,678.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	28.07	5025.70	Rupees Five Thousand Twenty Five and Paise Seventy Only	Per Cubic Metre	1,41,071.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	11.00	381.80	Rupees Three Hundred Eighty One and Paise Eighty Only	Each	4,200.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.B. Granular material including carriage of materials with in all leads, lifts and other incidentals.	4.62	1622.20	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	7,495.00
		<b>Total</b>				<b>1,55,524.00</b>

  
 Executive Engineer,  
 Mandi Division No-II,  
 H.P. PWD, Mandi.

**Name of work :- A/R & M/O on Mandi Tili Kehnwal Biar Kathlag Padhun road 0/00 to 14/400.**  
**(SH:- C/O R/wall at RD 14/317 to 14/326).**

**%age Rate of SCHEDULE OF QUANTITY**

Estimated Cost Rs. 2,03,683/-  
 Earnest Money Rs. 4,100/-  
 Time :- One month.

Sr. No.	Description of items.	Quantity	Rates			Unit	Amount
			Figure	Words			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m ( one point five metre) in width or ten square metre on plan), including dressing of sides and ramming of bottoms, lift upto any lead, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any lead including carriage of materials with in all leads, lifts and other incidentals.	6.48	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per Cubic Metre	1,111.00	
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas upto any lead including getting out and disposal of surplus excavated earth work upto any lead in ordinary rock as directed by the Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	9.90	235.05	Rupees Two Hundred Thirty Five and Paise Five Only	Per Cubic Metre	2,327.00	
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	36.09	5025.70	Rupees Five Thousand Twenty Five and Paise Seventy Only	Per Cubic Metre	1,81,378.00	
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	15.00	381.80	Rupees Three Hundred Eighty One and Paise Eighty Only	Each	5,727.00	
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	8.10	1622.20	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	13,140.00	
Total						2,03,683.00	

Estimated Cost Rs. 2,03,683/-

Earnest Money Rs. 4,100/-

Time : One month

  
 Executive Engineer,  
 Mandi Division No-II,  
 HP. PWD, Mandi.

# **%age Rate of SCHEDULE OF QUANTITY**

**Name of work :- C/O Ratti Pul to Alathu via Sai road Km. 0/0 to 1/500 under SCSp**  
**(SH:- C/O B/wall at RD. 0/395 to 0/410).**

Estimated Cost Rs. 1,93,862/-  
 Earnest Money Rs. 3900/-  
 Time :- One month.

Sr.	Description of Items.	Quantity	Rates	Words	Unit	Amount
			Figure			
1	2	3	4	5	6	7
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	25.73	114.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	11,176.00
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals	35.55	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	1,78,617.00
3	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	12.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	4,069.00
					<b>Total</b>	<b>1,93,862.00</b>

  
 Executive Engineer,  
 Mandi Division No-II,  
 PWD, Mandi.

# Rate of SCHEDULE OF QUANTITY

A/R & M/O Non Residential building under Mandi Sub-Division No.III HPPWD Mandi.  
(SH:- Supplying and installation of computer, UPS, Printer including all accessories)

Estimated Cost Rs. 3,58,500 /-  
Earnest Money Rs. 7200 /-  
Time :- Fifteen days.

## Description of items.

Sl. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing and supplying Lenovo all in one computer, Ryzen 5, 8GB Ram, 512 GB SSD, 24" LED IPS Display wireless Keyboard, mouse window 11 preloaded office 2019 H&S, preloaded (3 Years warranty) including carriage of materials with in all leads, lifts and other incidentals.	3.00	80,000.00	Rupees Eighty Thousand Only	Each	2,40,000.00
2	Providing and supplying HP 126 A Multipurpose Laserjet printer, i.e. Print, Scan and Copy (one year warranty) including carriage of materials with in all leads, lifts and other incidentals.	5.00	21,000.00	Rupees Twenty One Thousand Only	Each	1,05,000.00
3	Providing and supplying U.P.S. (Universal Power Supply) 600 VD (one year warranty) including carriage of materials with in all leads, lifts and other incidentals.	3.00	4,500.00	Rupees Four Thousand Five Hundred Only	Each	13,500.00
					<b>Total</b>	<b>3,58,500.00</b>

Executive Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi

**%age Rate of SCHEDULE OF QUANTITY**

**Name of work :-** A/R & M/O Non Residential building under Mandi Sub-Division No.III HPPWD Mandi.  
(Slt:- Supplying and fixing stainless steel water cooler)

Estimated Cost Rs. 51,330/-  
Earnest Money Rs. 1100/-  
Time :- Fifteen days.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Supplying and fixing Stainless steel water cooler 60 ltr. (sixty litre) capacity Single tap including fitting with in all leads, lifts and other incidentals.	1.00	51,330.00	Ruppes Fifty One Thousand Three Hundred Thirty Only	Each	51,330.00
<b>Total</b>						<b>51,330.00</b>

  
Executive Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi

**%age Rate of SCHEDULE OF QUANTITY**  
**(SH:- C/O B/wall in old building Circuit House parking front side RD. 0/00 to 0/021.50).**

Name of work :- A/R & M/O on Circuit House Mandi Distt. Mandi.

Estimated Cost Rs. 4,76,318/-  
 Earnest Money Rs. 9600/-  
 Time :- One month.

Sr.	Description of items.	Quantity	Rates Figure	Words		Unit	Amount
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	3	4	Rupees One Hundred Ninety and Paise Ninety Only	5	6	7
2	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	34.93	190.90			Per Cubic Metre	6,668.00
3	Coursed Rubble stone masonry (2nd sort) in cement mortar (1:6) (One cement : six sand) for sub-structure complete as drawing and technical specification of Ministry of Rural road Development for Rural road clauses 702, 704, 1202 and 1204 including carriage of materials with in all leads, lifts and other incidentals.	9.56	434.35			Per Cubic Metre	4,152.00
4	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification Clause 702, 704, 1202 and 1204 in cement mortar (1:6) (One cement : six sand) as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	10.88	5283.9			Per Cubic Metre	57,489
5	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	9.88	4998.80			Per Cubic Metre	49,388
6	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	68.03	5032.30			Per Cubic Metre	3,42,347.00
		48.00	339.05			Each	16,274.00
						<b>Total</b>	<b>4,76,318.00</b>

  
 Executive Engineer,  
 Mandi Division No-II,  
 HP. PWD, Mandi.

**%age Rate of SCHEDULE OF QUANTITY**  
**Name of work:- C/O link road Sanyardi Km. 0/00 to 1/300.**  
**(SH:- C/O PCC R/wall at RD 0/600 to 0/610).**

Estimated cost:- Rs. 3,59,457/-  
 Earnest Money Rs. 7200/-  
 Time:- One Month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	44.85	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	19,48
2	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	63.00	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	3,16,55
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	10.20	1500.20	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	15,30
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	24.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	8,13
	<b>Total</b>					<b>3,59,45</b>

  
 Executive Engineer,  
 Mandi Division No-II,  
 HP. PWD, Mandi.

# %age Rate of SCHEDULE OF QUANTITY

Name of work :- A/R & M/O on Talyahar Paidi road Km. 0/00 to 5/100.  
(SH:- C/O R/wall at RD. 3/060 to 3/085)

Estimated Cost Rs. 2,80,466/-  
Earnest Money Rs. 5700/-  
Time :- One month.

Description of items.		Quantity	Rates		Unit	Amount
Sr.			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals.	8.88	135.30	Rupees One Hundred Thirty Five and Paise Thirty Only	Per Cubic Metre	1,201.00
2	Excavation in Hilly Area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with a lift upto any lead as per Technical Specification clause 1603.2 including carriage of materials with in all leads, lifts and other incidentals.	9.52	303.30	Rupees Three Hundred Three and Paise Thirty Only	Per Cubic Metre	2,887.00
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	25.44	5082.10	Rupees Five Thousand Eighty Two and Paise Ten Only	Per Cubic Metre	1,29,289.00
4	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	24.48	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	1,22,997.00
5	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	26.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	8,815.00
6	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	9.12	1675.15	Rupees Four Hundred Eighty One and Paise Thirty Only	Per Cubic Metre	15,277.00
Total						2,80,466.00

Executive Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi.

**%age Rate of SCHEDULE OF QUANTITY**

Name of work:- A/R & M/O Residential building PWD Type-II Qtr. at Jail road Mandi Distt. Mandi H.P.

(SH:- Providing wood work painting, distempering, Kitchen cup board and other minor repair work in Type-II Qtr. No. 14 Block-B).

Estimated cost:- Rs. 1,25,773/-  
Earnest Money Rs. 2600/-  
Time:- One Month

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Providing wood work in frames of doors, windows clerestory windows and other frames wrought framed and fixed in position 2nd class deodar wood including carriage of materials with in all leads, lifts and other incidentals.	0.134	115845.55	Rupees One Lakh Fifteen Thousand Eight Hundred Forty Five and Paise Fifty Five Only	Per Cubic metre	15,523.00
2	Providing and fixing 35mm (thirty five millimetre) thick second class deodar wood wire gauge shutters using galvanized M.S. wire gauge of I.S. gauge designation 85G with wire of dia 0.56 mm (zero point five six millimetre) for doors, windows, clerestory windows including bright finished/black enamelled iron butt hinges with necessary screws including carriage of materials with in all leads, lifts and other incidentals.	12.39	3280.15	Rupees Three Thousand Two Hundred Eighty and Paise Fifteen Only	Per Square metre	40,641.00
3	Providing and fixing 100mm (one hundred millimetre) aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, necessary screws etc. complete including carriage of materials with in all leads, lifts and other incidentals.	34	50.75	Rupees Fifty and Paise Seventy Five Only	Each	1,726.00
4	Providing and fixing 150x10mm (one hundred fifty into ten millimetre) aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials with in all leads, lifts and other incidentals.	42	55.35	Rupees Fifty Five and Paise Thirty Five Only	Each	2,325.00
5	Discentpering with 1st quality acrylic discentper (Ready mix) having VOC content less than 50 grams/ litre (fifty grams/litre) of approved brand and manufacture to give an even shade Old work (one or more coats) including carriage of materials with in all leads, lifts and other incidentals.	203.60	48.10	Rupees Forty Eight and Paise Ten Only	Per Square metre	9,793.00
6	Removing dry or oil bound discentper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. including carriage of materials with in all leads, lifts and other incidentals.	81.44	13.60	Rupees Thirteen and Paise Sixty Only	Per Square metre	1,108.00
7	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials with in all leads, lifts and other incidentals.	81.44	95.60	Rupees Ninety Five and Paise Sixty Only	Per Square metre	7,786.00
8	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 litr/10 sqm (zero point ninety litre per ten square metre) over an under coat of primer applied @0.75 litr/10 sqm (zero point seventy five litre per ten square metre) of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidentals.	114.33	106.80	Rupees One Hundred Six and Paise Eighty Only	Per Square Metre	12,210.00
9	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade shade on old work (one ore more coat including carriage of materials with in all leads, lifts and other incidentals.	10.65	71.10	Rupees Seventy One and Paise Ten Only	Per Square metre	757.00

10	Finishing wall with water proofing cement paint of required shade old work (one or more coat applied @ 2.20 kg / 10 sqm )over primer coat of applied @ 0.80 ltr. / 10 sqm complete including coat of primer including carriage of materials with in all leads, lifts and other incidentals.	34.32	75.10	Ruppes Seventy Five and Paise Ten Only	Per Square metre	2,577.00
11	Providing and fixing 6mm (six-millimetre) thick standard quality hard sheet lining with butt jointing and nails (frame work and cover fillets to be measured and paid separately) including carriage of materials with in all leads, lifts and other incidentals.	1.23	716.80	Ruppes Seven Hundred Sixteen and Paise Eighty Only	Per square metre	882.00
12	Providing and fixing 18mm (eighteen millimetre) thick HDMR Board in wall paneling as per direction of Engineer-in-charge complete including carriage of materials with in all leads, lifts and other incidentals.	9.32	2400.00	Ruppes Two Thousand Four Hundred Only	Per Square metre	22,368.00
13	Providing and fixing hydraulic hinges for almirah of superior quality as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	10.00	235.75	Ruppes Two Hundred Thirty Five and Paise Seventy Five Only	Each	2,358.00
14	Providing and fixing fancy handle for almirah of superior quality as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	5	340.00	Ruppes Three Hundred Forty Only	Each	1,700.00
15	Providing and fixing vitreous china wash down water closet (European Type -W.C. Pan) with integral 'p' or 's' trap including jointing the trap with soil pipe in cement mortar 1:1 (one cement : one sand) (sheet and cover to be measured and paid for separately) (Anglo Indian universal closet) including carriage of materials with in all leads, lifts and other incidentals.	1.00	3354.00	Ruppes Three Thousand Three Hundred Fifty Four Only	Each	3,354.00
16	Providing and fixing plastic seat (Solid type) and cover for wash down water closet with C.P. brass hinges and rubber buffers (white plastic seat and cover) including carriage of materials with in all leads, lifts and other incidentals.	1.00	665.10	Ruppes Six Hundred Sixty Five and Paise Ten Only	Each	665.00
	<b>Total</b>					<b>1,25,773.00</b>

  
 Executive Engineer,  
 Mandi Division No-II,  
 HP. PWD, Mandi

# %age rate of SCHEDULE OF QUANTITY

C/O link road Sambal Nallah (Saatumile) Km 0/00 to 5/700.  
(Sft. F/C 5/7 mtr. wide jeepable to Motorable road in Km. 2/958 to 3/285).

Estimated cost Rs. 4,95,374/-  
Earnest Money Rs. 10000/-  
Time:- One Month

Description of items.	Quantity	Rates		Unit	Amount
		Figure	Words		
2	3	4	5	6	7
ation in soil in Hilly area by all means in all kinds of soil such as pick work, jumper work, ng work both in soft and hard rock with chiselling/wedging out rock (where blasting is rited) and other intermediate classification of soil including cutting and trimming of side and disposal of unserviceable material by mechanical transport and stacking the sable/ useful material on road berms as per technical specification clause 1603.1,1603.2 or d by the Engineer-in-charge. The work shall be executed in workman like manner and any damages to the private/ Govt. property in the vicinity of work site, if damage access roperty during the course of execution shall be the absolute responsibility of the contractor shall have to be duly compensated by him in all cases.	2190.67	290.13	Rupees Two Hundred Ninety and Paise Thirteen Only	Per Cubic Metre	6,35,588
<b>Total</b>					<b>6,35,588.00</b>
credit for useful stone- the recovery for useful stone shall be deducted from each running bill contractor on prorata basis against item No. 1	233.69	600.00	Rupees Six Hundred Only	Per Cubic Metre	1,40,214.00
<b>Total</b>					<b>4,95,374.00</b>


  
Executive Engineer,  
Mandi Division No-II,  
H.P. PWD, Mandi.

# %age Rate of SCHEDULE OF QUANTITY

Name of work :- C/O Approach road to Central Gramin Himachal Bhandar (Rural Huts) near Transit Camp Pandoh H.P.  
(SH:- C/O Parking, Edge wall and grating). Deposit Work

Estimated Cost Rs. 4,99,321/-  
Earnest Money Rs. 10000/-  
Time :- One month.

Sr.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead of 50m dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil with in all leads, lifts and other incidentals.	24.36	434.35	Rupees Four Hundred Thirty Four and Paise Thirty Five Only	Per Cubic Metre	10,581.00
2	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including hauling/carriage of materials through all modes of transportation with in all leads and lifts of materials and other incidentals.	699.2	102.35	Rupees One Hundred Two and Paise Thirty Five Only	Per Cubic Metre	71,563.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	73.08	5024.40	Rupees Five Thousand Twenty Four and Paise Forty Only	Per Cubic Metre	3,67,183.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm (one hundred millimetre) dia. U-PVC pipe extending through the full width of the structure with slope of (V) : 20 (H) towards drawing face complete as per drawing and technical specifications including carriage of materials with in all leads, lifts and other incidentals.	29.00	339.05	Rupees Three Hundred Thirty Nine and Paise Five Only	Each	9,832.00
5	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials with in all leads, lifts and other incidentals.	286.46	140.20	Rupees One Hundred Forty and Paise Twenty Only	Per Kilogram	40,162
	<b>Total</b>					<b>4,99,321.00</b>

  
Executive Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi.

# %age Rate of SCHEDULE OF QUANTITY

Maintenance of Nerchowk Pandoh including Pandoh by pass Section of NH-21 Km. 191/190 to 203/500  
under NHDP-IVB on Hybrid Mode in the state of Himachal Pradesh. (SH: Clearing/removal of slips over drain,  
demolition of blocked PCC existing drain at RD. 201/750 to 203/00).

Estimated Cost Rs. 3,06,909/-  
Earnest Money Rs. 6200/-  
Time :- One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Demolishing cement concrete manually/by mechanical means including disposal of material upto any lead as per direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	58.50	1274.85	Rupees One Thousand Two Hundred Seventy Four and Paise Eighty Five Only	Per cubic metre	74,579.00
	Excavation in soil in hilly area by all means in all kinds of soil such as pick work, unper work, blasting work both in soft and hard rock with chiselling/wedging out rock (where blasting is prohibited) and other intermediate classification of soil including cutting and trimming of side slopes and disposal of unserviceable material by mechanical transport and stacking the serviceable/ useful material on road berms as per technical specification clause 1603.1,1603.2 or directed by the Engineer-in-charge. The work shall be executed in workman like manner and avoids any damages to the private/ Govt. property in the vicinity of work site, if damage access any property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	177.10	229.15	Rupees Two Hundred Twenty Nine and Paise Fifteen Only	Per Cubic Metre	40,582.00
	Removal of slips/ landslides in hilly area in all kinds of soil including saturated soil, rocky portion requiring blasting/ chiselling by all means including cutting and trimming of slopes and disposal of unserviceable material and stacking of serviceable material, with in all leads and lifts as per technical specification clause 302.3.5 and 1611 as per the direction of Engineer-in Charge. Any loss to the public/private property or any accident etc. happens during the course of execution shall be absolute responsibility of the contractor, which shall have to be fully compensated by him in all cases. The rate includes the cost for arrangement of labour/ machinery at sudden notice, transportation and hutments, interruption of traffic while working and inclement weather etc.	1261.50	152.00	Rupees One Hundred Fifty Two Only	Per Cubic Metre	1,91,748.00
	<b>Total</b>					<b>3,06,909.00</b>

  
Executive Engineer,  
Mandi Division No-II,  
HP. PWD, Mandi.

# **1 %age Rate of SCHEDULE OF QUANTITY**

Line of work :- A/R & M/O various roads of under Mandi Sub-Division IV HPPWD Mandi. (Bir Section)  
 /SH:- Hiring of JCB for removal of slips, debris, & excavation of Katcha drain)

Estimated Cost Rs. 1,50,000/-  
 Earnest Money Rs. 3000/-  
 Time :- One month.

Sl. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
01.	Hiring of JCB for removal of slips, debris, & excavation of Katcha drain and trimming of side slopes and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	150.00	1000.00	Rupees One Thousand Only	Per Hour	1,50,000.00
					<b>Total</b>	<b>1,50,000.00</b>

*(Signature)*  
 Executive Engineer,  
 Mandi Division No-II,  
 H.P.W.D. Mandi.