

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PW-MDI(Padhar)E-Tender-NIT/2022-23-

2742-44

Dated:- 30 ⁵/₂₂

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2.

Subject: -

Publishing of tender notice.

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

Copy forwarded the Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nirman Bhawan, Nigam Vihar, Shimla-2 for information and further necessary action please.


Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before **06.06.2022 up to 12:00 Noon** and the same shall be opened on the same day **at 12:30 P.M.** in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on **04.06.2022 upto 01:00 P.M.**

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., **at Padhar** reserves the right to accept or reject the tenders. The tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Annual repair & maintenance of Non-residential building in HPPWD Sub-Division Padhar under Mandi Division No. I at Padhar (SH:- Providing brick work in partition walls, painting and distempering & repair and installation of sanitary works in divisional office building at Padhar)	2,78,754/-	5,600/-	350/-	One month
2	Construction of Mini Secretariate cum Combind office Building at Padhar District Mandi (H.P.) (SH:- Providing and laying Tactile flooring)	3,64,136/-	7,300/-	350/-	One month
3	Construction of Boaching Lapas Rulang road Km 0/0 to 8/0 Under SCSP (SH:- Construction of PCC Breast wall at R.D. 1/975 to 1/995) (Right Side)	3,91,501/-	7,800/-	350/-	One month
4	Construction of Boaching Lapas Rulang road Km 0/0 to 8/0 Under SCSP (SH:- Construction of PCC Breast wall at R.D. 1/975 to 1/990) (Left Side)	2,91,957/-	5,800/-	350/-	One month
5	Construction of Boaching Lapas Rulang road Km 0/0 to 8/0 Under SCSP (SH:- Construction of wire crated Retaining wall at R.D. 2/090 to 2/100)	1,17,435/-	2,400/-	350/-	One month

- 1. Certified that tender of above works are being called of emergent nature in exigency of public interest.**

TERMS AND CONDITIONS:-

- The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
- The intending Contractor/Firm Should have attached copy of registration/renewal.
- The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
- The intending Contractors are requested to see the site of the work before submitting the tender.

5. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit that he is not having more two works.
6. The offer of the tender shall remain valid upto 90 days after the opening of tender.
7. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% to (-) 30% of the amount put to tender, otherwise the tender will be cancelled and recalled.
8. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Mandi Division No. I,
HPPWD., at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh

Schedule of Quantity

Estimated Cost:- Rs. 278754.00
 Earnest Money:- Rs. 5600.00
 Time:- One month

Name of work:- Annual repair & maintenance of Non residential building in H.P.W.D. Sub Division Padhar under Mandi Division No.1 at padhar. (Sub Head:- Providing brick work in partition walls, painting and distemping & repair and installation of sanitary works in divisional office building at Padhar.)

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Dismantling of flushing cistern of all types (C.I./PVC/Vitrious China) including stacking of useful materials near the site and disposal of unserviceable materials within all leads, lifts and other incidental charges complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.00 Nos.			Each	
2	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etcetera complete and stacking of serviceable materials within all leads, lifts and other incidental charges complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00 Nos.			Each	
3	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level up to floor all level in cement mortar 1:4 (one cement : four coarse sand) including curing and carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	5.67 Sqm.			Per square metre	
4	15 mm (fifteen millimetre) cement plaster on rough side of single or half brick wall of mix: 1:4 (one cement: four coarse sand) including curing and carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	7.56 Sqm.			Per square metre	
5	Providing and applying white cement based putty of average thickness 1 mm (one millimetre), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	640.25 Sqm.			Per square metre	
6	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etcetera including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	640.25 Sqm.			Per square metre	
7	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre (fifty gram per litre) of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	640.25 Sqm.			Per square metre	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
8	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications two or more coats applied @ 0.90 ltr/10 sqm (at the rate of zero point nine zero litre per ten square metre) over and under coat of primer applied @ 0.75 ltr. / 10 sqm (at the rate of zero point seven five litre per ten square metre) of approved brand and manufacture including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	138.54 Sqm.			Per square metre	
9	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 kg (thirty five kilogram) and door width upto 700 mm (seven hundred millimetre), with necessary accessories and screws etcetera complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00 No.			Each	
10	Providing and fixing bright finished brass handles with screws etcetera complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.					
10.1	125 mm (One hundred twenty five millimetre)	1.00 No.			Each	
10.2	100 mm (One hundred millimetre)	1.00 No.			Each	
11	Providing and fixing chromium plated brass 100 mm (one hundred millimetre) mortice latch and lock with 6 (six) levers and a pair of lever handles of approved quality with necessary screws etcetera complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00 No.			Each	
12	Providing and fixing 20mm (twenty millimetre) diameter curtain rods of 1.25 mm (one point two five millimetre) thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etcetera, wherever necessary complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	12.00 Metre			Per running metre	
13	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimetre) bevelled edge mirror of superior glass (of approved quality) complete with 6 mm (six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00 Nos.			Each	
14	Providing and fixing 3 (three) layer PP-R (Polypropylene Random copolymer) pipes PN - 16 (sixteen) Pipe, 32mm (thirty two millimetre) OD (SDR-7.4) conforming to IS 15801, UV stabilized & anti - microbial fusion welded, having thermal stability for hot & cold water supply, including all PP - R plain & brass threaded polypropylene random fittings, i/c fixing the pipe with clamps at 1.00 m (one metre) spacing including testing of joints and carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	30.00 Metre			Per running metre	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
15	Providing and fixing 15 mm (fifteen millimetre) nominal bore C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	6.00 Nos.			Each	
16	Providing and fixing 15 mm (fifteen millimetre) nominal bore C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms (six hundred ninety gram) complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00 No.			Each	
17	Providing and fixing 15 mm (fifteen millimetre) nominal bore C.P. brass bib cock of approved quality conforming to IS:8931 complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.00 Nos.			Each	
18	Providing and fixing 15 mm (fifteen millimetre) nominal bore C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms (eight hundred ten grams) complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	6.00 Nos.			Each	
19	Providing and fixing PTMT soap dish holder having length of 138mm (one hundred thirty eight millimetre), breadth 102mm (one hundred two millimetre), height of 75mm (seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms (one hundred six gram) complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00 Nos.			Each	
20	Providing and fixing uplasticised PVC connection pipe 15 mm (fifteen millimetre) nominal bore with 45 cm (forty five centimetre) length with brass unions complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	5.00 Nos.			Each	
21	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00 Nos.			Each	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
22	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350mm (four hundred thirty into two hundred sixty into three hundred fifty millimetre) and 340x410x265mm (three hundred forty into four hundred ten into two hundred sixty five millimetre) sizes respectively with automatic flushing cistern with standard flush pipe and C.P. Brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required, one urinal basin with 5 (five) litre white P.V.C. automatic flushing cistern complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.00 Nos.			Each	
23	Providing and fixing 15 mm (fifteen millimetre) nominal bore G.I. pipes complete with G.I. fittings including trenching and refilling etcetera complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	42.00 metre			Per running metre	
24	Providing and fixing White Vitreous China Wash basin size 630x450 mm (six hundred thirty into four hundred fifty millimetre) with a pair of 15 mm (fifteen millimetre) C.P. with C.I. brackets, 15 mm (fifteen millimetre) C.P. brass pillar taps, 32 mm (thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00 No.			Each	
25	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink with drain board 470x420 mm (four hundred seventy into four hundred twenty millimetre) bowl depth 178 mm (one hundred seventy eight millimetre) as per IS: 13983 with C.I. brackets and stainless steel plug 40 mm (forty millimetre), including painting of fittings and brackets, cutting and making good the walls wherever required complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	2.00 Nos.			Each	
26	Providing and fixing 8 mm (eight millimetre) diameter C.P. / S.S. Jet with flexible tube upto 1 (one) metre long with S.S. triangular plate to Euroopan type W.C. of quality and make as approved by Engineer-in-Charge complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00 Nos.			Each	
27	Providing and fixing P.V.C. waste flexible pipe 32 mm (thirt two millimetre) diameter for sink or wash basin including P.V.C. waste fittings complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	3.00 0.00			Each	

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
28	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m (one metre) spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 50 mm (fifty millimetre) nominal outer diameter pipes complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	18.00 metre			Per running metre	
29	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m (one metre) spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. External work - 110 mm (one hundred ten millimetre) nominal outer diameter pipes complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	6.00 metre			Per running metre	
30	Fixing water meter and stop cock in G.I. pipe line including cutting and threading the pipe and making long screws etc. complete (cost of water meter and stop cock to be paid separately) complete including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	1.00 No.			Each	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 H.P.PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- Rs. 364136.00
 Earnest Money:- Rs. 7300.00
 Time:- One month

Name of work:- Construction of Mini Secretariate cum Combin office Building at Padhar District Mandi (H.P.) .
Sub Head:- Providing and laying Tactile flooring.

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Providing and laying tactile flooring (for vision impaired persons as per standards) of size 300x300x9.8mm (three hundred into three hundred into nine point eight millimetre) having with water absorption less than 0.5% (zero point five percent) and conforming to IS: 15622 of approved make in all colours and shades for outdoor floors such as footpath, court yard, multi modals locations etcetera laid on 20mm (twenty millimetre) thick base of cement mortar 1:4 (one cement : four coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etcetera including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	146.76 square metre			Per square metre	
2	Extra for pre finished nosing in treads of steps of Kota stone/ sand stone slabs including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	528.15 metre			Per running metre	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 HP.PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- Rs. 391501.00
 Earnest Money:- Rs. 7800.00
 Time:- One month

Name of work:- Construction of Boaching Lapas Rulang road Km. 0/0 to 8/0. Under SSCP.
 Sub Head:- Construction of P.C.C. Breast wall at R.D. 1/975 to 1/995. (Right Side)

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	28.80 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	59.29 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	8.40 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	18.00 Nos.			Each	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 H.P. PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- Rs. 291957.00
 Earnest Money:- Rs. 5800.00
 Time:- One month

Name of work:- Construction of Boaching Lapas Rulang road Km. 0/0 to 8/0. Under SCSP.
 Sub Head:- Construction of P.C.C. Breast wall at R.D. 1/975 to 1/990. (Left Side)

Sr. No.	Description of Item	Qty	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	17.10 Cum.			Per cubic metre	
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	44.46 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	7.42 Cum.			Per cubic metre	
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge.	10.00 Nos.			Each	
	Total:-					


 Executive Engineer,
 Mandi Division No.1,
 H.P. PWD. at Padhar.

Schedule of Quantity

Estimated Cost:- 117435.00
 Earnest Money:- 2400.00
 Time:- One month

ame of work:- Construction of Boaching Lapas Rulang road Km. 0/0 to 8/0. under SCSP.
ub Head:- Construction of wire crated Retaining wall at R.D.2/090 to 2/100.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.65 Cum.			Per cubic metre	
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts, carriage of material and other incidentals as per direction of Engineer-in-Charge.	31.24 Cum.			Per cubic metre	
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	3.90 Cum.			Per cubic metre	
				Total:-		


 Executive Engineer,
 Mandi Division No.1,
 P.W.D. at Padhar.