

Email

Himachal Pradesh  
Public Works Department

NO/PW/PNH/AB/Tender/2022- 7560-62

Dated:- 25.06.2022

€To

The Executive Engineer (IT cell),  
Nigam Vihar, Shimla-2.

Subject:- Publication of tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Secy (PW) to the Govt. of HP letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16<sup>th</sup> July 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- NIT & Schedule of quantity and Certificate.



Executive Engineer,  
National Highway Division,  
HPPWD Pandoh.

Copy forwarded to the Superintending Engineer, NH Circle, HPPWD Shahpur for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer (IT Cell), Nigam vihar, Shimla-2 for information and further necessary action please.



Executive Engineer,  
National Highway Division,  
HPPWD Pandoh.

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
"NOTICE INVITING TENDER "

Sealed item rate tenders on form No. 6 & 8 are hereby invited by the Executive Engineer, NH Division, HPPWD, Pandoh for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HPPWD so as to reach in this office as per time schedule given below:-

1. Date of receipt of Applications for tender forms: - 06.07.2022
2. Date of issue/sale of Tender forms: - 07.07.2022
3. Date of receipt of Tender: - 08.07.2022 at 10.30 AM
4. Date of opening of Tender:- 08.07.2022 at 11.30 AM

Sr. No.	Name of work	Estimated cost	Earnest money	Cost of form	Time Period for completion	Form No.	Eligibility of Contractors
1	A/R & M/O on Attari-Leh-via Hamirpur -Tauni Devi-AwahDevi-Sarkaghat-Kotli-Manali road NH-70 (New No. 03) Km. 196/495 to 264/950 (SH:- Construction of P.C.C. Retaining Wall at RD 242/750 to 242/755).	Rs. 3,65,184/-	Rs. 7,400/-	Rs. 350/-	Two Months	6 & 8	Class C & D enlisted in HPPWD
2	A/R & M/O on Attari-Leh-via Hamirpur -Tauni * Devi-AwahDevi-Sarkaghat-Kotli-Manali road NH-70 (New No. 03) Km. 196/495 to 264/950 (SH:- Construction of P.C.C. Retaining Wall at RD 242/756 to 242/761).	Rs. 3,72,597/-	Rs. 7,500/-	Rs. 350/-	One Months	6&8	-do-

**TERMS & CONDITIONS:-** The tender documents shall be issued to those contractors/firms who fulfil the following documents with the application:-

1. The valid enlistment/registration of contractor in appropriate class.
2. Permanent Account Number (PAN).
3. GST Number.
4. Earnest money in the shape of National saving certificate/Time deposit Account in any of the Post office in HP, FDR from any Nationalized Bank (i/c Kangar Central Cooperative Bank and CD Cooperative Society) duly pledged in favour of the Executive Engineer.
5. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
6. Tax Clearance Certificate (T.C.C.) issued from the concerned Exercise and Taxation department.
7. Ambiguous/telegraphic/conditional tenders or tender by fax/E-mail shall not be entertained/considered and will summarily be rejected.
8. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
9. The offer of the tender shall remain valid upto 120 days after the opening of tender.
10. If the date given above happens to be a holiday, the same shall be processed on next working days.
11. The contractors/firm must quote their rates in words as well as in figures failing which Xn reserves the right to accept/reject any or all tenders.
12. The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.

13. One contractor should not have more than two major works in hand at a time.
14. Work should be completed by the contractor within the stipulated period.
15. Works completion and work in hand certificate issued by the concerned Executive Engineer must be attached with the application for issue of tender form.



Executive Engineer,  
National Highway Division,  
HP.PWD Pandoh.

For and on behalf of the Governor of HP.

NO/PW/PNH/AB/Tender/2022- 7550-59

Dated:- 25.06.2022

Copy forwarded for information and necessary actions to:-

1. The Engineer-in-Chief, HP.PWD, Nigam Vihar, Shimla.
2. The Chief Engineer, NH HP.PWD Shimla-2.
3. The Superintending Engineer, NH Circle, HPPWD Shahpur. It is requested to display the notice on the Notice Board please.
4. All the Superintending Engineers/Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Mandi. It is requested to display the notice on Notice Board.
6. The Tehsildar, Kotli Distt. Mandi. It is requested to display the notice on Notice Board
7. The B.D.O Kotli Distt. H.P. It is requested to display the notice on Notice Board.
8. All Assistant Engineers working under this Division. It is requested to display the notice on Notice Board.
9. Correspondence Branch/Drawing Branch/Notice board.
10. Lok Mitra Kendra, Pandoh.
11. Various Contractors/Firms.



Executive Engineer,  
National Highway Division,  
HP.PWD Pandoh.

CERTIFICATE

Certified that the Tender called vide this office letter No.PW-PNH-AB-Tender-2022- 7550-59 dated 25-06-2022 is very urgent nature. so may be uploaded on Department website in public interest.



Executive Engineer,  
National Highway Division,  
HP.PWD. Pandoh.



Schedule of Quantity


Estimated Cost:- Rs.3,65,184/-

Earnest money:- Rs.7400/-

Time allowed:- Two month.

Name of Work:- A/R & M/O on Attari-Leh via Hamirpur - Taunidevi-Awahdevi-Sarkaghat-Mandi-Manali Road NH-70(New NH-03)K.M.196/495 to 264/960.(Sub-Head:- Construction of P.C.C.Retaining wall at RD. 242/750 to 242/755.

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m(one point five metre) in width or 10 sqm(ten squaremetre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre) including getting out the excavated soil and disposal of surplus excavated soil, including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	33.70 Cubic metre			Per cubic metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc. including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	89.21 Square metre			Per square metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (One Cement Three coarse sand) Six graded stone aggregate 40 mm(forty millimetre nominal size) including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	59.45 Cubic metre			Per cubic metre	
4	Providing and laying weep holes in stone, brick masonry, plain/reinforced concrete abutments/wing walls/return walls, breast walls and retaining walls with 100 mm (one hundred millimetre) diameter PVC pipe, extended through the full width of the structure with slope of IV:20 H(One vertical isto twenty horizontal) towards drawing face complete as per drawing and MORT&H technical specification No 2706 and 2200 (5th revision- 2013) including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	9.00 Nos			Each	
5	Providing and laying back filling with granular material behind abutment, wing wall, return wall, retaining wall and breast wall including compaction complete as per drawings & MORT&H technical specification No 710.1.4 of IRC 78 and 2200 (5th revision- 2013) including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	4.45 Cubic metre			Per cubic metre	
					Total:-	

  
 Executive Engineer,  
 NH Division HPPWD,  
 Pandoh

Schedule of Quantity


Estimated Cost:- Rs.3,72,597/-

Earnest money:- Rs.7500/-

Time allowed:- Two month.

Name of Work:-A/R & M/O on Attari-Leh via Hamirpur -Taunidevi-Awahdevi-Sarkaghat-Mandi-Manali Road NH-70(New NH-03)K.M.196/495 to 264/960.(Sub-Head:-Construction of P.C.C.Retaining wall at RD. 242/756 to242/761 .

Sr. No.	Description of item	Quantity	Rate		Unit	Amount
			In Figure	In words		
1	Earth work in excavation for all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m(one point five metre) in width or 10 sqm/ten squaremetre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m(one point five metre) including getting out the excavated soil and disposal of surplus excavated soil, including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	27.35 Cubic metre			Per cubic metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses filets, kerbs and steps etc. including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	89.21 Square metre			Per square metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 (One Cement Three coarse sand). Six graded stone aggregate 40 mm(forty millimetre nominal size) including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	59.45 Cubic metre			Per cubic metre	
4	Providing and laying weep holes in stone, brick masonry, plain/reinforced concrete abutments/wing walls/return walls, breast walls and retaining walls with 100 mm (one hundred millimetre) diameter PVC pipe, extended through the full width of the structure with slope of IV 20 H(One vertical isto twenty horizontal) towards drawing face complete as per drawing and MORT&H technical specification No.2706 and 2200 (5th revision- 2013) including haulage of materials and equipments in all reads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	9.00 Nos			Each	
5	Providing and laying back filling with granular material behind abutment, wing wall, return wall, retaining wall and breast wall including compaction complete as per drawings & MORT&H technical specification No. 710 1.4 of IRC:78 and 2200 (5th revision- 2013) including haulage of materials and equipments in all leads and lifts with all modes of transportation and as per the entire satisfaction and direction of Engineer-in charge.	11.10 Cubic metre			Per cubic metre	
					<b>Total:-</b>	

  
 Executive Engineer,  
 NH Division HPPWD,  
 Pandoh