

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDERS"

Short terms tenders on form 6 & 8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 120 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of application for the tender

Form a/w requisite documents:-

17/06/2022 up to 02:30 PM

2. Date of issue/sale of Tender forms against Cash payment (Non-refundable):-

18/06/2022 up to 03:00 PM

The tender shall be received up to **11:00A.M. on 20/06/2022** and will be opened on the same day at 11:30 A.M in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours on **20/06/2022.**

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The XEN reserve the right to accept or reject the tenders without assigning any reason.

S.No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit	D. class
1.	C/O link road Salwad to Balh Chalog km 0/0 to 5/0 (SH:- C/O R/Wall at RD 0/470 to 0/491 and B/Wall in km 0/500 to 0/512)	208927/-	4200/-	350/-	Three Month	D
2.	M/T on link road Balhseena to House of Sh. Jugdev Singh Captain Balhseena km 0/00 to 0/328 (SH:- P/L 20 mm thick premix carpet surface at RD 0/0 to 0/328) Under D.C. Deposit	229247/-	4600/-	350/-	Three Month	D
3.	C/O Kotlu Sunhani road km 0/0 to 4/500 (SH:- C/O B/wall at RD 2/732 to 2/739, C/O R/wall at RD 2/782 to 2/790, Edge wall at junction point toward sargal side & C/O 600 mm dia RCC HPC at RD 1/095)	176483/-	3500/-	350/-	Three Month	D
4.	C/O Bachretu to Naghar road km 0/0 to 5/000 (SH:- C/O B/Wall at RD 3/107 to 3/122 & R/Wall at RD 3/121 to 3/129) Under SCSP.	136006/-	2700/-	350/-	Three Month	D
5.	C/O Balance work of additional Rest House Building at Shahtalai (SH:- P/L Kota Stone Flooring tank platform etc.	499253/-	10000/-	350/-	Three month	D
6.	C/O PHC Building at Buhar Tehsil Jhandutta Distt. Bilaspur (HP) (SH:- C/O Rain Water Harvesting tank of 25000 litre capacity) Deposit Work.	292288/-	5800/-	350/-	Three month	D
7.	C/O M/T Chatyal Balh to Khirishi Jamoi road km 0/0 to 2/00 (SH:- Balance work along with slab culvert Chatyal Balh side D/Stream R/Wall at RD 1/907 to 1/913 & U/Stream R/Wall at RD 1/907 to 1/921) Under OTMNP.	499189/-	10000/-	350/-	Three month	D
8.	C/O link road Chiknaghat to Kothi via Doon km 0/0 to 1/500 (SH:- C/O 5/7 mtr wide Formation cutting at RD 0/315 to 0/600 & C/O 900 mm dia HP Culvert at RD 0/610 & 0/710 along with both side wing wall Under OTMNP.	495538/-	9900/-	350/-	Three month	D
9.	C/O link road Makari to Chanjoti km 0/0 to 3/00 (SH:- C/O B/Wall at RD 1/600 to 1/622.50) Under BASP Deposit	277854/-	5600/-	350/-	Three month	D

10.	Repair of PHC Building Bheri Tehsil Jhandutta Distt. Bilaspur (HP) Deposit BASP	270378/-	5400/-	350/-	Three month	D
11.	C/O link road from GTB road to Nav Durga Mandir Baniya km 0/0 to 1/00 (SH:- C/O R/Wall at RD 0/466 to 0/480) Under OTMNP	297857/-	6000/-	350/-	Three month	D
12.	M/T on Devi ka Mod to Koshrian Boatghat road km 0/0 to 2/500 (SH:- Maint. Of Pot holes and WBM at RD 1/200 to 1/450)	102282/-	2000/-	350/-	Three month	D
13.	C/O Koshrian to Jaddu road km 0/0 to 14/600 (SH:- C/O R/Wall at RD 10/105 to 10/120) OTMNP	301131/-	6000/-	350/-	Three month	D
14.	C/O Bheri to Kalol road km 0/0 to 6/0 (SH:- P/L G-III at RD 2/550 to 2/980)	96213/-	1900/-	350/-	Two Month	D
15.	C/O link from Berthin to Badgaon km 0/0 to 1/00 (SH:-C/O U-Shape drain at RD 0/00 to 0/100) OTMNP	75292/-	1500/-	350/-	Three Month	D
16.	C/O Non Residential building of Sub Division Jhandutta (Old JE Residence) (SH:- C/O One additional Room)	394107/-	7900/-	350/-	Three Month	D
17.	A/R & M/O on MDR-116 km 0/0 to 31/00 (SH:- Balance work/Repair of pot holes in km 4/00 to 7/00, 9/00 to 10/00 11/00 to 14/00)	499190/-	10000/-	350/-	One Month	D
18.	C/O link road from Manan to Sidh Mandir km 0/0 to 1/000 (SH:- C/O R/wall at RD 0/140 to 0/158) OTMNP	99902/-	2000/-	350/-	Three Month	D
19.	R/R damages on B.V.C. road km 0/0 to 20/00 (SH:- Hiring of Tractor with Trolly including Labour Hiring)	99650/-	2000/-	350/-	Three Month	D
20.	C/O MDR road (95) Panol Jhandutta Nand Nagroun road km 0/0 to 21/00 (SH:- C/O 600 mm dia RCC HPC at RD 9/310 & Laying 450 mm dia Hume pipe for foot path crossing , Villages roads & house approaches) Under MDR.	272895/-	5500/-	350/-	Three Month	D
21.	C/O G.T.B road km 0/0 to 25/000 (SH:- P/L C.C Pavement at RD 24/325 to 24/365) Under OTMNP	157531/-	3200/-	350/-	Three Month	D
22.	Imp. Of Black Spot on B.J.S.M. road km 0/0 to 20/00 (SH:- C/O B/Wall at RD 5/335 to 5/355 with U-shape drain at RD 5/315 to 5/405) Under OTMNP	332912/-	6700/-	350/-	Three Month	D
23.	C/O link road Kot to Badeen km 0/0 to 0/500 (SH:- Providing Grating over U-shape drain & C/O U-shape drain & PCC Pavement at RD 0/435 to 0/450) Under SCDP	98295/-	2000/-	350/-	Three Month	D
24.	C/O Dahad Dehlwin road km 0/0 to 3/00 (SH:- C/O B/Wall at RD 0/550 to 0/557 & 0/620 to 0/628, 0/643 to 0/650 & Extension of 900 mm dia RCC HPC, U-shape drain and Wing Wall) Under OTMNP	208429/-	4200/-	350/-	Three Month	D
25.	C/O Fencing /Boundary wall H.E.C Kalol Horticulture Building at Kalol (Deposit work)BASP	194899/-	3900/-	350	three month	D
26.	C/O Berthin Chhat Dabiri road Km 0/0 to 2/00 (SH:- C/O C C Pavement at RD 1/050 to 1/100)(Under OTMNP)	357012/-	7100/-	350	three month	D
27.	C/O link road Bhoroli kalla to Jhanjnoo via Gurnadi Km 0/0 to 8/00 (SH:- C/O 6.00mtr span R.C.C slab Culvert U/S & D/S Side wing wall at RD 0/073 to 0/077(U/S) & RD 0/073 to 0/083(D/S) OTMNP	442045/-	8800/-	350	Three month	D

new

28.	C/O link road to Harizan Basti Mekhwin Km 0/0 to 1/0 (SH:- C/O V-shape Drain at RD 0/0 to 0/380(Under OTMNP)	475442/-	9500/-	Three month	350/-	D
29.	C/O Boundary wall Steps & Badminton Court to Govt. SSS Berthin Distt. Bilaspur(Deposit work)	497038/-	9900/-	Three months	350/-	D
30.	C/O link road from Dahad to Dehlwin road Km 0/0 to 3/0 (SH:- C/O R/walls at RD 1/673 to 1/683 & 1/706 to 1/724 Under OTMNP)	492782/-	9900/-	Three month	350/-	D
31.	C/O link road from Dahad to Dehlwin road Km 0/0 to 3/0 (SH:- C/O R/walls at RD 1/578 to 1/586.1/615 to 1/628 1/633 to 1/645 & 1/702 to 1/7270(Under OTMNP)	448908/-	9000/-	Three month	350/-	D
32.	C/O link road from Dahad to Dehlwin road Km 0/0 to 3/0 SH:- C/O R/walls at RD 1/591 to 1/1/596,1/905 to 1/940 & 1/974 to 1/998 (Under OTMNP)	428885/-	8600/-	Three month	350/-	D
33.	C/O link road to village sargal Km 0/0 to 0/450 (SH:- C/O R/wall at RD 0/178 to 0/198(Under OTMNP)	177680/-	3600/-	Three month	350/-	D
34.	C/O Dholag to Marloun road Km 0/0 to 4/500 (SH:- C/O D/S T/wall & W/wall at RD 2/915 to 2/985) Under OTMNP)	251608/-	5000/-	Three month	350/-	D
35.	A/R & M/O Mallari to Kallar road Km 0/0 to 6/0 (SH:- Repair of pot holes in Km 4/0 to 5/435	93344/-	1900/-	Three month	350/-	D
36.	C/O link road Bala to Lower Bala Km 0/0 to 1/160 (SH:- C/O 900mm dia H/Pipe culvert at RD 0/810,0/870,c/o W/wall At RD 0/620to 0/630, C/O R/wall at RD 1/140 to 1/160 & P/L soling G-I 0/040 to 0/205 (G-II 0/040 to 0/475 Under SCDP)	449893/-	9000/-	Three month	350/-	D
37.	C/O Link road to house of Hakam singh Km 0/00/250 (SH:- C/O cement concrete Pavement stone soling at RD 0/157 to 0/250 (Under Deposit work)	185055/-	3700/-	Three month	350/-	D
38.	C/O link road to Harizan Basti Mekhwin Km 0/0 to 1/0 (SH:- 0/0 to 1/0 (SH:- C/O R/wall at RD 0/380 to 0/390&0/550 to 0/564)(Under OTMNP)	493040/-	9900/-	Three month	350/-	D

TERMS & CONDITIONS:

1. The tender forms will not be issued to those contractors whose performance is not found Satisfactory.

2. The contractors should have executed two similar type of works 1/3 of each amount put to tender or single work of amount equal to the amount put to tender within last five years.

3. GST, EPF No, Earnest Money, Tender form cost, copy of Enlistment should be accompanied with application.

4. Application without all documents will not be entertained.

5. Proxy Application will not be entertained.

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

No-PW-JDT-CB-Tender NIT/2022-23:-

5716-26

Dated:-

07/06/22

Copy forwarded to the following for information and necessary action Please:-

1. The Engineer -in-Chief HP PWD Nirman Bhawan Shimla
2. All the Chief Engineer in HP PWD
3. The Superintending Engineer 10th Circle HP PWD Bilaspur
4. All the Assistant Engineer Working under this Division
5. The B.D.O Jhandutta
6. A/B & D/B in this office
7. Various Contractors working under this office
8. Notice Board

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Certificate

Certified that the tenders called vide this office letter
No. PW-JDT EA-I-Tender /2022-23- 5116-26 dated
07/06/22 is emergent nature and in Public interest

Executive Engineer
Jhandutta Division
HPPWD Jhandutta

Himachal Pradesh
Public works Department

NO-PW-JDT-EA-I Tender NIT/2022-23:- 5127-29 Dated:- 07/06/2022

To,
The Executive Engineer (IT Cell)
Nigam Bihar Shimla-2

Subject:- Publishing of Tender notice

Dear Sir,

Enclosed please find herewith the tender Notice of work as give in the Notice inviting Tender for uploading on department website as per notification Pr. Sec.(PW)to the Govt.of HP letter No-FBW(B)A9(3)1/2020dated Shimla -2the 16th july 2021 as the work mentioned in the tender notice are urgent in nature and public interest

DA:- Notice Inviting Tender

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

Copy forwarded the Superintending Engineer 10th Circle
Bilaspur HP PWD Bilaspur for information please

Copy forwarded to the Computer Cell O/O Executive Engineer
(IT Cell) Nigam Bihar Shimla -2 for information and further necessary action action

Executive Engineer
Jhandutta Division
HP PWD Jhandutta

SCHEDULE OF QUANTITY

Estimated cost:- ₹ 208927.00	Only
Earnest Money:- ₹ 4200.00	Only
Time allowed:- One Month	

Name of Work :- C/ O Link road Salwad to Balh chalog km 0/0 to 5/0 (SH:- C/O R/Wall at RD 0/470 to 0/491 and B/Wall in Km0/500 to 0/512)-

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	58.97			Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand, ten graded stone agg. 40 mm, nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centering & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	87.47			Per Cubic Meter	
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	62.00			Each	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.84			Per Cubic Meter	
Total:-						

SCHEDULE OF QUANTITY

Name of Work :- M/T on link road Balhseena to House of Shri Jugdev Singh Captain Balhseena Km 0/00 to 0/328 (SIH:- P/L 20 mm thick premix Carpet surface at RD 0/0 to 0/328), Under D. C. Deposit.

Estimated cost:- ₹ 229247.00 Only
Earnest Money:- ₹ 4600.00 Only
Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Preparation of sub-grade by dressing to camber (Earth work for the cutting involved for sub-grade to be measured and paid for separately) depending upon the classification of soil complete as per HP PWD, Specification as per direction of Engineer-in-charge, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	48.00			Per square metre	
2	Consolidation of sub-grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HP PWD, specification as per direction of Engineer-in-charge, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	48.00			Per square metre	
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading I as per Technical Specification Clause 405, including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octroi, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.25			Per cubic metre	
4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN (equity to one hundred kilonewtons) in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading -II as per MORD Technical Specification Clause 405, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	3.54			Per Cubic metre	

5	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spreading primer at the rate of 0.70- 1.0 kg per square metre (Zero point seven zero to one point zero zero kilograms) as per table 500.1(a) of MORD technical specification 2014, by mechanical means as per technical specification clause 502. of MORD technical specification 2014, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive , octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	1050.00				Per Square Metre	
6	Providing and applying tack coat with bitumen emulsion (RS-1) (one) using emulsion distributor at the rate of 0.20 to 0.25 kg (Zero point twenty to zero point twenty five) kilogram per Square metre as per table 500.2 of MORD technical specification 2014, on the prepared bituminous surface cleaned with hydraulic broom as per technical specification clause 503. of MORD technical specification 2014, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	1050.00				Per Square Metre	
7	Providing laying and rolling of open graded premix carpet of 20 mm (twenty millimeter) thickness composed of 13.2 mm to 5.6 mm (thirteen point two to five point six millimeter) aggregate either using penetration grade bitumen of emulsion to required fine grade and lavel to serve as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with three wheel 80-100 Ks (eighty to one hundred kilonewtons) static roller capacity, as per mord 2014 clause 506.1, finished to required level and grades to be followed by seal coat of type-B as per technical specification clause 508. (By mechanical means) Bitumen (S-90) (Ninety) including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government	1050.00				Per Square Metre	
8	Providing and laying seal coat for sealing the voids in bitumen surfaced laid to the specified levels, grade and cross fall using Type -C as per technical specification clause 508.3.4 of mord 2014 including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	1050.00				Per Square Metre	
Total:-							

SCHEDULE OF QUANTITY

Name of Work :- Construction of Kothu Sanhali road Km 0/0 to 4/500. (SI:- Construction of B/wall at RD 2/732 to 2/739, C/o R/wall at RD 2/782 to 2/790, Edge wall at Junction point toward sargal side & C/o 600 mm dia RCC Hume pipe culvert at RD 1/095). Under OTMNP.

2/739, C/o R/wall to R/wall at RD 2/782 to 2/790, Edge wall at Junction point toward sargal side & C/o 600 mm dia RCC Haume pipe culvert at RD 1/095). Under OTMNP.							Estimated cost:- ₹ 176483.00		Only
							Earnest Money:- ₹ 3500.00		Only
							Time allowed:- Three Month		
Sr. No.	Description of items	Quantity	Figures	Rate	words	Unit	Amount		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/e setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a level of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	30.84				Per Cubic Meter			
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone aggr. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	76.60				Per Cubic Meter			
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V); 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	28.00				Each			
4	Providing and laying reinforced cement concrete pipe NH2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one into two) but excluding excavation, protection work, back filling concrete and masonry work in head walls and parapets clause 1108 in 600 mm (six hundred millimeter) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	7.50				Per running Metre			
Total:-									

SCHEDULE OF QUANTITY

Name of Work :- Construction of Bachretu to Nagghiyar road Km 0/0 to 5/000 (SH:- C/O B/Wall at RD 3/107 to 3/122 & R/wall at RD 3/121 to 3/129) Under SSCP.

Name of work :- Construction of Bachettu to Nagghiyar road Km 0/0 to 5/000 (SH:- C/O B/Wall at RD 3/107 to 3/122 & R/Wall at RD 3/121 to 3/129) Under SCSP.									
Estimated cost:- ₹ 136006.00									
Earnest Money:- ₹ 2700.00									
Only									
Time allowed:- Three Month									
Sr. No.	Description of items	Quantity	Rate		Unit	Amount			
			Figures	words					
1	Excavation in earthwork in billy area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, fitting of new/existing, blinding and finishing of the road to specified dimensions or as directed by the Engineer-in-charge. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be fully compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	19.20			Per Cubic Meter				
2	Earth work in excavation for structure as per drawing and technical specification clause 303.1 for setting out construction of shooting and fencing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs; dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-charge; including carriage of materials, within all leads and lifts as per direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.79			Per Cubic Meter				
3	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone agg. 40 mm, nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centering & dewatering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-charge; including carriage of materials , within all leads and lifts as per direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	58.79			Per Cubic Meter				
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	1.00			Per Cubic Meter				
5	Providing weep holes in brick masonry (stone masonry, plain reinforced concrete abutment, wing wall return wall with 100 mm dia PVC pipe) extending through full of width of the structure with slope of (V) 70(H) towards draining face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-charge; including carriage of materials , within all leads and lifts as per direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	38.00			Each				
Total :-									

SCHEDULE OF QUANTITY

Name of Work :- Construction of balance work of additional Rest House Building at Shahatalai (SH:- P/L Kota Stone Flooring tank Platform etc.)

Estimated cost:- ₹ 499253.00 **Only**

Earnest Money:- ₹ 10000.00 **Only**

Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ranning of bottoms, lift upto all, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a all lead. All kinds of soil, incidentals, lift up to any height stacking excavated soil up to all leads and lifts clear from the edge of excavation and then returning the stacked soil in fifteen centimetre thick layer when required into plinths, sides of foundation etcetra consolidating each deposited layers by ranning and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respect.	13.12			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:1½:3 (1 Cement: 1½ coarse sand) : 3 graded stone aggregate 20 mm nominal size) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.47			Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand): 6 graded stone aggregate 40 mm nominal size) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	11.12			Per cubic metre	

4	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0				0	
i)	Foundations, footings, bases for columns	9.88				Per square metre	
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in cement mortar 1:4 (1 cement : 4 coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.85				Per square metre	
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.95				Per cubic metre	

7	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	147.43				Per square metre	
8	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete. including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.5				Per square metre	
9	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	67.34				Per square metre	

P-4 P-1

10	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6 (1 cement: 6 fine sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	99.11			Per square metre	
11	Extra for lining out plaster to initiate stone or concrete blocks walling including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	53.62			Per square metre	
12	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:3:6 or richer mix (i/e equivalent design mix) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.27			Per cubic metre	
Total:-						

Executive Engineer
Jhandaata Division
HPPWD, Jhandaata

SCHEDULE OF QUANTITY

6

Name of Work :- C/o PHC Building at Buhar Tehsil Jhandutta Distt.
Bilaspur (H.P.) (SH:- C/o Rain Water Harvesting tank of 25000 litre Capacity.) Deposit work.

Name of Work :- C/o PHC Building at Buhar Tehsil Jhandutta Dist. Bilaspur (H.P.) (SH:- C/o Rain Water Harvesting tank of 25000 litre Capacity.) Deposit work.		Estimated cost:- ₹ 2922288.00		Only	
		Earnest Money:- ₹ 5800.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
		Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto all, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a all lead. All kinds of soil, incidentals, lift up to any height stacking excavated soil up to all leads and lifts clear from the edge of excavation and then returning the stacked soil in fifteen centimetre thick layer when required into plinths, sides of foundation etcetra consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respect.	34.08		Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) mechanically mixed, vibrated and curing complete excluding cost of form work in foundation and plinth including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.53		Per cubic metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.03		Per cubic metre	

7
44

4	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials, tools and machinery with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0				0
a	Walls (any thickness) including attached plasters, buttresses, plinth and string courses etc.	60.29				Per square metre
b	Suspended floors, roofs, landings, balconies and access platform	7.06				Per square metre
5	6 mm cement plaster of mix 1:3 (one cement into three fine sand) including carriage of materials, tools and machinery with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	35.32				Per square metre
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials, tools and machinery with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.41				Per cubic metre
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials, tools and machinery with in all leads, lifts and other incidentals as per direction of Engineer in Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	844				Per kilogram

8	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gables and similar works including carriage of materials, tools and machinery, with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.4				Per kilogram	
9	Supplying and fixing C.I. cover without frame for manholes 500 mm diameter C.I. cover (medium duty) the weight of the cover to be not less than 58 kg including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1				Each	
10	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement :4 coarse sand) for stop cock, with C. I. surface box 100x100 x75 mm (one hundred into one hundred into seventy five millimeter) (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (one cement into two coarse sand into four graded stone aggregate 20 mm (twenty millimeter) nominal size), if necessary excavation, foundation concrete 1:5:10 (one cement into five fine sand into ten graded stone aggregate 40mm nominal size) and inside plastering with cement mortar 1:3 (one cement into three coarse sand) 12 mm (twelve millimeter) thick, finished with a floating coat of neat cement complete as per standard design With common burnt clay F.P.S.(non modular bricks of class designation 7.5 (seven point five) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6				Each	

SCHEDULE OF QUANTITY

Name of Work :- C/O M/T Chhatyal Bath to Khirishi Jamoi road Km 0/0 to 2/00
(SH:- Balance work along with slab culvert Chhatyal Bath side D/Stream R/wall
at RD 1/907 to 1/913 & U/Stream R/Wall at RD 1/907 to 1/921). Under OTMNP.

Estimated cost:- ₹ 499189.00 **Only**
Earnest Money:- ₹ 10000.00 **Only**
Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	66.34			Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone aggr. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	171.94			Per Cubic Meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	43.88			Per Cubic Meter	

22

4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	66.00			Each	
5	Construction of embankment with approved material obtained from borrow pits within all leads and lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	545.87			Per cubic metre	
Total:-						

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

[Handwritten Signature]

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road Chiknaghat to Kothi via Doon Km 0/0 to 1/500
(SH:- C/O S/7 mtr wide Formation cutting at RD 0/315 to 0/600 & Construction of 900 mm dia HP Culvert at RD 0/610 & 0/710 along with both side wing wall). Under OTMNP

Estimated cost:- ₹ 495538.00 Only
Earnest Money:- ₹ 9900.00 Only
Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification 2014 Clause 302.1603.1, 1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling line dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 305.62 Cubic metre @ Rs. 300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	1833.74			Per Cubic Meter	
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i.e setting out construction of shoring and bracing removal of slumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	82.28			Per Cubic Meter	

7
84

3	Providing and laying cement concrete 1:4:8 (One cement into four sand into eight graded stone aggregate 40mm(Forty millimetre) nominal size) and curing complete including cost of form work in retaining walls/breast walls: as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	3.87				Per cubic metre	
4	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of head walls as per drawings & Technical Specification Clause 1109, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	20.58				Per Cubic Meter	
5	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 900 mm including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	13.25				Per running Meter	
6	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone aggregate 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	62.68				Per Cubic Meter	
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	13.98				Per Cubic Meter	

7/et

8	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	26.00					Each	
Total:-								

Executive Engineer,

Jharkhand Division

HPPWD, Jharkhand



SCHEDULE OF QUANTITY

Name of Work :- Construction of link road Makari to Chanjoti Km 0/0 to 3/00
(SH:- C/O B/Wall at RD 1/600 to 1/622.50) Under BASP Deposit.

Name of Work :- Construction of link road Makari to Chanjoti Km 0/0 to 3/00						
Estimated cost:- ₹ 277854.00						
Only						
Earnest Money:- ₹ 5600.00						
Only						
Time allowed:- Three Month						
Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m All kinds of soil, including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	43.42			Per Cubic Meter	
2	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.					
i)	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc	60.65			Per square Meter	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	52.89			Per Cubic Meter	

4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	42.00	Each	
Total:-				


 Executive Engineer,
 Jharkhand Division
 HPPWD, Jharghata

SCHEDULE OF QUANTITY

Name of Work :- Repair of PHC Building Bheri Tehsil Jhandauta Dist.
Bilaspur (H.P.) Deposit BASP -

Sr. No.	Description of items	Quantity	Estimated cost:- ₹		Earnest Money:- ₹	
			Time allowed:- Three Month			
			Figures	Rate words	Unit	Amount
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge Nominal concrete 1:4:8 or leaner mix (i.e equivalent design mix) including carriage of materials, tools and machinery with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.24			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.24			Per cubic metre	
3	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) 25 mm thick including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	73.91			Per square metre	

7/EE

4	Kota stone slabs 20 mm thick in pieces of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	47.19				Per square metre	
5	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.84				Per square metre	
Total:-							

Executive Engineer,
 Jharkhand Division
 HPPWD, Jharkhand

[Handwritten Signature]
 20/10/2020

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road from GTB road to Nav Durga Mandir Baniya
Km 0/0 to 1/00 (SH:- C/O R/Wall at RD 0/466 to 0/480) Under OTMNP.

Name of Work :- Construction of link road from GTB road to Nav Durga Mandir Baniya Km 0/0 to 1/00 (SH:- C/O R/Wall at RD 0/466 to 0/480) Under OTMNP.						Estimated cost:- ₹ 297857.00		Only
						Earnest Money:- ₹ 6000.00		Only
						Time allowed:- Three Month		
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount		
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth upto a all lead and lift as directed by Engineer-in-charge. All kinds of soil including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	13.62			Per Cubic Meter			
2	Centering and shuttering including strutting, propping etc. and removal of form work for Retaining walls, return walls, walls (any thickness) including attached plasters, buttresses, plinth and string courses fillets, kerbs and steps etc including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	72.68			per square meter			
3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (one cement into five coarse sand into ten graded stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	44.26			Per Cubic Meter			
4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment, wing wall return wall with 100 mm (one hundred millimeter) dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	25.00			Each			
Total:-								

Executive Engineer
Jhansi Division
HPPWD, Jhansi

12

SCHEDULE OF QUANTITY

Name of Work :- M/T on Devi Ka Mod to Kosriyan Boatghat road Km 0/0 to 2/500 (SH:- Maintenance of Pot holes and WBM at RD 1/200 to 1/450)		Estimated cost:- ₹ 102282.00	Only
		Earnest Money:- ₹ 2000.00	Only
Time allowed:- Three Month			

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	398.14			Per Square Meter	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat. 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2.503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	398.14			Per Square Meter	
Total:-						

Executive Engineer,

Jhanderda Division

HPWD, Jhanderda

HPWD, Jhanderda

SCHEDULE OF QUANTITY

Name of Work :- Construction of Kosharian to Jaddu road Km 0/0 to 14/600 (SI:-

Construction of R/wall at RD 10/105 to 10/120). Under OTMNP.

Name of Work :-Construction of Kosharian to Jaddu road Km 0/0 to 14/600 (SH:- Construction of R/wall at RD 10/105 to 10/120), Under OTMNP.		Estimated cost:- ₹ 301131.00		Only	
		Earnest Money:- ₹ 6000.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of Items	Quantity	Rate	Unit	Amount
		Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 (ie setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	27.56		Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	129.24		Per Cubic Meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 (granular material, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	34.50		Per Cubic Meter	
4	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V). 200(H) towards drawing face complete as per HPPWD specification including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	54.00		Each	
Total :-					


 Executive Engineer
 Jhanda Division
 HPPWD, Jhanda

DRAFT SCHEDULE OF QUANTITY

Name of Work :- Construction of Bheri to Kalol road Km 0/0 to 6/0. (SH:- Providing & laying G-III at RD 2/550 to 2/980) .

DRAFT SCHEDULE OF QUANTITIES									
Name of Work :- Construction of Bheri to Kalol road Km 0/0 to 6/0. (SH:- Providing & laying G-III at RD 2/550 to 2/980) .									
		Estimated cost:- ₹		96213.00		Only			
		Earnest Money:- ₹		1900.00		Only			
		Time allowed:- Three Month							
Sr No	Description of items	Quantity	Rate		Unit	Amount			
			Figures	words					
1	Providing, laying, spreading and compacting, stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KM (equity to one hundred kilowatt) in stages to proper grade and camber, applying and brooming, stone screening to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading -III as per Technical Specification Clause 405, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Mahsana, Toll tax, Sale tax or other taxes imposed by the Government.	103.20			Per Cubic metre				
Total :-									

Executive Engineer,
 Bhambhata Division
 RD/MD Bhambhata


SCHEDULE OF QUANTITY

Name of Work :- Construction of link from Berthin to Badgoan Km 0/0 to 1/00

(SH:- Construction of U-Shape drain at RD 0/00 to 0/100). Under OTMNP.

Estimated cost:- ₹ 75292.00	Only
Earnest Money:- ₹ 1500.00	Only

Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	56.25			Per Cubic Meter	
2	Providing and Laying cement concrete M-10 (Ten) graded crushed stone aggregate, 40mm (forty millimetre) nominal size with minimum cement contents 260kg (two hundred sixty) kilogram, per cubic metre and curring complete, including cost of form work for plain /reinforce concrete in structures like U-shape drain, V- Shape drain, culverts, drains and other structure as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts, shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	23.25			Per Cubic Meter	
Total:-						

Executive Engineer,

Jhandauta Division

HPPWD, Jhandauta

SCHEDULE OF QUANTITY

Name of Work :- Construction of Non Residential building of Sub Division Jhandutta (Old JE Residence) (SH:- Construction of one additional Room.)

Sr. No.	Description of items	Quantity	Estimated cost:- ₹		Time allowed:- Three Month	
			Earnest Money:- ₹		Only	
			Figures	Rate words	Unit	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto all, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a all lead. All kinds of soil, incidentals, lift up to any height stacking excavated soil up to all leads and lifts clear from the edge of excavation and then returning the stacked soil in fifteen centimetre thick layer when required into plinths, sides of foundation etcetra consolidating each deposited layers by ramming and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respect.	13.5			Per cubic metre	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level in 1:4:8 (one Cement into four coarse sand) : into eight graded stone aggregate 40 mm (forty millimeter) nominal size) mechanically mixed, vibrated and curing complete excluding cost of form work in foundation and plinth including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	4.36			Per cubic metre	
3	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0				0

66

a	Foundations, footings, bases for columns	12.96				Per square metre	
b	Lintels, beams, plinth beams, girders, bressumers and cantilevers	35.3				Per square metre	
c	Suspended floors, roofs, landings, balconies and access platform	25.58				Per square metre	
d	Edges of slabs and breaks in floors and walls Under 20 cm wide	19.94				Per running metre	
4 a	Reinforced cement concrete work in beams, suspended floors, roof having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement into one point five coarse sand) into three graded stone aggregate 20 mm (twenty millimeter) nominal size), including cartage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.94				Per cubic metre	
b	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. above plinth level up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement 1:1.5:3 (one cement into one point five coarse sand) : three graded stone aggregate 20 mm (twenty millimeter) nominal size) including cartage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.53				Per cubic metre	
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Mild steel and Medium Tensile steel bars including cartage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2035.15				Per kilogram	

6	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought (framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be put for separately). Sill wood including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	0.12				Per cubic metre	
7	Providing and fixing panelled or paneled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding paneling which will be paid for separately, all complete as per direction of Engineer-in-Charge. Kith seasoned and chemically treated hollock wood 35 mm thick shutters including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.49				Per square metre	
8	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (one point four millimeter) in both directions with wire of dia 0.63 mm (zero point six three millimeter) for doors, windows and clerestory windows with hinges and necessary screws Kith seasoned and chemically treated hollock wood including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.49				Per square metre	
9	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundation and plinth in Cement mortar 1:6 (one cement into six coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	5.94				Per cubic metre	

10	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6 (one cement into six fine sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	93.94				Per square metre	
11	6 mm cement plaster of mix 1:3 (one cement into three fine sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	25.58				Per square metre	
12	Applying priming coat With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.92				Per square metre	
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.92				Per square metre	
14	Dispersing with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	104.86				Per square metre	

15	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm (three hundred into three hundred millimeter) or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimeter) thick Cement Mortar 1:4 (one Cement into four Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three point three kilogram per square meter) including pointing the joints with white cement and matching pigments etc., complete, including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	16.61				Per square metre	
16	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 250x16 mm including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1				Each	
17	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete in 200 X 10 mm (two hundred into ten millimeter) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10				Each	
18	Providing and fixing ISI marked oxidised M.S. handles conforming to IS-4992 with necessary screws etc. complete in 125 mm (one hundred twenty five millimeter) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10				Each	

19	Providing and fixing 150 mm bright finished floor brass door stopper with rubber cushion, necessary brass screws etc. to suit shutter thickness complete including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2				Each	
20	Providing and fixing bright finished brass hard drawn hooks and eyes including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10				Each	
21	Cement plaster skirting up to 30 cm height, with cement mortar 1:3 (1 cement : 3 coarse sand), finished with a floating coat of neat cement, 18 mm thick including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.45				Per square metre	
Total:-							


 Executive Engineer,
 Jhanduta Division
 HPPWD, Jhanduta

17

SCHEDULE OF QUANTITY

NAME OF WORK:- A/R & M/o on MDR -116 Km 0/0 to 31/00 (SH:-Balance work /Repair of pot holes in Km 4/00 to 7/00 , 9/00 to 10/00 & 11/00 to 14/00).

NAME OF WORK:- A/R & M/o on MDR -116 Km 0/0 to 31/00 (SH:-Balance work /Repair of pot holes in Km 4/00 to 7/00 , 9/00 to 10/00 & 11/00 to 14/00) .					Estimated cost:- ₹		499190.00	Only
					Earnest Money:- ₹		10000.00	Only
					Time allowed:- one Months			
Sr. No.	Description of items	Quantity	Rates in		Unit	Amount		
			Figures	words				
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimeter) thick pre-mix carpet and seal coat type B specification Clause 1904.2 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1559.97			Per square metre			
Total:-								

Executive Engineer,
Jhanduta Division,
HPWD, Jhanduta.

SCHEDULE OF QUANTITY

18

Name of Work :- Construction of link road from Mannan to Sidh Mandir Km 0/0 to 1/000 (SH:- C/O R/W all at RD 0/140 to 0/158). 07MAJ

SCHEDULE OF QUANTITY						
Name of Work :- Construction of link road from Mannan to Sidh Mandir Km 0/0 to 1/000 (SH:- C/O R/Wall at RD 0/140 to 0/158). DTMAD		Estimated cost:- ₹ 99902.00		Only		
		Earnest Money:- ₹ 2000.00		Only		
		Time allowed:- Three Month				
Sr. No.	Description of items	Quantity	Figures	Rate words	Unit	Amount
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of abutting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	16.06			Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone agg. 40 mm nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	43.82			Per Cubic Meter	
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment, wing wall, return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification. including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	10.00			Each	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	9.72			Per Cubic Meter	
Total:-						


 Executive Engineer
 Jhandautta Division
 HPPWD, Jhandautta

191

SCHEDULE OF QUANTITY

Name of Work :- R/R damages on B.V.C. road Km 0/0 to 20/00 (SH:- Hiring of Tractor with Trolly including Labour Hiring)

Name of Work :- R/R damages on B.V.C. road Km 0/0 to 20/00 (SH:- Hiring of Tractor with Trolly including Labour Hiring)						
Sr. No.	Description of items	Quantity	Estimated cost:- ₹		Unit	Amount
			Earnest Money:- ₹			
			Time allowed:- Three Month			
		Figures	Rate words			Only
1	Hiring of tractor with trolly for Shifting of materials cartage/ shifting of excavated material or any type of materials as per requirement including P.O.L. charges and other establishment required at site i.e. driver cleaner and other staff and other incidental charges complete as per the direction of Engineer-in-Charge.	30.00			Per day	
2	Hiring of labour for loading and unloading of material from tractor trolly and clearing of road surface making ready the road surface to repair of pot holes etc as per the direction of Engineer-in-Charge.	169.00			Per day	
Total:-						


Executive Engineer,
 Bhadutta Division
 HPPWD, Bhadutta

SCHEDULE OF QUANTITY

Name of Work :- C/O MDR road (95) Panol Jhanduta Nand Nagraon road Km 0/0 to 21/00 (SH:- C/O 600 mm dia RCC
Hume pipe culvert at RD 9/310 & Laying 450 mm dia Hume pipe for foot path crossing, villages roads & House approaches)
Under MDR.

Estimated cost:- ₹ 272895.00
Earnest Money:- ₹ 5500.00
Time allowed:- Three Month
Only
Only

Sl No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1.06 setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a head of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	147.12			Per Cubic Meter	
2	Providing and laying cement concrete 1:4:8 (One cement into four sand into eight) graded stone aggregate 40mm (Forty millimetre) nominal size) and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification within all leads and lifts and as per the direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	3.42			Per cubic metre	
3	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	40.50			Per Cubic Meter	
4	Providing and laying reinforced cement concrete pipe NP-2 (two) for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one into two) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octy. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	15.00			Per running Meter	
II	450 mm dia (four hundred fifty millimeter)	150.00			Per running Meter	
Total -						

Executive Engineer,
Infrastructure Division,
HPPWD, Bhubaneswar

HPWD, Bhubaneswar

SCHEDULE OF QUANTITY

**Name of Work :- Construction of G.T.B. road Km 0/0 to 25/000 (SIH:- Providing & Laying
C.C. Pavement at RD 24/325 to 24/365). Under OTMNP.**

Name of Work :- Construction of G.T.B. road Km 0/0 to 25/000 (SH:- Providing & Laying C.C. Pavement at RD 24/325 to 24/365). Under OTMNP.		Estimated cost:- ₹ 157531.00		Only	
		Earnest Money:- ₹ 3200.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
			Figures	words	
1	Earth work in excavation for structure as per drawing and technical specification clause 305 I i.e setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	36.00		Per Cubic Meter	
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty) to one hundred kilonewtons static roller in stages to proper grade and camber, applying and brooming, stone screening/grading materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-I as per MORD Technical Specification Clause 405 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	18.00		Per Cubic metre	
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-2 as per Technical Specification Clause 405. By Mechanical Means including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	13.50		Per Cubic metre	
4	Construction of an reinforce plain cement concrete pavement thickness as per design, over a prepared sub base with 43 (forty three) grade cement or any other type as per Clause 1501.2.2 M-30 (thirty) (Grade) coarse and fine aggregates conforming to IS 383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimeter), mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weight batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including leveling the including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	28.10		Per Cubic Meter	
Total:-					


 Executive Engineer
 Industries Division
 H.P.D. Baramulla

SCHEDULE OF QUANTITY

Name of Work :- Improvement of Black Spot on B.J.S.M. road Km 0/0 to 20/00 (SH-C/O B/wall at RD 5/355 to 5/355 with U-shape Drain at RD 5/315 to 5/405). Under OTMNP.

Name of Work :- Improvement of Black Spot on B.J.S.M. road Km 0/0 to 10/00 (SH- C/o B/wall at RD 5/335 to 5/355 with U-shape Drain at RD 5/315 to 5/405), Under OTMNP.									
SCHEDULE OF QUANTITY									
Sr. No.		Description of items	Quantity	Estimated cost:- ₹ 332912.00		Only			
				Earnest Money:- ₹ 6700.00		Only			
Time allowed:- Three Month									
			Figures	Rate	words	Unit	Amount		
1		Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and turning of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. Technical Specification 2014 Clause 302.1603.1, 1603.2, and sorting out useful material for and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machines, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 79.45 Cubic metre @ Rs.300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	476.67				Per Cubic Meter		
2		Earth work in excavation for structure as per drawing and technical specification clause 305.1.1e setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs, dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	63.59				Per Cubic Meter		
3		Providing and laying cement concrete 1:5:10 (one cement five sand ten graded stone agg. 40 mm, nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	47.01				Per Cubic Meter		
4		Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm dia PVC pipe extending through full of width of the structure with slope of (V). 200(1) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	36.00				Each		

5	Providing and Laying cement concrete M-10 (Ten) graded crushed stone aggregate 40mm (forty millimetre) nominal size with minimum cement contents 260kg (two hundred sixty) kilogram, per cubic metre and curing complete including cost of form work for plain/reinforce concrete in structures like U-shape drain, V-Shape drain, culverts, drains and other structure as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curing complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	29.70				Per Cubic Meter	
Total:-							


 Executive Engineer
 Jhandaata Division
 HPPWD, Jhandaata

23

SCHEDULE OF QUANTITY

Name of Work:- Construction of link road Kot to Budeen Km 0/0 to 0/500 (SH:- Providing Grating over U-shape Drain & Construction of U-Shape Drain & PCC Pavement at RD 0/435 to 0/450). Balance

Work. Under SCDP.

Work Under SCDP.					
Sr. No.	Description of items	Quantity	Rate		Amount
			Figures	words	
1	Boulder filling dry hand packed tightly in wire crates vertical bands with sloping face (wire crates to be measured separately) including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	2.03			Per Cubic Meter
2	Providing and Laying cement concrete M-10 (Ten) graded crushed stone aggregate, 40mm (forty millimetre) nominal size with minimum cement contents 266kg (two hundred sixty six) kilogram, per cubic metre and curing complete including cost of form work for plain /reinforce concrete in structures like U-shape drain, V-Shape drain, culverts, drains and other structure as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts, shoring and shattering and curing complete including pumping or hauling out water (surface and sub soil water) up to all depths and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.03			Per Cubic Meter
3	Providing and laying cement concrete 1:1.5:3 (1 cement, 1.5 Sand 3 graded stone aggregate 20 mm nominal size and curing complete excluding cost of form work in Foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	3.73			Per Cubic Meter
4	Providing steel R.S.Js/ built-up steel sections including cutting, welding/riveting, bolting, fixing in position for composite girders with shear connectors complete with painting as per drawing and technical specifications Clause 1205.6 in Steel section including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	11.02			Per quintal
Total:-					

Executive Engineer,

Jhanda Division

HPPWD, Jhanda

24

SCHEDULE OF QUANTITY

Name of Work :- Construction of Dahad Dehwin road Km 0/0 to 3/00. (SH:- C/O B/wall at RD 0/550 to 0/557 & 0/620 to 0/628, 0/643 to 0/650 & Extension of 900 mm dia RCC Hume pipe culvert, U-shape drain and Wing wall). Under OTMNP.

Estimated cost:- ₹ 208429.00	Only
Earnest Money:- ₹ 4200.00	Only
Time allowed:- Three Month	

Sl. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Excavation in earthwork in hilly area all heights and depths, in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side. Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited) as per technical specification clause 1603.1 including carriage and stacking of useful material for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, trimming, filling of unevenness, bludge and finishing of the road to specified dimensions or as directed by the Engineer-in-charge. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	15.00			Per Cubic Meter	
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 the setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	79.98			Per Cubic Meter	
3	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open foundation of Head walls as per drawings & Technical Specification Clause 1109. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	13.59			Per Cubic Meter	
4	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling concrete and masonry work in head walls and parapets clause 1108 in 900 mm. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	2.50			Per running Meter	

24

5	Providing and laying cement concrete (1:5:10) (one cement, five sand, ten graded stone agg. 40 mm nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	65.24					Per Cubic Meter	
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.25					Per Cubic Meter	
7	Providing weep holes in brick masonry / stone masonry, plain / reinforced concrete abutment, wing wall return wall with 100 mm dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	58.00					Each	
Total:-								


 Executive Engineer,
 Jhandaufa Division
 HPPWD, Jhandaufa

25

SCHEDULE OF QUANTITY

Name of Work :- Construction of Fencing / Boundary wall H.E.C. Kalol
Horticulture Building at kalol. Deposit work (BASP).

Name of Work :- Construction of Fencing / Boundery wall H.E.C. Kalol Horticulture Building at kalol. Deposit work (BASP).		Estimated cost:- ₹ 194899.00		Only	
		Earnest Money:- ₹ 3900.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
		Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ranning of bottoms, lift upto all, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a all lead. All kinds of soil, incidentals, lift up to any height stacking excavated soil up to all leads and lifts clear from the edge of excavation and then returning the stacked soil in fifteen centimetre thick layer when required into plinths, sides of foundation etcetra consolidating each deposited layers by ranning and watering and then disposing of all surplus excavated earth to the disposal point within all leads and lifts complete in all respect.	16.00		Per cubic metre	
2	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana - Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.				
a	Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	62.00		Per square metre	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) mechanically mixed, vibrated and curing complete excluding cost of form work in foundation and plinth including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana - Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00		Per cubic metre	

4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (one cement into six coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.05				Per square metre	
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level (Cement mortar 1:4 (1 cement : 4 coarse sand) including carriage of materials, tools and machinery with in all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.45				Per square metre	
Total:-							


 Executive Engineer
 Bhadanta Division
 HPPW.D, Bhadrak

SCHEDULE OF QUANTITY

Name of Work :- Construction of Berthin Chhat Dabiri road Km 0/0 to 2/00 (SH:-
Construction of CC Pavement at RD 1/050 to 1/100), Under OTMNP.

Estimated cost:- ₹ 357012.00

Earnest Money:- ₹ 7100.00

Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	56.25			Per cubic metre	
2	Preparation and consolidation of sub grade with power road roller of 8 to 12 tonne capacity after excavating earth to an average of 22.5 cm depth, dressing to camber and consolidating with road roller including making good the undulations etc. and re-rolling the sub grade and disposal of surplus earthwork lead upto 50 metres including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	225.00			Per square metre	
3	Supplying and stacking at site 63 mm to 45 mm size stone aggregate including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	29.93			Per cubic metre	
4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	22.50			Per cubic metre	
5	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete including cartage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	45.50			Per cubic metre	
Total -						

27 **SCHEDULE OF QUANTITY**

name of Work :- Construction of link road Bharoli Kallan to Jhanjoo Via Gurnadi
 in 6/0 to 8/00 (SH); C/O 6.00 mtr span R.C.C. Slab Culvert U/S & D/S Side wing wall
 RD 0/073 to 0/077 (U/S) & RD 0/073 to 0/083 (D/S). *OT m/m*

Sl. No.	Description of items	Estimated cost:- ₹ 442045.00				Only
		Earnest Money:- ₹ 8800.00				Only
		Time allowed:- Three Month				
		Quantity	Figures	Rate words	Unit	Amount
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shooting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	18.42			Per Cubic Meter	
2	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.					
3	Providing and laying cement concrete 1:3:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centing & shuttering in foundation and plinth including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	74.00			Per Cubic Meter	

4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	113.05				Per Cubic Meter	
5	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	22.00				Each	
Total:-							

Executive Engineer,
Jhanda Division
HPPWD, Jhanda

22

SCHEDULE OF QUANTITY

Name of work :- Construction of link road to Harizan Basti Mekhwin Km 0/0 to 1/0
(SH:- C/o V-shape Drain at RD 0/0 to 0/380). Under OTMNP.

Estimated cost:- ₹ 475442.00 Only
Earnest Money:- ₹ 9500.00 Only
Time allowed:- Three Month

Sl. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:3:6 (one cement into three coarse sand) into six graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of material with in all leads and lifts, shoring and shuttering and curring complete including pumping or hauling out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material, tools equipment safety measures and other including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	68.00			Per Cubic Meter	
Total:-						

Executive Engineer
Jhandauta Division
HPPW/D, Jhandauta

SCHEDULE OF QUANTITY

**Name of Work :- Construction of Boundary wall, Steps & Badminton Court
to Govt. SSS Berthin Distt. Bilaspur. Deposit Work.**

Estimated cost:- ₹ 497038.00 Only
Earnest Money:- ₹ 9900.00 Only

Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Figures	Rate	Unit	Amount
			words			
1	Demolition of brick work below G.L. upto all depth including stacking of serviceable materials and disposal of un-serviceable materials within all lead in cement mortar including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.40			Per Cubic Meter	
2	Demolition of rubble stone masonry in cement mortar above ground level upto all floor level including stacking of serviceable materials and disposal of un-serviceable materials including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, heavy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	17.50			Per Cubic Meter	
3	Earth work in excavation for structure as per drawing and technical specification clause 305.1 the setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a all lead , dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	27.93			Per Cubic Meter	

4	Providing and Laying cement concrete M-10 (Ten) graded crushed stone aggregate, 40mm (forty millimetre) nominal size with minimum cement contents 260 kg (two hundred sixty) kilogram, per cubic metre and curing complete , including cost of form work for plain /reinforce concrete in structures like U-shape drain, V- Shape drain, culverts, drains and other structure as per drawing and MORD technical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curing complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge.The rate includes, octroi, royalty, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.45				Per Cubic Meter	
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 R.C.C grade M -20 1:2:4 including and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge.The rate includes, octroi, royalty, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1.00				Per Cubic Meter	
6	Supplying, fitting and placing TMT bar reinforcement in foundation complete as per drawings and technical specifications Clauses 1000 and 1202 including and carriage of machinery, material ,tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge.The rate includes, octroi, royalty, Malkhana , Toll tax , Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.00				Per tonne	

7	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in gratings, framed guard bars, ladders, railing brackets and similar works, including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	2.50					Per quantity	
8	Cement concrete flooring 1:2:4 (one cement into two sand into four graded stone aggregate 20 mm (twenty millimeter) nominal size) laid in one layer finished with a floating coat of neat Cement 50 mm (fifty millimeter) thick, including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.12					Per square metre	
9	linofilm covering to floor, plain or coloured laid with an approved adhesive on sub floor including cutting and fixing complete to sub floor including damp proofing treatment (damp proofing treatment to be measured separately for payment.) 3.2 mm (three point two millimeter) thick, including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in-Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	87.12					Per square metre	

10	Brick work using common burnt clay building bricks in foundation and plinth in Cement Mortar 1:6 (one Cement : six Sand) Second Class Bricks including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.26				Per Cubic Meter	
11	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arisies, internal rounded angles, chatters and/or rounded angles not exceeding 80 mm (eighty millimeter) in girth and finished even and smooth. Cement Mortar 1:5 (one Cement into five Sand), including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	188.23				Per square metre	
12	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equivalent on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth complete, including and carriage of machinery, material, tools equipment safety measures and other incidentals as per the direction of Engineer-in Charge. The rate includes, octroi, royalty Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	188.23				Per square metre	
Total:-							

Executive Engineer,

Jhandauta Division

HPPWD, Jhandauta

35 **SCHEDULE OF QUANTITY**

Name of Work :- Construction of link road from Dahad to Dehwin road Km 0/0 to 3/0 (SH:- Construction of R/walls at RD 1/673 to 1/683 & 1/706 to 1/724) Under OTMNP.

Estimated cost:- ₹ 492782.00 Only
Earnest Money:- ₹ 9900.00 Only

Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 w/ setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	128.64			Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement , five sand, ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	210.36			Per Cubic Meter	
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V) 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	46.00			Each	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	46.32			Per Cubic Meter	
5	Construction of embankment with approved material obtained from borrow pits within all leads and lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	40.80			Per cubic metre	
Total :-						

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road from Dahad to Dehwin road Km 0/0 to 3/0 (SH:- Construction of R/walls at RD 1/578 to 1/586, 1/615 to 1/628, 1/633 to 1/645 & 1/702 to 1/727) Under OTMNP.

Estimated cost:- ₹ 448908.00

Earnest Money:- ₹ 9000.00

Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	Words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 the setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	74.61			Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	186.03			Per Cubic Meter	
3	Providing weep holes in brick masonry/stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V) : 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	77.00			Each	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	54.42			Per Cubic Meter	
5	Construction of embankment with approved material obtained from borrow pits, within all leads and lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract	49.82			Per cubic metre	
Total :-						

Executive Engineer,
Banshalwa Division
HPPWD, Banshalwa

32

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road from Bahad to Delhiwin road Km 0/0 to 3/0 (SH:- Construction of R/Walls at RD 1/591 to 1/596, 1/905 to 1/940 & 1/974 to 1/998) Under OTMNP.

Sr. No.	Description of items	Quantity	Estimated cost :- ₹ 42885.00		Only
			Earnest Money :- ₹ 8600.00		Only
			Time allowed :- Three Month	Rate	Unit
		Figures	words		Amount
1	Each work in excavation for structure as per drawing and technical specification clause 305.1 i.e setting out construction of shorting and bracing removal of stumps and other deteriorous material and disposal upto a head of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	81.68		Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone age: 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	156.99		Per Cubic Meter	
3	Providing weep holes in brick masonry/stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe extending through full of width of the structure with slope of (V) : 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	100.00		Each	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	122.94		Per Cubic Meter	
5	Construction of embankment with approved material obtained from borrow pits within all leads and lifts, transporting to site, spreading, grading to required slope and compacting to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	51.60		Per cubic metre	
Total :-					

33 SCHEDULE OF QUANTITY

Name of Work :- Construction of link road to village Sargat Km 0/0 to 0/450 (SH:- C/O R/wall at RD 0/178 to 0/198). Under OTMNP.

Name of Work :- Construction of link road to village Sargal Km 0/0 to 0/450 (SH:- C/O R/wall at RD 0/178 to 0/198). Under OTMNP.		Estimated cost:- ₹ 177680.00		Only		
		Earnest Money:- ₹ 3600.00		Only		
Time allowed:- One Month						
Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 304.1 i.e setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	17.37			Per Cubic Meter	
2	Providing and laying cement concrete 1:5:10 (one cement, five sand, ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	66.58			Per Cubic Meter	
3	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment, wing wall return wall with 100 mm. dia PVC pipe extending through full of width of the structure with slope of (V)- 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	29.00			Each	
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	35.40			Per Cubic Meter	
5	Construction of embankment with approved material obtained from borrow pits, within all leads and lifts, transporting to site, spreading, grading to required slope and compaction to meet requirement of table 300.1 and 300.2 as per technical specification clause 301.5 and including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	75.00			Per cubic metre	
Total:-						


 Executive Engineer
 Jhandauta Division
 HPPWD, Jhandauta

SCHEDULE OF QUANTITY

Name of Work :-C/o Dholag to Malroun road Km 0/0 to 4/500 (SH:- C/o D/S T/Wall & W/wall at RD 2/915 to 2/985). Under OTMNP.

Name of Work :-C/o Dholag to Mafroun road Km 0/0 to 4/500 (SH:- C/o D/S T/Wall & W/wall at RD 2/915 to 2/985). Under OTMNP.		Estimated cost:- ₹ 251608.00		Only	
		Earnest Money:- ₹ 5000.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
			Figures words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shorting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material . including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	63.13		Per Cubic Meter	
2	Providing and laying concrete for plain/reinforced cement concrete 1:4:8 (One cement isto four sand isto eight graded stone aggregate 25 mm.(twenty five millimetre) nominal size) in open foundation and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification clause 802, 803, 1202 & 1203 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	2.02		Per cubic metre	
3	Plain Cement Concrete M10 (1:3:6 nominal mix) in levelling course below open oundation of Head walls as per drawings & Technical Specification Clause 1109, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	17.91		Per Cubic Meter	
4	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	83.43		Per Cubic Meter	

5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	17.04				Per Cubic Meter	
6	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	22.00				Each	
Total:-							


 Executive Engineer,
 Jhandaata Division
 HPPWD, Jhandaata

SCHEDULE OF QUANTITY

Name of Work :- A/R & M/O Mallari to Kallar road km 0/0 to 6/0 (SH:- Repair of Pot holes in km 4/0 to 5/435)

Name of Work :- A/R & M/O Mallari to Kallar road km 0/0 to 6/0 (SH:- Repair of Pot holes in km 4/0 to 5/435)		Estimated cost:- ₹ 93344.00		Only	
		Earnest Money:- ₹ 1900.00		Only	
		Time allowed:- Three Month			
Sr. No.	Description of items	Quantity	Rate	Unit	Amount
			Figures	words	
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and raveling as per technical specification Clause 1906 including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	272.75		Per Square Meter	
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	409.10		Per Square Meter	
Total:-					

Executive Engineer,
Jhandaulla Division
HPPWD, Jhandaulla

36

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road Bala to Lower Bala Km 0/0 to 1/160
 SH:- C/O 900 mm dia Hume pipe culvert at RD 0/810, 0/870, C/o B Wall RD 0/620
 to 0/630 , C/o R/wall at RD 1/140 to 1/160 & P/L soling G-1 0/040 to 0/205, G-II
 0/040 to 0/475). Under SCDP.

Estimated cost:- ₹ 449893.00 Only
 Earnest Money:- ₹ 9000.00 Only
 Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shooting and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	104.65			Per Cubic Meter	
2	Providing and laying cement concrete 1:4:8 (One cement into four sand into eight graded stone aggregate 40mm. (Forty millimetre) nominal size) and curing complete including cost of form work in retaining walls/breast walls, as per HPPWD specification within all leads and lifts and as per the direction of Engineer-in-charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	5.09			Per cubic metre	
3	Providing and laying cement concrete mechanically mixed and vibrated 1:3:6 (one cement : three sand : six graded crushed stone aggregate 40 mm. (forty millimetre) nominal size) as per drawing and technical specification clause 802, 803, 1202 and 1203 including cost of form work and curing complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes, octroi, Malkana , Toll tax , Goods & Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.71			Per Cubic Meter	
4	Providing and laying reinforced cement concrete pipe NP 2 (Two) for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 in 900 mm including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	12.50			Per running Meter	

1-EE

5	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone agg. 40 mm nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	84.05				Per Cubic Meter	
6	Providing weep holes in brick masonry /stone masonry, plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V) : 20(H) towards drawing face complete as per HPPWD specification including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	66.00				Each	
7	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry. Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	8.10				Per Cubic Meter	
8	Preparation of sub-grade by dressing to camber (Earth work for the cutting involved for sub-grade to be measured and paid for separately) depending upon the classification of soil complete as per HPPWD, Specification as per direction of Engineer-in-Charge, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive, octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	552.75				Per square metre	
9	Consolidation of sub-grade with road roller including making good the undulation etcetera with earth or quarry soil etcetera and re-rolling the sub-grade completed as per HPPWD, specification as per direction of Engineer-in-Charge, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive , octroi, royalty Malkhana, Toll tax, Sale tax or other taxes imposed by the Government.	552.75				Per square metre	
10	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty - one hundred kilonewton) static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-I as per Technical Specification Clause 405 By Mechanical Means, including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge. The rates are inclusive , octroi, royalty Malkhana, Toll tax , Sale tax or other taxes imposed by the Government.	55.27				Per Cubic metre	

7/18

11	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty + one hundred kilonewton) static roller in stages to proper grade and camber, applying and brooming, crushable screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-II as per Technical Specification Clause 405 By Mechanical Means including carriage of material with in all leads and lifts and other incidental as per the direction of Engineer-in-Charge The rates are inclusive + octroi, royalty Malkhana , Toll tax , Sale tax or other taxes imposed by the Government.	99.50				Per Cubic metre	
Total:-							


 Executive Engineer,
 Jhandutta Division
 HPPWD, Jhandutta

37

SCHEDULE OF QUANTITY

Name of Work :- Construction of link road to house of Hakam Singh Km 0/0 to 0/250 (SH:-Construction of cement Concrete Pavement , Stone Soling at RD 0/157 to 0/250) Under Deposit Work.

Estimated cost:- ₹ 185055.00 Only
 Earnest Money:- ₹ 3700.00 Only
 Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Providing and laying stone soling properly handpacked filling intersices with Kharaia stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification 100 mm spread thickness (Finished work including materials and labour) including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	34.88			Per Cubic Meter	
2	Construction of un reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 (forty three) grade cement or any other type as per Clause 1501.2.2 M-30 (thirty) (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimeter) , mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	37.20			Per Cubic Meter	
Total:-						

Executive Engineer,

Jhandutta Division

HPPW&A Jhandutta

38

SCHEDULE OF QUANTITY

Name of work :- Construction of link road to Harizan Basti Mekhwin Km 0/0 to 1/0

(SH:- C/O R/Wall at RD 0/380 to 0/390 & 0/550 to 0/564). Under OTMNP.

Estimated cost:- ₹ 493040.00

Earnest Money:- ₹ 9900.00

Only

Time allowed:- Three Month

Sr. No.	Description of items	Quantity	Rate		Unit	Amount
			Figures	words		
1	Each work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50 (fifty) mtrs. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material in all leads and lifts as per the direction of Engineer-in-Charge. including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	43.04			Per Cubic Meter	
2	Centering and shuttering including strutting, propping etc. and removal of form for Walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	142.62			Per square Meter	
3	Providing and laying cement concrete 1:5:10 (one cement : five sand: ten graded stone aggr. 40 mm. nominal size) and curing complete excluding the cost of form work in foundation and plinth excluding the cost of centring & shuttering in foundation and plinth including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	85.55			Per Cubic Meter	
4	Providing weep holes in brick masonry /stone masonry: plain /reinforced concrete abutment wing wall return wall with 100 mm. dia PVC pipe entering through full of width of the structure with slope of (V): 20(H) towards drawing face complete as per HPPWD specification including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	31.00			Each	

5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1.204.3.8 Granular material, including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract.	11.22				Per Cubic Meter	
Total:-							

Executive Engineer
Bhandara Division
HPPWD, Bhandara