



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW-BSR-E-105/2022-23-
To

- 6605-6614

Dated:- 20/06/2022

The Executive Engineer (IT Cell),
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.

Executive Engineer
Barsar Division
HPPWD Barsar.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Chief Engineer (HZ), H.P.P.W.D., Hamirpur.
3. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
4. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
5. Drawing Branch in this office.
6. Accounts Branch in this office.
7. Supdt of C Branch in this office.
8. Notice Board.

Executive Engineer
Barsar Division
HPPWD Barsar.



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- www.hppwd.gov.in. Email:- ee-bar-hp@nic.in

Phone No:- 01972-288041


Fax No. 01972-288041.

NOTICE INVITING TENDER.

Sealed item rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **28.06.2022 up to 10.30 A.M.** and same will be opened on the same day at 11.00 A.M. in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **25.06.2022 upto 4.00 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **27.06.2022** during office hours till **1.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period
1	Restoration of Rain Damages on Jalari Galore Salauni Bijhari Deotsidh Road Km. 0/00 to 30/00. (SH:- P/L Interlocking Concrete Block Pavement at RD. 16/560 to 16/630 and 16/900 to 16/956).	Rs. 4,91,410.00 Only	Rs. 9,900.00 Only	One Month
2	A/R & M/O on HPPWD Divisional Office Building at Barsar and Sub Divisional Office Building at Dhaneta. (SH:- P/F Split A.C. 1.5 Ton Capacity).	Rs. 4,32,000.00 Only	Rs. 8,700.00 Only	One Month
3	Restoration of Rain Damages on Kangoo Dhaneta Road Km. 0/00 to 6/00. (SH:- P/L Interlocking Concrete Block Pavement at RD. 0/100 to 0/200 and 5/500 to 5/526).	Rs. 4,90,764.00 Only	Rs. 9,900.00 Only	One Month
4.	A/R & M/O P.W.D. Colony at Barsar. (SH:- P/F Almirah at Type-III Quarter and Type-IV Quarter).	Rs. 4,97,944.00 Only	Rs. 10,000.00 Only	Two Months
5.	A/R & M/O Divisional Office Building Barsar (Mehre). (SH:- P/F Steel Railing).	Rs. 4,96,075.00 Only	Rs. 10,000.00 Only	One Month
6	A/R & M/O on HPPWD Divisional Office Building at Barsar & Sub Divisional Office Building at Barsar. (SH:-P/F Split A.C 1.5 Ton Capacity).	Rs. 4,32,000.00 Only	Rs. 8,700.00 Only	One Month
7	Restoration of Rain Damages on Kango Dhanoa Road Km. 0/00 to 5/00 & Kahi Di Bhal Khatrod Panyali Jattan Road Km. 2/00 to 5/00. (SH:- Removal of Slips, Maintenance of Drain & Maintenance of Earthen Shoulder in Between Km. 0/00 to 5/00 and 2/00 to 5/00 Respectively).	Rs. 3,42,511.00 Only	Rs. 6,900.00 Only	One Month
8	Restoration of Rain Damages on Link Road to Village Hathol Km. 0/00 to 6/00 & Jhareri Sanahi Harماسanda Road Km. 0/00 to 3/00. (SH:- Removal of Land Slide Slips, Maintenance of Drain and Maintenance of Earthen Shoulder in Between Km 0/00 to 6/00, 0/00 to 3/00, 0/00 to 3/00 Respectively).	Rs. 2,63,211.00 Only	Rs. 5,300.00 Only	One Month

HIM SUCHANA AVAM JAN SAMPARK.


 Executive Engineer
 Barsar Division
 HPPWD Barsar.


On behalf of Governor of Himachal Pradesh.



CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No PW-BSR-E-105/2022-23-

6605-6614 dated 20/06/2022


Executive Engineer
Barsar Division
HPPWD Barsar.

Schedule of quantity

Name of work:-Restoration of rain damages on Jalari Galore Salouni bijhari Deotsidh road Km 0/00 to 30/00
(SH:- P/L intelocking concrete block Pavement at Rd 16/560 to 16/630 & 16/900 to 16/956)

Job No :- 1

Estimated Cost Rs:-491410 .00

Earnest Money Rs:- 9900.00

Time Limit :- one Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	55.44	Cubic metre			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	50.40	Cubic metre			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can prescribe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.08	Cubic metre			Per Cubic Metre	

4	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 80 mm(Eighty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modern, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	504.00	Square metre			Per square Metre	
						Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity

Name of work:- A/R & M/O on HPPWD Divisional office building at Barsar & Sub Divisional office building at Dhaneta
(SH:- P/F Split AC 1.5 Ton capacity)

Job No :- 2
Estimated Cost Rs:-432000 .00
Earnest Money Rs:- 8700.00
Time Limit :- one Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Numbers	Figure	words			
1	Providing and fixing split AC 3 star (Three Star) 1.5 (one point five) ton capacity cold inverter AC including fixing charge & electrical fitting including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	8.00				Each	
						Total:	



Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:-Restoration of rain damages on Kangoo Dhanoa road Km 0/00 to 6/00

(SH:- P/L intelocking concrete block Pavement at Rd 0/100 to 0/200 & 5/500 to 5/526)

Job No :- 3

Estimated Cost Rs:-490764 .00

Earnest Money Rs:- 9900.00

Time Limit :- one Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	50.40			Per Cubic Metre	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	50.40			Per Cubic Metre	
3	Providing and laying mechanically mixed and vibrated plain / reinforced cement concrete standard design mixed two obtain minimum can presibe strength of M-25(M-twenty five) with nominal size using minimum cement contents of 400kg (Four hundred kilogram) per cubic metre graded crushed stone aggregate 20mm (twenty millimeter) nominal size for plain/reinforcement concrete in open foundations complete upto any height including form work with M.S plate complete as per drawing and technical specifications clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.08			Per Cubic Metre	

4	Providing and laying of inter locking concrete paver block vibro compacted upto M-50 (M-Fifty) grade having thickness 80 mm(Eighty millimeter) including border or karb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modern, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	504.00	Square metre				Per square Metre	
							Total:-	



Executive Engineer
Barsar Division
HPPWD Barsar



Schedule of quantity

Name of work:- A/R &M/O P.W.D colony at Barsar

(SH:- P/F Amirah at Type-III and Type-IV quarter)

Job No- 4

Estimated cost Rs:- 497944.00

Earnest money Rs:- 10000 .00

Time Limit :- Two Month

Sr.No	Discription of item	Quantity	Unit	Rate inclusive all taxes i/c G.S.T		Amount
				Figures	words	
1	Providing and fixing cup board shutters 25 mm (twenty five millimetre) thick, with Pre-laminated flat pressed three layer particle board or graded wood particle board IS: 12823 marked, exterior grade (Grade I Type II), having one side decorative lamination and other side balancing lamination, including IInd class teak wood lipping of 25 mm (twenty five millimetre) wide x12 mm(twelve millimetre) thick with necessary screws and bright finished stainless steel piano hinges, complete as per direction of the Engineer-in-Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	111.80	square metre			Per square metre
2	Providing and fixing 12mm(twelve millimetre) thick commercial ply conforming to IS : 1328 BWR type plain lining with necessary screws/nuts & bolts/ nails, including a coat of approved primer on one face, and fixed on wooden /steel frame work, complete as per direction of Engineer-in- charge (Frame work shall be paid for separately).including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	46.80	square metre			Per square metre
3	Providing and fixing 1mm(one millimetre) decorative high pressure laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS : 2046 Type S, including cost of adhesive of approved quality..including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	111.80	square metre			Per square metre
4	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :150x10mm(one hundred fifty into ten millimetre) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	26.00	Numbers			Each
5	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100mm (one hundred millimetre) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	26.00	Numbers			Each

6	Providing and fixing 150mm (one hundred fifty millimetre) bright finished brass hasp and staple (safety type) with necessary screws etc. complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	26.00	Numbers		Each
7	Providing and fixing Triple strip vertical type magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etc. complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	26.00	Numbers		Each
8	Providing and fixing 50 mm bright finished brass cup board or wardrobe knob of approved quality with necessary screws including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	40.00	Numbers		Each
9	Providing and fixing 65 mm (sixty five millimetre) special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etc. complete as per direction of Engineer-in-charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	26.00	Numbers		Each
10	Providing and fixing 25 mm (twenty five millimetre) dia chromium plated brass curtain rod having wall thickness of 1.25mm (one point twenty five millimetre) with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete as per direction of Engineer-in-charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	40.00	Running metre		Per running metre
11	Providing and fixing bright finished brass helical door spring (superior quality) as per direction of Engineer-in-charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	5.00	Numbers		Each
12	Providing and fixing 75x63x4 mm (ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade with necessary screws etc. complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	26.00	Numbers		Each
				Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Schedule of quantity
Name of work:-A/R & M/O Divisional office building at Barsar (Mehre)
(SH:- P/F Steel railing)

Job No :- 5
Estimated Cost Rs:-496075 .00
Earnest Money Rs:- 10000.00
Time Limit :- one Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	162.50 Cubic metre		Per Cubic Metre	
2	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802,803,1202&1203 as per direction of Engineer-in- Charge . including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	58.50 cubic metre		Per Cubic Metre	
3	Providing and laying cement concrete 1:2 :4 (One cement : two Sand: four graded /crushed stone aggregate) 20mm (twenty millimeter nominal size) for plain / reinforcement concrete in open foundation complete including cost of form work steel plate as per drawing and technical specification clause No 802, 803, 1202 &1204 including entire carriage of material in all leads and lifts. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	6.30 cubic metre		Per Cubic Metre	

4	Providing and laying 20mm (twenty millimeters) thick cement plaster in single coat on the rough side of brick concrete/stone walls for interior plastering upto all floor levels including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (Eighty millimeters) in girth and finished even and smooth in cement mortar 1:5(One cement : five sand) and curing complete as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	84.00 square metre			per square metre	
5	White washing with lime on undecorated wall surfaces two coats to give an even shade including thoroughly brooming the surface to remove all dirt dust mortar dirt and other foreign matter. including carriage of materials within all leads, lifts and other incidental, or as directed by the Engineer-in-Charge. The rate including Royalty, Malkana, Octroi, Toll Tax , GST or any other taxes imposed by the Government	84.00 square metre			per square metre	
6	Steel work welded in built up section made of Tata Jindal, Bhushan Industries , trusses and framed work including cutting , hoisting fixing in position and applying a priming coat of red lead paint in grating framed guards bars, ladders railing brackets and similar work upto any height including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	40.59 quintal			Per quintal	
					Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar

Name of work:- A/R & M/O on HPPWD Divisional office building at Barsar & Sub Divisional office building at Barsar
(SH:- P/F Split AC 1.5 Ton capacity)

Schedule of quantity

Job No :- 6

Estimated Cost Rs:-432200 .00

Earnest Money Rs:- 8700.00

Time Limit :- one Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T	Unit	Amount
		Numbers	Words			
1	Providing and fixing split AC 3 star (Three Star) 1.5 (one point five) ton capacity cold inverter AC including fixing charge & electrical fitting including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	8.00			Each	
					Total:-	


Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:- Restoration of rain damages on Kangoo Dhanoa road Km 0/00 to 5/00 & Kahi Di Bhal Khatrod Panyali Jattan road Km 2/00 to 5/00

Job No:- 7

Estimated Cost Rs:-342511.00

Earnest Money Rs:-6900.00

Time Limit :- One Month

(SH):- Removal of slips, Maintenance of drain & maintenance of earthen shoulder in between Km 0/00 to 5/00 & 2/00 to 5/00 respectively)

Sr. No	Description of item	Quantity		Figure	Rate inclusive all taxes i/c G.S.T		Unit	Amount
					words			
1	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slops and disposal all marital upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	369.64	cubic metre				Per Cubic Metre	
2	Clearing and grubbing road land clearing and grubbing road land including uprooting wild vegetation grass, bushes, shrubs, saplings and trees of grith upto 300mm (three hundred millimetre) removal of stumps of such trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned , upto a lead of 1000 metre(one thousand metre) including removal and disposal of top organic soil not exceeding 150mm(one hundred millimetre) in thickness as per Technical Specification Clause 201 including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	47700.00	Square metre				Per Cubic Metre	
3	Maintenance of earthen shoulder (filling with fresh slected soil making up less of material / irregutations on shoulder in design level by adding fresh approved selected soil and compacting it with appropriat equipment OMC upto a lead of 1000mtrs as per including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, malkana ,toll tax, GST or other taxes imposed by the Government .	7780.00	Square metre				Per square Metre	
4	Maintenance of Drain :- Maintenance of drain including erosion, repair clearing, cleaning reshaping regarding deeding of side drain as well as catch water drain as per technical specification clause No 1907 including carriage of material and equipments in all leads and lifts with all mode of transport and as per the direction of Engineer-in- Charge. including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	28000.00	Running metre				Per running Metre	
							Total-	

(Signature)

Executive Engineer
Barsar Division
HPPWD Barsar

Schedule of quantity

Name of work:- Restoration of rain damages on link road to village Hathol Km 0/00 to 0/600 & Jhareri Sanahi Bharyal road Km 0/00 to 3/00
& Jhareri Sanahi Harmasanda road Km 0/00 to 3/00 (SH):- Removal of land slide slips, Maintenance of drain & maintenance of earthen shoulder in between Km 0/00 to 0/600, 0/00 to 3/00 & 0/00 to 3/00 respectively)

Job No:- 8

Estimated Cost Rs:-263211.00

Earnest Money Rs:-5300.00

Time Limit :- One Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Removal of land slide in hilly area in ordinary rock not requiring by mechanical means including cutting and dumping of slops and disposal all marital upto any leads and lifts as per technical specification under clause 302.35 including dressing of grass from berms . including entire carriage,of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	600.32	cubic metre			Per Cubic Metre	
3	Maintenance of earthen shoulder (filling with fresh slected soil making up less of material / irregutations on shoulder in design level by adding fresh approved selected soil and compacting it with appropriat equipment OMC upto a lead of 1000mtrs as per including carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government .	8265.00	Square metre			Per square Metre	
4	Maintenance of Drain :- Maintenance of drain including erosion, repair clearing , cleaning reshaping regarding deeding of side drain as well as catch water drain as per technical specification clause No 1907 including carriage of material and equipments in all leads and lifts with all mode of transport and as per the direction of Engineer-in- Charge. including entire carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	30000.00	Running metre			Per running Metre	
						Total:-	


 Executive Engineer
 Barsar Division
 HPPWD Barsar